



2021 2022

Sheffield Shield

Playing Conditions

This page has been left blank

# **The Preamble – The Spirit of Cricket**

Cricket owes much of its appeal and enjoyment to the fact that it should be played not only according to the Laws, but also within the Spirit of Cricket.

The major responsibility for ensuring fair play rests with the captains, but extends to all players, match officials and, especially in junior cricket, teachers, coaches and parents.

Respect is central to the Spirit of Cricket.

Respect your captain, team-mates, opponents and the authority of the umpires.

Play hard and play fair.

Accept the umpire's decision.

Create a positive atmosphere by your own conduct, and encourage others to do likewise.

Show self-discipline, even when things go against you.

Congratulate the opposition on their successes, and enjoy those of your own team.

Thank the officials and your opposition at the end of the match, whatever the result.

Cricket is an exciting game that encourages leadership, friendship and teamwork, which brings together people from different nationalities, cultures and religions, especially when played within the Spirit of Cricket.

# Welcome to the 2021-22 edition of the Cricket Australia Playing Handbook.

This handbook draws together the main regulations that govern players, support personnel and officials who participate in cricket competitions played under the control and auspices of Cricket Australia.

Both the Playing Conditions and the Cricket Australia Codes and Policies are intended to regulate Australian cricket so that everyone involved in the sport can understand and uphold the unique spirit of cricket.

It is important to Cricket Australia that this Handbook is a resource that is relevant so, if there is any useful information missing from the handbook or any details that have changed since publication, please send an email to [integrity@cricket.com.au](mailto:integrity@cricket.com.au) and Cricket Australia will make any necessary updates.

Cricket Australia also urges you to visit the Rules and Regulations section of the [www.cricketaustralia.com.au](http://www.cricketaustralia.com.au) website as, over the next twelve months, some of the regulations contained within this handbook may change.

See It? Hear It? Report It!

Corruption, doping and other improper conduct have no place in cricket. If you see or hear something that threatens the integrity of the game you should report it to Cricket Australia's Integrity Unit. All information shared will assist in identifying and eliminating threats to the integrity of cricket.

There are a number of ways you can confidentially report integrity risks, including via:

The Cricket Integrity Hotline: 1300 FAIR GAME (1300 3247 4263)

Email: [integrity@cricket.com.au](mailto:integrity@cricket.com.au)  
[anti-corruption@cricket.com.au](mailto:anti-corruption@cricket.com.au)  
[anti-doping@cricket.com.au](mailto:anti-doping@cricket.com.au)

# Table of Contents

|    |  |    |
|----|--|----|
| 1  | THE PLAYERS .....                                  | 5  |
| 2  | THE UMPIRES .....                                  | 7  |
| 3  | THE SCORERS.....                                   | 14 |
| 4  | THE BALL.....                                      | 15 |
| 5  | THE BAT .....                                      | 16 |
| 6  | THE PITCH.....                                     | 18 |
| 7  | THE CREASES .....                                  | 21 |
| 8  | THE WICKETS .....                                  | 22 |
| 9  | PREPARATION AND MAINTENANCE OF THE PLAYING AREA .. | 23 |
| 10 | COVERING THE PITCH .....                           | 26 |
| 11 | INTERVALS.....                                     | 27 |
| 12 | START OF PLAY; CESSATION OF PLAY .....             | 32 |
| 13 | INNINGS .....                                      | 42 |
| 14 | THE FOLLOW-ON.....                                 | 43 |
| 15 | DECLARATION AND FORFEITURE .....                   | 44 |
| 16 | THE RESULT .....                                   | 44 |
| 17 | THE OVER .....                                     | 52 |
| 18 | SCORING RUNS.....                                  | 54 |
| 19 | BOUNDARIES .....                                   | 58 |
| 20 | DEAD BALL .....                                    | 62 |
| 21 | NO BALL.....                                       | 65 |
| 22 | WIDE BALL .....                                    | 69 |
| 23 | BYE AND LEG BYE .....                              | 71 |
| 24 | FIELDER'S ABSENCE; SUBSTITUTES .....               | 72 |
| 25 | BATSMAN'S INNINGS .....                            | 75 |
| 26 | PRACTICE ON THE FIELD.....                         | 79 |
| 27 | THE WICKET-KEEPER.....                             | 81 |
| 28 | THE FIELDER .....                                  | 83 |
| 29 | THE WICKET IS DOWN.....                            | 87 |

|    |   |     |
|----|---|-----|
| 30 | BATSMAN OUT OF HIS GROUND .....                     | 88  |
| 31 | APPEALS .....                                       | 89  |
| 32 | BOWLED .....  | 91  |
| 33 | CAUGHT.....   | 91  |
| 34 | HIT THE BALL TWICE .....                            | 93  |
| 35 | HIT WICKET .....                                    | 94  |
| 36 | LEG BEFORE WICKET.....                              | 95  |
| 37 | OBSTRUCTING THE FIELD .....                         | 96  |
| 38 | RUN OUT .....                                       | 98  |
| 39 | STUMPED .....                                       | 99  |
| 40 | TIMED OUT .....                                     | 100 |
| 41 | UNFAIR PLAY .....                                   | 100 |
| 42 | PLAYERS' CONDUCT .....                              | 119 |
| 43 | SHEFFIELD SHIELD FINAL.....                         | 121 |
|    | APPENDIX A – Definitions and Explanations.....      | 125 |
|    | APPENDIX B – The Bat.....                           | 133 |
|    | APPENDIX C – Concussion Substitute .....            | 137 |
|    | APPENDIX D- Third Umpire and TV/Stream Replays..... | 141 |
|    | APPENDIX E – The Creases.....                       | 145 |
|    | APPENDIX F – The Wickets.....                       | 147 |
|    | APPENDIX G – Over Calculations .....                | 148 |
|    | APPENDIX H – Heat Policy.....                       | 150 |
|    | APPENDIX I – Covid Illness Replacement.....         | 155 |

# 2021/22 Sheffield Shield

## Playing Conditions

(Incorporating the MCC Laws of Cricket 2017 Code 2<sup>nd</sup> Edition 2019)

**NOTE:** Cricket Australia shall appoint a Match Referee who may meet with the umpires and captains prior to the commencement of the match to secure uniform interpretation of these Playing Conditions (unless otherwise specified) and to adjudicate, if necessary, should there be any dispute.

### 1 THE PLAYERS

#### 1.1 Number of players

- 1.1.1 A match is played between two sides, each of eleven players, one of whom shall be captain.
- 1.1.2 However, for State 2<sup>nd</sup> XI:
  - 1.1.2.1 a match is played between two sides, each of twelve players, one of who shall be captain; and
  - 1.1.2.2 only 11 players shall be permitted to bat in each innings; and
  - 1.1.2.3 only 11 players shall be permitted to field at any one time; but
  - 1.1.2.4 all 12 players may bat and bowl in the match.

#### 1.2 Nomination and replacement of players

- 1.2.1 Each captain shall nominate his players (including the selected emergency fielder/s) in writing to the Match Referee before the toss. No player may be replaced after the nomination without the consent of the opposing captain, apart from the Concussion Substitute or Covid 19 Replacement which will be managed in accordance with Appendices C & I.

**NOTE:** The captains are not required to nominate the Concussion Substitute/s or Covid-19 Replacements at this time. Concussion Substitute/s or Covid-19 Replacements will be managed on a case by case basis in accordance with Appendices C.& I

- 1.2.2 Subject to notifying the visiting State or its Team Manager, the emergency fielder of the home State may be released to play with his Club team, and the home State may supply another emergency fielder to act in his place (if required).
- 1.2.3 The 12<sup>th</sup> player, or any other emergency fielder, must wear a distinguishing top from the players on the field when walking inside the fence but outside the boundary rope.
- 1.2.4 Should any player playing in a match be required by Cricket Australia for playing duties, that requirement shall take precedence and the following will apply:
- 1.2.4.1 the player's State Association may nominate a replacement player to the opposing Team Captain for approval, which must not be unreasonably withheld. Where approval is not provided by the opposing Team Captain, the Match Referee will make a final determination on whether to grant approval for the replacement;
  - 1.2.4.2 once a replacement player has been approved, that player may act as a replacement for the remainder of that match;
  - 1.2.4.3 if the originally replaced player is no longer required by Cricket Australia, that player may resume his place in the team only if his replacement has not either batted or bowled during the absence; and
  - 1.2.4.4 otherwise the originally replaced player may take no further part in that match and the replacement player must continue in his place.
- 1.2.5 Any eligible player may act as a substitute (including as a Concussion Substitute or COVID-19 Replacement provided that is managed in accordance with Appendix C and Appendix I).

### **1.3 Captain**

- 1.3.1 If at any time the captain is not available, a deputy shall act for him.
- 1.3.2 If a captain is not available to nominate the players, then any person associated with that team may act as his deputy to do so. See 1.2.



- 1.3.3 At any time after the nomination of the players, only a nominated player can act as deputy in discharging the duties and responsibilities of the captain as stated in these clauses, including at the toss. See clause 13.4 (The toss).

## **1.4 Responsibility of captains**

The captains are responsible at all times for ensuring that play is conducted within The Spirit of Cricket as well as within the clauses. See The Preamble – The Spirit of Cricket and clause 41.1 (Fair and unfair play – responsibility of captains).

# **2 THE UMPIRES**

## **2.1 Appointment and attendance**

Cricket Australia will appoint all umpires.

## **2.2 Change of umpire**

- 2.2.1 Where an injury or illness occurs to an umpire, and they must leave the field for treatment, the other umpire shall officiate at the bowler's end. The local State Association shall provide a competent person to stand at the striker's end until the injured umpire is able to resume or a suitable replacement has been appointed.

- 2.2.2 However, for a televised match the following applies:

2.2.2.1 Where an injury or illness occurs to an umpire, and they must leave the field for treatment, the third or fourth umpire (if available) shall officiate in their place, as determined by Cricket Australia (in its absolute discretion).

2.2.2.2 The match shall continue without a third/fourth umpire until the injured/ill umpire is able to take the third umpire's role or a suitable replacement is appointed.

## **2.3 Consultation with captains**

Before the toss the umpires shall:

- 2.3.1 meet with the captains and the umpires shall determine:
- 2.3.1.1 the balls to be used during the match. See clause 4 (The ball).

- 2.3.1.2 the hours of play and the times and durations of intervals for meals and times for drinks intervals. See clause 11 (Intervals).
- 2.3.1.3 which clock or watch and back-up time piece is to be used during the match.
- 2.3.1.4 the boundary of the field of play and allowances for boundaries, including whether any obstacle within the field of play is to be regarded as a boundary. See clause 19 (Boundaries).
- 2.3.1.5 the use of covers. See clause 10 (Covering the pitch).
- 2.3.1.6 any special conditions of play affecting the conduct of the match.
- 2.3.2 inform the scorers of agreements in 2.3.1.2, 2.3.1.3, 2.3.1.4 and 2.3.1.6.

## **2.4 The wickets, creases and boundaries**

Before the toss and during the match, the umpires shall satisfy themselves that:

- 2.4.1 the wickets are properly pitched. See clause 8 (The wickets).
- 2.4.2 the creases are correctly marked. See clause 7 (The creases).
- 2.4.3 the boundary of the field of play complies with the requirements of clauses 19.1 (Determining the boundary of the field of play), 19.2 (Identifying and marking the boundary) and 19.3 (Restoring the boundary).

## **2.5 Conduct of the match, implements and equipment**

Before the toss and during the match, the umpires shall satisfy themselves that:

- 2.5.1 the conduct of the match is strictly in accordance with the clauses.
- 2.5.2 the implements used in the match conform to the following:
  - 2.5.2.1 clause 4 (The ball).
  - 2.5.2.2 externally visible requirements of clause 5 (The bat) and Appendix B.
  - 2.5.2.3 clauses 8.2 (Size of stumps) and 8.3 (The bails).
- 2.5.3 no player uses equipment other than that permitted. See Appendix A.2. Note particularly therein the interpretation of 'protective helmet'.

- 2.5.4 the wicket-keeper's gloves comply with the requirements of clause 27.2 (Gloves).

## **2.6 Fair and unfair play**

The umpires shall be the sole judges of fair and unfair play.

## **2.7 Fitness for play**

- 2.7.1 It is solely for the umpires together to decide whether either condition of ground, weather or light or exceptional circumstances mean that it would be dangerous or unreasonable for play to take place.

Conditions shall not be regarded as either dangerous or unreasonable merely because they are not ideal.

The fact that the grass and the ball are wet does not warrant the ground conditions being regarded as unreasonable or dangerous.

- 2.7.2 Conditions shall be regarded as dangerous if there is actual and foreseeable risk to the safety of any player or umpire. Conditions shall also be regarded as dangerous if the heat conditions are such that it invokes the Australian Cricket Heat Policy as outlined in Appendix K to the extent that the application of the policy recommends play to be suspended.

- 2.7.3 Conditions shall be regarded as unreasonable if, although posing no risk to safety, it would not be sensible for play to proceed.

- 2.7.4 If the umpires consider the ground is so wet or slippery as to deprive the bowler of a reasonable foothold, the fielders of the power of free movement, or the batsmen of the ability to play their strokes or to run between the wickets, then these conditions shall be regarded as so bad that it would be dangerous and unreasonable for play to take place.

- 2.7.5 If conditions during a rain stoppage improve and the rain is reduced to drizzle, the umpires must consider if they would have suspended play in the first place under similar conditions. If both on-field umpires agree that the current drizzle would not have caused a stoppage, then play shall resume immediately.

- 2.7.6 If, during a suspension of play pursuant to the Australian Cricket Heat Policy, conditions improve such that the relevant Heat Stress Risk Index falls below the threshold rating for suspension of play, then the on-field umpires must consider if they would have suspended play in the first place under similar conditions. If both on-field umpires agree that the current HSRI would not have caused a suspension in play, then play shall resume immediately.

Note: Heat Stress Risk Index and heat stress interventions will be managed in accordance to Appendix H

- 2.7.7 The umpires shall disregard any shadow on the pitch from the stadium or from any permanent object on the ground.
- 2.7.8 If a shadow from the fielder falls across the striker's half of the pitch, the fielder must remain stationary from the time the bowler commences his run up until the striker has received the ball. In the event of a fielder moving before the striker receives the ball, the umpire shall call and signal Dead Ball if they consider the striker has been disadvantaged by the action.

## **2.8 Suspension of play in dangerous or unreasonable circumstances**

- 2.8.1 All references to ground include the pitch. See clause 6.1 (Area of pitch).
- 2.8.2 The umpires shall immediately suspend play, or not allow play to start or to recommence, if both umpires agree that the conditions of ground, weather or light, or any other circumstances are either dangerous or unreasonable.
- 2.8.3 When there is a suspension of play it is the responsibility of the umpires to monitor conditions. They shall make inspections as often as appropriate, unaccompanied by any players or officials. Immediately the umpires together agree that the conditions are no longer dangerous or unreasonable they shall call upon the players to resume play.

## **2.9 Position of umpires**

The umpires shall stand where they can best see any act upon which their decision may be required.

Subject to this over-riding consideration, the bowler's end umpire shall stand in a position so as not to interfere with either the bowler's run-up or the striker's view.

The striker's end umpire may elect to stand on the off side instead of the on side of the pitch, provided they informs the captain of the fielding side, the striker and the other umpire.

## **2.10 Umpires changing ends**

The umpires shall change ends after each side has had one completed innings. See clause 13.3 (Completed innings).

## **2.11 Disagreement and dispute**

Where there is disagreement or dispute about any matter, the umpires together shall make the final decision. See also clause 31.6 (Consultation by umpires).

## **2.12 Umpire's decision**

An umpire may alter any decision provided that such alteration is made promptly. This apart, an umpire's decision, once made, is final.

## **2.13 Signals**

2.13.1 The following code of signals shall be used by umpires.

2.13.1.1 Signals made while the ball is in play:

**Dead ball:** by crossing and re-crossing the wrists below the waist.

**No ball:** by extending one arm horizontally.

**Out:** by raising an index finger above the head.  
(If not out, the umpire shall call Not out.)

**Wide:** by extending both arms horizontally.

2.13.1.2 When the ball is dead, the bowler's end umpire shall repeat the signals in 2.13.1.1, with the exception of the signal for Out, to the scorers.

2.13.1.3 The signals listed below shall be made to the scorers only when the ball is dead.

**Boundary 4:** by waving an arm from side to side finishing with the arm across the chest

- Boundary 6:** by raising both arms above the head.
- Bye:** by raising an open hand above the head.
- Commencement of last hour:** by pointing to a raised wrist with the other hand.

**Five Penalty runs awarded to batting side:**

by repeated tapping of one shoulder with the opposite hand.

**Five Penalty runs awarded to fielding side:**

by placing one hand on the opposite shoulder.

**Leg bye:** by touching a raised knee with the hand.

**New ball:** by holding the ball above the head.

**Revoke last signal:** by touching both shoulders, each with the opposite hand.

**Short run:** by bending one arm upwards and touching the nearer shoulder with the tips of the fingers.

The following signals are for Level 4 player conduct offences. Each signal has two parts, both of which should be acknowledged separately by the scorers.

- Level 4 conduct:**
- Part 1:** by putting one arm out to the side of the body and repeatedly raising it and lowering it.
  - Part 2:** by raising an index finger, held at shoulder height, to the side of the body.

2.13.1.4 All the signals in 2.13.1.3 are to be made by the bowler's end umpire except that for Short run, which is to be signalled by the umpire at the end where short running occurs. However, the bowler's end umpire shall be responsible both for the final signal of Short run to the scorers and for informing them as to the number of runs to be recorded.

2.13.2 The umpire shall wait until each signal to the scorers has been separately acknowledged by a scorer before allowing play to proceed.

If several signals are to be used, they should be given in the order that the events occurred.

## **2.14 Informing the umpires**

Throughout the clauses, wherever the umpires are to receive information from captains or other players, it will be sufficient for one umpire to be so informed and for them to inform the other umpire.

## **2.15 Correctness of scores**

Consultation between umpires and scorers on doubtful points is essential. The umpires shall, throughout the match, satisfy themselves as to the correctness of the number of runs scored, the wickets that have fallen and, where appropriate, the number of overs bowled. They shall agree these with the scorers at least at every interval, other than a drinks interval, and at the conclusion of the match. See clauses 3.2 (Correctness of scores), 16.8 (Correctness of result) and 16.10 (Result not to be changed).

## **2.16 Third Umpire/TV/Stream Replays**

Refer to Appendix D.

## **2.17 Light Meters**

2.17.1 Cricket Australia shall supply light meters to the match officials to be used in accordance with these playing conditions.

2.17.2 All light meters shall be uniformly calibrated.

2.17.3 In the Sheffield Shield, the umpires shall be entitled to use light meter readings:

2.17.3.1 as a guideline for determining whether the light is fit for play in accordance with the criteria set out in 2.7 and 2.8;

2.17.3.2 to, at any stage, determine whether there has been a deterioration or improvement in the light; and/or

2.17.3.3 as benchmarks for the remainder of a stoppage and match.

## **2.18 Use of artificial lights**

2.18.1 If in the opinion of the umpires, natural light is deteriorating to an unfit level, they shall authorise the ground authorities to use the available artificial lighting so that the match can continue in acceptable conditions. If natural light improves, the artificial lights may be turned off.

2.18.2 The lights are only to be used to enable a full day's play.

2.18.3 Where artificial lights are in use, all references to light under 2.7 (Fitness for play) and 2.8 (Suspension of play in dangerous or unreasonable conditions) still apply. For clarity, in these circumstances the umpires will only suspend play if they determine conditions to be unsafe or dangerous, otherwise play shall continue until the required overs are completed or the time for the cessation of play is reached.

2.18.4 In the event of power failure or malfunction the provisions relating to the delay or interruption of play due to ground, weather or light conditions will apply, including 2.7 and 2.8.

2.18.5 For State 2<sup>nd</sup> XI matches where artificial lighting is available the lighting may be used at the discretion of the home team.

Both teams and match officials must be advised of the use lights prior to the toss.

After the toss the decision to allow/not allow the use of artificial lighting cannot be changed.

## **3 THE SCORERS**

### **3.1 Appointment of scorers**

Two scorers shall be appointed to record all runs scored, all wickets taken and, where appropriate, number of overs bowled.

### **3.2 Correctness of scores**

The scorers shall frequently check to ensure that their records agree. They shall agree with the umpires, at least at every interval, other than drinks intervals, and at the conclusion of the match, the runs scored, the wickets



that have fallen and, where appropriate, the number of overs bowled. See clause 2.15 (Correctness of scores).

### **3.3 Acknowledging signals**

The scorers shall accept all instructions and signals given to them by the umpires and shall immediately acknowledge each separate signal.

## **4 THE BALL**

### **4.1 Weight and size**

The ball, when new, shall weigh not less than 5.5 ounces/155.9 g, nor more than 5.75 ounces/163 g, and shall measure not less than 8.81 in/22.4 cm, nor more than 9 in/22.9 cm in circumference.

### **4.2 Approval and control of balls**

- 4.2.1 First class quality balls approved by Cricket Australia must be used.

**NOTE:** The Kookaburra “Turf” brand red ball has been approved. Cricket Australia may from time to time approve the use of other balls (e.g. Kookaburra Pink balls or Dukes balls).

The captain of the fielding side or his nominee may select the ball(s) to be used from the supply provided by the Home State Association.

- 4.2.2 The umpires shall:

- 4.2.2.1 retain possession of the match ball(s) throughout the duration of a match when play is not actually taking place;
- 4.2.2.2 during play, periodically inspect the condition of the ball; and
- 4.2.2.3 take possession of the ball in use at the fall of each wicket, at the start of any interval and at any interruption of play.

### **4.3 New ball**

A new ball will be used at the start of each innings.

### **4.4 New ball in match of more than one day's duration**

The captain of the fielding side may demand a new ball when the number of overs, excluding any part overs, bowled with the old one is equal to or greater

than 80 overs. The umpire shall inform the other umpire and indicate to the batsmen and the scorers whenever a new ball is taken into play.

#### **4.5 Ball lost or becoming unfit for play**

- 4.5.1 If, during play, the ball cannot be found or recovered or the umpires agree that it has become unfit for play through normal use, the umpires shall replace it with a ball which has had wear comparable with that which the previous ball had received before the need for its replacement.
- 4.5.2 In the event of a ball becoming wet and soggy because of play continuing during inclement weather, or it being affected by dew, and in the opinion of the umpires the ball becomes unfit for play, the ball shall be replaced with a ball that has had a similar amount of wear.
- 4.5.3 In the case of 4.5.2, a bowler or batsman may raise the matter with the umpires and the umpires' decision as to a replacement or otherwise will be final.
- 4.5.4 Where the ball needs to be replaced for any reason after 110 overs have been bowled with it, it shall be replaced with a new ball.
- 4.5.5 When the ball is replaced, the umpire shall inform the batsmen and the fielding captain.

### **5 THE BAT**

#### **5.1 The bat**

- 5.1.1 The bat consists of two parts, a handle and a blade.
- 5.1.2 The basic requirements and measurements of the bat are set out in this clause with detailed specifications in Appendix B.

#### **5.2 The handle**

- 5.2.1 The handle is to be made principally of cane and/or wood.
- 5.2.2 The part of the handle that is wholly outside the blade is defined to be the upper portion of the handle. It is a straight shaft for holding the bat.
- 5.2.3 The upper portion of the handle may be covered with a grip as defined in Appendix B.2.2.

### **5.3 The blade**

- 5.3.1 The blade comprises the whole of the bat apart from the handle as defined in 5.2 and in Appendix B.
- 5.3.2 The blade shall consist solely of wood.
- 5.3.3 All bats may have commercial identifications on the blade, the size of which must comply with the relevant specification in Appendix B.

### **5.4 Protection and repair**

Subject to the specifications in Appendix B and providing 5.5 (Damage to the ball) is not contravened:

- 5.4.1 solely for the purposes of either protection from surface damage to the face, sides and shoulders of the blade or repair to the blade after surface damage, material that is not rigid, either at the time of its application to the blade or subsequently, may be placed on these surfaces.
- 5.4.2 for repair of the blade after damage other than surface damage:
  - 5.4.2.1 solid material may be inserted into the blade.
  - 5.4.2.2 the only material permitted for any insertion is wood with minimal essential adhesives.
- 5.4.3 to prevent damage to the toe, material may be placed on that part of the blade but shall not extend over any part of the face, back or sides of the blade.

### **5.5 Damage to the ball**

- 5.5.1 For any part of the bat, covered or uncovered, the hardness of the constituent materials and the surface texture thereof shall not be such that either or both could cause unacceptable damage to the ball.
- 5.5.2 Any material placed on any part of the bat, for whatever purpose, shall similarly not be such that it could cause unacceptable damage to the ball.
- 5.5.3 For the purpose of this clause, unacceptable damage is any change that is greater than normal wear and tear caused by the ball striking the uncovered wooden surface of the blade.

### **5.6 Contact with the ball**

In these clauses:

- 5.6.1 reference to the bat shall imply that the bat is held in the batsman's hand or a glove worn on his hand, unless stated otherwise.
- 5.6.2 contact between the ball and any of 5.6.2.1 to 5.6.2.4:
- 5.6.2.1 the bat itself;
  - 5.6.2.2 the batsman's hand holding the bat;
  - 5.6.2.3 any part of a glove worn on the batsman's hand holding the bat;
  - 5.6.2.4 any additional materials permitted under 5.4,
- shall be regarded as the ball striking or touching the bat or being struck by the bat.

## **5.7 Bat size limits**

- 5.7.1 The overall length of the bat, when the lower portion of the handle is inserted, shall not be more than 38 in/96.52 cm.
- 5.7.2 The blade of the bat shall not exceed the following dimensions:
- 5.7.2.1 Width: 4.25in / 10.8 cm
  - 5.7.2.2 Depth: 2.64in / 6.7 cm Edges: 1.56in / 4.0cm.
- Furthermore, it should also be able to pass through a bat gauge as described in Appendix B.
- 5.7.3 Except for bats of size 6 and less, the handle shall not exceed 52% of the overall length of the bat.
- 5.7.4 The material permitted for covering the blade in 5.4.1 shall not exceed 0.04 in/0.1 cm in thickness.
- 5.7.5 The maximum permitted thickness of protective material placed on the toe of the blade is 0.12 in/0.3 cm.

## **5.8 Categories of bat**

Only Type A bats must be used.

# **6 THE PITCH**

## **6.1 Area of pitch**

The pitch is a rectangular area of the ground 22 yards/20.12 m in length and 10 ft/3.05 m in width. It is bounded at either end by the bowling creases and on either side by imaginary lines, one each side of the imaginary line joining the centres of the two middle stumps, each parallel to it and 5 ft/1.52 m from

it. See clauses 8.1 (Description, width and pitching) and 7.2 (The bowling crease).

## **6.2 Fitness of pitch for play**

The umpires shall be the sole judges of the fitness of the pitch for play. See clauses 2.7 (Fitness for play) and 2.8 (Suspension of play in dangerous or unreasonable conditions).

## **6.3 Selection and preparation**

6.3.1 Before the match, the Ground Authority shall be responsible for the selection and preparation of the pitch. During the match, the umpires shall control its use and maintenance.

6.3.2 Captains, umpires and ground staff shall cooperate to ensure that, prior to the start of any day's play, no one:

6.3.2.1 bounces a ball on the pitch to assess its condition or for any other reason.

6.3.2.2 strikes the pitch with a bat to assess its condition or for any other reason; or

6.3.2.3 causes damage to the pitch in any other way.

6.3.3 Prior to the start of play on any day, only the captain and team coach may walk on the pitch to assess its condition. Spiked footwear is not permitted at this time.

6.3.4 Prior to the commencement of a day's play and during intervals, one commentator and camera crew of the official licensed broadcaster/s (but not a news crew) may be permitted to inspect the pitch and surrounds (without walking on the pitch or interfering with pitch preparation) subject to the following:

6.3.4.1 a ball must not be bounced on the pitch; and

6.3.4.2 a key or knife may only be inserted in the pitch in the area between the popping and bowling creases.

## **6.4 Changing the pitch**

6.4.1 In the event a match cannot be played or is abandoned because of inadequate pitch and/or ground preparation the match will in the first instance and if possible, be relocated and/or rescheduled by Cricket Australia (in its absolute discretion).

- 6.4.2 Any relocated and/or rescheduled match, if possible, will be played in the home State of the “away” team of the scheduled match at a venue to be selected by Cricket Australia (in its absolute discretion).
- 6.4.3 If the scheduled match cannot be relocated and/or rescheduled each team will be awarded:
- 6.4.3.1 3 points; plus
  - 6.4.3.2 the average total bonus points that were accumulated per team across the other two matches played in the round of the abandoned match.

## **6.5 Disputes about the pitch**

- 6.5.1 The Match Referee will decide any disputes relating to this clause (excluding 6.4) and their ruling will be final.
- 6.5.2 The Match Referee may consult with relevant representatives of Cricket Australia in relation to any aspect of such a dispute, where they consider it necessary.
- 6.5.3 Where 6.4 has been applied in relation to a match:
- 6.5.3.1 Cricket Australia will conduct a thorough investigation of the circumstances into the rescheduling or abandonment of the scheduled match and prepare a report regarding the decision and a recommended penalty (if appropriate) to be imposed on the State Association responsible for pitch and/or ground preparation of the scheduled match.
  - 6.5.3.2 Cricket Australia (in its absolute discretion) has the right to impose a financial penalty of up to \$200,000 against the State Association responsible for pitch and/or ground preparation of the scheduled match.
  - 6.5.3.3 A financial penalty may be applied regardless of whether the match could be rescheduled/relocated or not.
  - 6.5.3.4 A Commissioner appointed by Cricket Australia will hear and determine all appeals against penalties imposed in accordance with 6.5.
  - 6.5.3.5 An appeal must be lodged by the original scheduled date of completion of the match or 2 days after Cricket Australia imposes any penalty under 6.5 (whichever is later).

- 6.5.3.6 The onus shall be on the appellant to prove that the venue was suitable for play to commence or continue (as applicable). Video evidence where available may be produced by the appellant or respondent in relation to the appeal.
- 6.5.3.7 For the purposes of 6.4, the pitch and/or ground preparation will be deemed to have been inadequate if the match cannot be played or completed as a direct or indirect result of the State Association (or any of its employees, contractors or agents) responsible for preparing the pitch and/or ground failing to take proper precautions in the circumstances to ensure that the pitch and/or ground was properly:
- 6.5.3.7.1 prepared; or
  - 6.5.3.7.2 protected against the elements or other acts of God, vandalism or foul play, machinery or equipment failure or other reasonably foreseeable events.
- 6.5.3.8 A Ground Authority and/or groundskeeper who is responsible for the preparation of the pitch and/or ground and who is employed by a body other than the State Association responsible for preparing the pitch and/or ground, is deemed to be a contractor or agent of that Association.

## **7 THE CREASES**

### **7.1 The creases**

The positions of a bowling crease, a popping crease and two return creases shall be marked by white lines, as set out in 7.2, 7.3 and 7.4, at each end of the pitch. See Appendix E.

### **7.2 The bowling crease**

The bowling crease, which is the back edge of the crease marking, is the line that marks the end of the pitch, as in clause 6.1 (Area of pitch). It shall be 8 ft 8 in/2.64 m in length.

### **7.3 The popping crease**

The popping crease, which is the back edge of the crease marking, shall be in front of and parallel to the bowling crease and shall be 4 ft/1.22 m from it. The popping crease shall be marked to a minimum of 15 yards/13.71m on either side of the imaginary line joining the centres of the two middle stumps and shall be considered to be unlimited in length.

### **7.4 The return creases**

The return creases, which are the inside edges of the crease markings, shall be at right angles to the popping crease at a distance of 4 ft 4 in/1.32 m either side of the imaginary line joining the centres of the two middle stumps. Each return crease shall be marked from the popping crease to a minimum of 8 ft/2.44 m behind it and shall be considered to be unlimited in length.

## **8 THE WICKETS**

### **8.1 Description, width and pitching**

Two sets of wickets shall be pitched opposite and parallel to each other in the centres of the bowling creases. Each set shall be 9 in/22.86 cm wide and shall consist of three wooden stumps with two wooden bails on top. See Appendix F.

### **8.2 Size of stumps**

- 8.2.1 The tops of the stumps shall be 28 in/71.12 cm above the playing surface and shall be dome shaped except for the bail grooves.
- 8.2.2 The portion of a stump above the playing surface shall be cylindrical apart from the domed top, with circular section of diameter not less than 1.38 in/3.50 cm nor more than 1.5 in/3.81 cm. See Appendix F.
- 8.2.3 For broadcast matches the home State Association may provide a slightly larger stump to accommodate the stump camera. When the larger stump is used, all six stumps must be the same size.

### **8.3 The bails**

- 8.3.1 The bails, when in position on top of the stumps,
  - 8.3.1.1 shall not project more than 0.5 in/1.27 cm above them.
  - 8.3.1.2 shall fit between the stumps without forcing them out of the vertical.



- 8.3.2 Each bail shall conform to the following specifications (see Appendix F):
- 8.3.2.1 Overall length: 4.31 in/10.95 cm
  - 8.3.2.2 Length of barrel: 2.13 in /5.40 cm
  - 8.3.2.3 Longer spigot: 1.38 in/3.50 cm
  - 8.3.2.4 Shorter spigot: 0.81 in/2.06 cm.
- 8.3.3 The two spigots and the barrel shall have the same centre line.
- 8.3.4 Devices aimed at protecting player safety by limiting the distance that a bail can travel off the stumps will be allowed, subject to the approval of Cricket Australia.

## **8.4 Dispensing with bails**

The umpires may agree to dispense with the use of bails, if necessary. If they so agree then no bails shall be used at either end. The use of bails shall be resumed as soon as conditions permit. See clause 29.4 (Dispensing with bails).

# **9 PREPARATION AND MAINTENANCE OF THE PLAYING AREA**

## **9.1 Rolling**

The pitch shall not be rolled during the match except as permitted in 9.1.1 and 9.1.2.

### **9.1.1 Frequency and duration of rolling**

During the match the pitch may be rolled at the request of the captain of the batting side, for a period of not more than 7 minutes, before the start of each innings, other than the first innings of the match, and before the start of each subsequent day's play. See 9.1.4.

### **9.1.2 Rolling after a delayed start**

In addition to the rolling permitted above, if, after the toss and before the first innings of the match, the start is delayed, the captain of the batting side may request that the pitch be rolled for not more than 7 minutes. However, if the umpires together agree that the delay has had no significant effect on the state of the pitch, they shall refuse such request for rolling of the pitch.

### 9.1.3 Choice of rollers

If there is more than one roller available the captain of the batting side shall choose which one is to be used.

### 9.1.4 Timing of permitted rolling

The rolling permitted (maximum 7 minutes) before play begins on any day shall be started not more than 30 minutes before the time scheduled or rescheduled for play to begin. The captain of the batting side may, however, delay the start of such rolling until not less than 10 minutes before the time scheduled or rescheduled for play to begin.

### 9.1.5 Artificial drying of the pitch

9.1.5.1 Prior to tossing the coin for choice of innings the artificial drying of the pitch and outfield shall be at the discretion of the ground staff.

9.1.5.2 Thereafter and throughout the match the drying of the outfield may be undertaken at any time by the ground staff, but the drying of the affected area of the pitch shall be carried out only on the instructions and under the supervision of the umpires.

9.1.5.3 The umpires shall be empowered to have the pitch dried without reference to the captains at any time they are of the opinion that it is unfit for play.

9.1.5.4 The umpires may instruct the ground staff to use any available equipment, including any roller for the purpose of drying the pitch and making it fit for play.

9.1.5.5 An absorbent roller may be used to remove water from the covers including the cover on the match pitch.

## 9.2 Clearing debris from the pitch

### 9.2.1 The pitch shall be cleared of any debris:

9.2.1.1 before the start of each day's play. This shall be after the completion of mowing and before any rolling, not earlier than 30 minutes nor later than 10 minutes before the time or any rescheduled time for start of play.

9.2.1.2 between innings. This shall precede rolling if any is to take place.

9.2.1.3 at all intervals for meals.

- 9.2.2 The clearance of debris in 9.2.1 shall be done by sweeping, except where the umpires consider that this may be detrimental to the surface of the pitch. In this case the debris must be cleared from that area by hand, without sweeping.
- 9.2.3 In addition to 9.2.1, debris may be cleared from the pitch by hand, without sweeping, before mowing and whenever either umpire considers it necessary.

### **9.3 Mowing**

#### **9.3.1 Responsibility for mowing**

- 9.3.1.1 All mowings which are carried out before the match shall be the sole responsibility of the Ground Authority.
- 9.3.1.2 All subsequent mowings shall be carried out under the supervision of the umpires.

#### **9.3.2 The pitch and outfield**

- 9.3.2.1 In order that throughout the match the ground conditions should be as nearly the same for both sides as possible, both the pitch and the outfield shall be mown on each day of the match on which play is expected to take place, if ground and weather conditions permit.
- 9.3.2.2 If, for reasons other than conditions of ground or weather, complete mowing of the outfield is not possible, the Ground Authority shall notify the captains and umpires of the procedure to be adopted for such mowing during the match.

#### **9.3.3 Timing of mowing**

- 9.3.3.1 Mowing of the pitch on any day shall be completed not later than 30 minutes before the time scheduled or rescheduled for play to begin on that day, before any sweeping prior to rolling. If necessary, debris may be removed from the pitch before mowing, by hand, without sweeping. See 9.2.3.
- 9.3.3.2 Mowing of the outfield on any day shall be completed not later than 15 minutes before the time scheduled or rescheduled for play to begin on that day.
- 9.3.3.3 The outfield must be mown daily before play begins.

### **9.4 Watering the pitch**

9.4.1 The pitch shall not be watered during the match.

9.4.2 The pitch square (other than the pitch in use) and the outfield may be watered after each day's play at the discretion of the Ground Authority after consultation with the Match Referee.

## **9.5 Re-marking creases**

Creases shall be re-marked whenever either umpire considers it necessary.

## **9.6 Maintenance of footholes**

The umpires shall ensure that the holes made by the bowlers and batsmen are cleaned out and dried whenever necessary to facilitate play.

The umpires shall allow, if necessary, the re-turfing of footholes made by the bowlers in their delivery strides, or the use of quick-setting fillings for the same purpose.

In addition, the umpires shall see that wherever possible and whenever it is considered necessary, action is taken during all intervals in play to do whatever is practicable to improve the bowler's footholes. As soon as possible after the conclusion of each day's play, bowler's footholes will be repaired.

## **9.7 Securing of footholds and maintenance of pitch**

During play, umpires shall allow the players to secure their footholds by the use of sawdust provided that no damage to the pitch is caused and that clause 41 (Fair and unfair play) is not contravened.

# **10 COVERING THE PITCH**

## **10.1 Before the match**

10.1.1 The use of covers before the match is the responsibility of the Ground Authority and may include full covering if required.

- 10.1.2 However, the Ground Authority shall grant suitable facility to the captains to inspect the pitch before the nomination of their players and to the umpires to discharge their duties as laid down in clauses 2 (The umpires), 6 (The pitch), 7 (The creases), 8 (The wickets), and 9 (Preparation and maintenance of the playing area).
- 10.1.3 The pitch must be entirely protected against rain up to the commencement of play.

## **10.2 During the match**

- 10.2.1 The pitch must be entirely protected against rain up to the commencement of play and for the duration of the match.
- 10.2.2 The pitch must be wholly covered at the termination of each day's play or, providing the weather is fine, within a period of two hours thereafter.
- 10.2.3 The covers must protect:
- 10.2.3.1 the whole pitch and its surroundings to a minimum of 5m either side of the pitch and any worn or soft areas in the outfield.
  - 10.2.3.2 where possible, the bowlers' run-ups to a distance of 10 x 10m.

## **10.3 Removal of covers**

- 10.3.1 All covers (including "hessian" or "scrim" covers used to protect the pitch against the sun) shall be removed not later than 2.5 hours before the scheduled start of play provided it is not raining at the time, but they will be replaced if rain falls prior to the commencement of play.
- 10.3.2 If covers are used during the day as protection from inclement weather, or if inclement weather delays the removal of covers, they shall be removed promptly as soon as conditions allow.

# **11 INTERVALS**

## **11.1 An interval**

- 11.1.1 The following shall be classed as intervals:
- 11.1.1.1 the period between close of play on one day and the start of the next day's play;

- 11.1.1.2 intervals between innings;
  - 11.1.1.3 intervals for meals;
  - 11.1.1.4 intervals for drinks; and
  - 11.1.1.5 any other agreed interval.
- 11.1.2 Each of these intervals, excluding the period specified at 11.1.1.1 shall be considered as scheduled breaks for the purposes of clauses 24.2.7 and 25.4.5.

## **11.2 Duration of intervals**

- 11.2.1 An interval for lunch or tea shall be of the duration agreed under clause 2.3 (Consultation with captains), taken from the call of Time before the interval until the call of Play on resumption after the interval.
- 11.2.2 An interval between innings shall be 10 minutes, commencing from the close of an innings until the call of Play for the start of the next innings. See, however, 11.3, 11.5 and 11.6.
- 11.2.3 Clause 11.2 shall apply subject to the following:
- 11.2.3.1 Lunch Interval: The interval shall be of 40 minutes duration.
  - 11.2.3.2 Tea Interval: The interval shall be of 20 minutes duration.
- For day/night matches:
- 11.2.3.3 Tea Interval: The interval shall be of 20 minutes duration.
  - 11.2.3.4 Dinner Interval: The interval shall be of 40 minutes duration.
- 11.2.4 Any references to a Lunch interval in these playing conditions (other than in this clause 11.2) should be read as a reference to Dinner in relation to day/night matches (unless otherwise indicated).

## **11.3 Allowance for interval between innings**

In addition to the provisions of 11.5, 11.6 and 12.12:

- 11.3.1 if an innings ends when 10 minutes or less remains before the time agreed for close of play, or when there are less than 2 overs remaining to complete the minimum over requirement on any day, whichever is later, there shall be no further play on that day. No change shall be made to the time for the start of play on the following day on account of the 10 minute interval between innings.

- 11.3.2 if a captain declares an innings closed during an interruption in play of more than 10 minutes duration, provided that at least 10 minutes remains of the interruption, no adjustment shall be made to the time for resumption of play on account of the 10 minute interval between innings, which shall be considered as included in the interruption. If less than 10 minutes remains of the interruption when the captain declares the innings closed, or forfeits an innings, the next innings shall commence 10 minutes after the declaration or forfeiture is made.
- 11.3.3 if a captain declares an innings closed during any interval other than an interval for drinks, provided that at least 10 minutes remains of the interval, the interval shall be of the agreed duration and shall be considered to include the 10 minute interval between innings. If less than 10 minutes remains of the interval when the captain declares the innings closed, or forfeits an innings, the interval shall be:
- 11.3.3.1 extended as necessary and the next innings shall commence 10 minutes after the declaration or forfeiture is made; and
- 11.3.3.2 the amount of full overs (based on a rate of 3.75 minutes per over) that could have been bowled in time by which the interval is extended in accordance with 11.3.3.1 above will be deducted from the remaining playing time in that day's play.

|   |
|---|
| <p><b>NOTE:</b> For example, where an interval is extended by 5 minutes under this clause, then one over will be deducted from the minimum overs remaining in that day.</p> |
|---|

## **11.4 Changing agreed times of intervals**

If, at any time during the match, either playing time is lost through adverse conditions of ground, weather or light or in exceptional circumstances, or the players have occasion to leave the field other than at a scheduled interval, the time of the lunch interval or of the tea interval may be changed if the two

umpires and both captains so agree, providing the requirements of 11.2 and 11.5, 11.6, 11.7 and 11.8.3 are not contravened.

### **11.5 Changing agreed time for lunch interval**

- 11.5.1 If an innings ends when 10 minutes or less remains before the agreed time for lunch, the interval shall be taken immediately. It shall be of the agreed duration and shall be considered to include the 10 minute interval between innings.
- 11.5.2 If because of adverse conditions of ground, weather or light, or in exceptional circumstances, a stoppage occurs when 10 minutes or less remains before the agreed time for lunch, then, whether or not agreement is reached in the circumstances of 11.4, the interval shall be taken immediately. It shall be of the agreed duration. Play shall resume at the end of this interval or as soon after as conditions permit.
- 11.5.3 If the players have occasion to leave the field for any reason when more than 10 minutes remains before the agreed time for lunch then, unless the umpires and captains together agree to alter it, lunch shall be taken at the agreed time.

### **11.6 Changing agreed time for tea interval**

- 11.6.1 If an innings ends when 30 minutes or less remains before the agreed time for tea, the interval shall be taken immediately. It shall be of the agreed duration and shall be considered to include the 10 minute interval between innings.
- 11.6.2 If, when 30 minutes remains before the agreed time for tea, an interval between innings is already in progress, play shall resume at the end of the 10 minute interval, if conditions permit.
- 11.6.3 If, because of adverse conditions of ground, weather or light, or in exceptional circumstances, a stoppage occurs when 30 minutes or less remains before the agreed time for tea, then unless there is an agreement to change the time for tea, as permitted in 11.4 the interval shall be taken immediately. The interval shall be of the agreed duration. Play shall resume at the end of the interval or as soon after as conditions permit.
- 11.6.4 If a stoppage is already in progress when 30 minutes remains before the agreed time for tea, 11.4 shall apply.



## **11.7 Lunch or tea interval – 9 wickets down**

- 11.7.1 For the lunch interval and for the tea interval if either 9 wickets are already down when 3 minutes remains to the agreed time for the interval, or the 9<sup>th</sup> wicket falls within this 3 minutes, or at any time up to and including the final ball of the over in progress at the agreed time for the interval, then the provisions of clause 12.5.2 shall not apply and the interval will not be taken until the end of the over that is in progress 30 minutes after the originally agreed time for the interval, unless the players have cause to leave the field of play or the innings is completed earlier.
- 11.7.2 For the purposes of this section of 11.7, the retirement of a batsman is not to be considered equivalent to the fall of a wicket.

|  |
|--|
| <p><b>NOTE:</b> This clause will still apply if the Lunch or Tea Interval has already been delayed by operation of clause 12.14.4 below.</p> |
|--|

## **11.8 Intervals for drinks**

- 11.8.1 If on any day the captains agree that there shall be intervals for drinks, the option to take such drinks shall be available to either side. Each interval shall be kept as short as possible and in any case shall not exceed 4 minutes.
- 11.8.2 A drinks interval shall be taken at the end of the over in progress when the agreed time is reached. If, however, a wicket falls or a batsman retires within 5 minutes of the agreed time then drinks shall be taken immediately.
- No other variation in the timing of drinks intervals shall be permitted except as provided for in 11.8.3.
- 11.8.3 If an innings ends or the players have to leave the field of play for any other reason within 30 minutes of the agreed time for a drinks interval, the umpires and captains together may rearrange the timing of drinks intervals in that session.
- 11.8.4 Intervals for drinks may not be taken during the last hour of the match, as defined in clause 12.6 (Last hour of match – number of overs). Subject to this limitation, the captains and umpires shall agree the times for such intervals, if any, before the toss and on each subsequent day not later than 10 minutes before play is scheduled to start.
- 11.8.5 Under conditions of extreme heat the umpires may permit extra or longer intervals for drinks (maximum 15 minutes).

Any time taken for a drinks interval over and above the permitted time for a drinks break shall be treated as a delay in play and clause 12.11.3 (Additional Hour) shall apply.

- 11.8.6 An individual player may be given a drink either on the boundary edge or at the fall of a wicket, on the field, if no playing time is wasted. If individual drinks have been brought onto the field at the fall of a wicket, the fielding side must be ready to continue play as soon as the new batsman reaches the pitch. No other drinks shall be taken onto the field without the permission of the umpires.
- 11.8.7 The umpires shall consider the weather and availability of drinks due to wickets falling and may disallow the scheduled drinks interval. This shall be communicated 5 minutes before the scheduled time. The batting side shall be responsible on all occasions to make drinks available to the umpires.
- 11.8.8 No person other than players or authorised room attendants shall be permitted on the field of play during an interval for drinks, except as permitted by the umpires or Match Referee for wholly acceptable reasons. In the case of a player taking the drinks onto the field, and he must be dressed in approved clothing and equipment.
- 11.8.9 It is not permitted for any coaching of the players to take place during any interval for drinks. For clarity, this playing condition is designed to prohibit coaching of the players by any coach or support staff member either on the field of play, on the boundary edge, or from anywhere else whatsoever, during the interval for drinks.

## **11.9 Scorers to be informed**

The umpires shall ensure that the scorers are informed of all agreements about hours of play and intervals and of any changes made thereto as permitted under this clause.

## **12 START OF PLAY; CESSATION OF PLAY**

### **12.1 Call of Play**

The bowler's end umpire shall call Play at the start of the match and on the resumption of play after any interval or interruption.

## **12.2 Call of Time**

- 12.2.1 The bowler's end umpire shall call Time when the ball is dead on the cessation of play before any interval or interruption and at the conclusion of the match. See clauses 20.3 (Call of Over or Time) and 31 (Appeals).
- 12.2.2 Except on the last day, if in the event of dangerous or unreasonable ground, weather or light conditions causing a suspension of play and/or if the players are already off the field at the rescheduled cessation time or any time thereafter, stumps shall be drawn.

## **12.3 Removal of bails**

After the call of Time, the bails shall be removed from both wickets.

## **12.4 Starting a new over**

Another over shall always be started at any time during the match, unless an interval is to be taken in the circumstances set out in 12.5.2, if the umpire, walking at normal pace, has arrived at the position behind the stumps at the bowler's end before the time agreed for the next interval, or for the close of play, has been reached.

## **12.5 Completion of an over**

Other than at the end of the match:

- 12.5.1 if the agreed time for an interval is reached during an over, the over shall be completed before the interval is taken, except as provided for in 12.5.2.
- 12.5.2 when less than 3 minutes remains before the time agreed for the next interval, the interval shall be taken immediately if either a batsman is dismissed or retires or the players have occasion to leave the field whether this occurs during an over or at the end of an over. Except at the end of an innings, if an over is thus interrupted it shall be completed on the resumption of play.

## **12.6 Last hour of match – number of overs**

- 12.6.1 When one hour of playing time of the match remains, according to the agreed hours of play, the over in progress shall be completed. The next over shall be the first of a minimum of 16 overs which must be bowled, provided that a result is not reached earlier and provided that there is no interval or interruption in play.

12.6.2 The bowler's end umpire shall indicate the commencement of this minimum of 16 overs to the players and to the scorers. The period of play thereafter shall be referred to as the last hour, whatever its actual duration.

12.6.3 Clause 12.6 applies subject to 12.10 and 12.11.

## **12.7 Conclusion of match**

12.7.1 The match is concluded:

12.7.1.1 as soon as a result as defined in clauses 16.1 to 16.4 and 16.5.1 (The result) is reached.

12.7.1.2 as soon as both the minimum number of overs for the last hour are completed and the agreed time for close of play is reached, unless a result is reached earlier.

12.7.2 The match is concluded if, without a conclusion having been reached under 12.7.1, the players leave the field for adverse conditions of ground, weather or light, or in exceptional circumstances, and no further play is possible.

## **12.8 Completion of last over of match**

The over in progress at the close of play on the final day shall be completed unless either a result has been reached or the players have occasion to leave the field. In this case there shall be no resumption of play except in the circumstances of clause 16.9 (Mistakes in scoring) and the match shall be at an end.

## **12.9 Bowler unable to complete an over during last hour of match**

If, for any reason, a bowler is unable to complete an over during the last hour, clause 17.8 (Bowler incapacitated or suspended during an over) shall apply. The separate parts of such an over shall count as one over of the minimum to be bowled.

## **12.10 Hours of Play**

12.10.1 On each day of play there will be three sessions of 2 hours scheduled duration, separated by an interval between each session.

| Day Match Example: |           | Day/Night Match Example: |           |
|--------------------|-----------|--------------------------|-----------|
| 10:30am – 12:30pm  | Session 1 | 2:00pm – 4:00pm          | Session 1 |
| 12:30pm – 1:10pm   | Lunch     | 4:00pm – 4:20pm          | Tea       |
| 1:10pm – 3:10pm    | Session 2 | 4:20pm – 6:20pm          | Session 2 |
| 3:10pm – 3:30pm    | Tea       | 6:20pm – 7:00pm          | Dinner    |
| 3:30pm – 5:30pm    | Session 3 | 7:00pm – 9:00pm          | Session 3 |

12.10.2 Refer to the competition fixtures for start times. Any State Association wishing to change the hours of play must first obtain approval from Cricket Australia.

12.10.3 Any rescheduling of times will be subject to 12.11 to 12.14 below.

## 12.11 Minimum overs in the day

**NOTE:** Appendix G contains examples that provide guidance on how 12.11 to 12.14 are to be applied in match situations.

12.11.1 Play shall continue on each day until the completion of a minimum number of overs or until the scheduled or rescheduled cessation time, whichever is the later.

12.11.2 Unless an innings ends or an interruption occurs, the minimum number of overs to be completed are:

12.11.2.1 on days other than the last day:

12.11.2.1.1 a minimum of 96 overs (with a minimum of 16 overs per hour); or

12.11.2.1.2 until the scheduled or rescheduled cessation time, whichever is the later.

12.11.2.1.3 play may continue for a maximum of 30 minutes beyond the scheduled or rescheduled cessation time (**Permitted Overtime**).

12.11.2.1.4 the over in progress at that time shall be completed (except if it is the last minimum over or beyond as outlined in 12.13.1) and any overs remaining will not be made up on any subsequent day.

12.11.2.2 on the last day: a minimum of 80 overs (or a minimum of 16 overs per hour) for playing time other than the last hour of the match when 12.12 below shall apply.

- 12.11.3 **Additional Hour:** In the event of play being suspended for any reason other than normal intervals, the playing time on that day shall be extended (except in the last hour of the match and subject to ground, weather or light conditions), by the amount of time lost up to a maximum of one hour. In these circumstances, the minimum number of overs to be bowled shall be a minimum of 16 overs per hour and the cessation time shall be rescheduled accordingly.

**NOTE:** The Additional Hour is available in addition to the Permitted Overtime.

- 12.11.4 If play has been suspended for 30 minutes or more prior to the commencement of the scheduled or rescheduled Tea (or Dinner in a day/night match) interval, the Tea (or Dinner in a day/night match) interval shall be delayed for 30 minutes.
- 12.11.5 If any time or overs are lost and cannot be made up under 12.11.3, additional time and overs of up to a maximum of one hour per day (16 overs) shall be added to the scheduled playing hours for the next day/s as required (to make up as much lost time as possible).

**NOTE:** Where the amount of playing time lost is greater than the number of overs remaining to be bowled in that day (based on an over rate of 3.75 minutes per over), then the total amount of time lost shall be made up on the next or subsequent days. Otherwise, the number of overs lost will be made up on the next or subsequent days.

- 12.11.5.1 Where appropriate the first 30 minutes (or less) of the additional time under 12.11.4 will be added prior to the scheduled start of the first session, and the remainder shall be added to the middle session.
- 12.11.5.2 If the middle session has been extended beyond the scheduled 2 hours, 12.11.4 shall not apply. That is, the length of the session shall remain fixed and any additional time required under 12.11.4 shall be added to the last session.
- 12.11.5.3 In circumstances where it is not possible to add this additional time prior to the scheduled start of the first session, the timing of the Lunch and Tea intervals (Tea and Dinner in a day/night match) will be adjusted to provide for a scheduled 2.5 hour session and not affect the start time.

- 12.11.5.4 On any day's play, except the last day, when the scheduled hours of play have been completed, but the required number of overs have not been bowled and adverse ground, weather or light causes play for that day to be abandoned, the overs which have not been bowled on that day shall be made up on the next or subsequent days.
- 12.11.5.5 On any one day, a maximum of 16 additional overs shall be permitted. When additional time is added to subsequent day(s), no scheduled day's play shall exceed 7 hours. That is, the scheduled cessation time cannot be extended beyond 7 playing hours from the scheduled or rescheduled commencement time.
- 12.11.6 For all matches played in states/territories other than Queensland and Western Australia, the start time shall be brought forward by a maximum of 30 minutes. For all matches played in Queensland and Western Australia, the start time shall be brought forward by a maximum of 60 minutes.
- 12.11.7 The length of each session of play is subject to the provisions of clause 11.
- 12.11.8 In the first instance, any calculation of the minimum number of overs to be bowled in the day and the rescheduling of playing hours shall be made under 12.11.2 to 12.11.5.
- 12.11.9 Should these calculations not achieve a reasonable equalisation of session lengths or where play is further interrupted at any time on any day the umpires may adjust the timings of the Lunch and/or Tea intervals to achieve reasonable equalisation.
- 12.11.10 In Day/Night matches the total additional time and overs carried over to days 2, 3 or 4 shall all be added prior to the scheduled start of the first session and distributed over the first two sessions as per this 12.11.
- 12.11.11 When an innings ends a minimum number of overs shall be bowled from the start of the new innings. The last hour of the match shall be excluded from this calculation where 12.12 will apply. Where there is a change of innings during a day's play (except at Lunch or Tea or when play is suspended due to adverse ground, weather or light conditions or for exceptional circumstances), 2 overs will be deducted from the minimum number of overs to be bowled.

- 12.11.12 Except in the last hour of the match, where 12.12 will apply, if play is suspended due to adverse ground, weather or light for more than 1 hour in aggregate on any day, the minimum number of overs shall be reduced by one over for each full 3.75 minutes of the aggregate playing time lost on that day.

## **12.12 Last hour of the match – minimum overs**

**NOTE:** Appendix G contains examples that provide guidance on how 12.11 to 12.14 are to be applied in match situations.

- 12.12.1 On the last day, the scheduled 6 hours (96 overs minimum) are separated into two distinct parts:

12.12.1.1 scheduled 5 hours (80 overs minimum); and

12.12.1.2 1 hour (16 overs minimum).

If any of the minimum of 80 overs have not been bowled when one hour of scheduled playing time remains, the last hour will commence following the completion of those overs. In this case the scheduled drinks interval will be taken at the completion of the 80 overs and the last hour of play will commence after the drinks interval.

- 12.12.2 A minimum of 16 overs shall be bowled in the last hour and all calculations with regard to suspensions of play or the start of a new innings shall be based on one over for each full 3.75 minutes (see 12.2.2).

- 12.12.3 If at the time of commencement of the Tea interval (or Dinner for a day/night match) on the last day of a match or at any time thereafter both captains (the batsmen at the crease may be deputised to act as the captain of the batting side) accept that there is no prospect of a result to the match, they may agree to cease play at that time.

## **12.13 Over calculations**

**NOTE:** Appendix G contains examples that provide guidance on how 12.11 to 12.14 are to be applied in match situations.

- 12.13.1 Regardless of any other provision, there shall be no further play on any day, other than the last day, if the players have occasion to leave the field during:

12.13.1.1 the last minimum over or beyond; and

12.13.1.2 within 3 minutes of the scheduled or re-scheduled cessation time or thereafter.



This clause shall not apply if 12.14 is applied.

- 12.13.2 An over completed on resumption of a new day's play shall be disregarded in calculating minimum overs for that day.
- 12.13.3 Fractions are to be ignored in all final calculations regarding the number of overs, except where there is a change of innings in the day's play, when the over in progress at the conclusion of the innings shall be rounded up.
- 12.13.4 The scoreboard shall show:
  - 12.13.4.1 The total number of overs bowled with the ball currently in use; and
  - 12.13.4.2 The minimum number of overs remaining to be bowled in the day's play; and
  - 12.13.4.3 The number of overs the fielding side is above or below the target overs for the match.

## **12.14 Extra Time**

**NOTE:** Appendix G contains examples that provide guidance on how 12.11 to 12.14 are to be applied in match situations.

- 12.14.1 The umpires may decide to allow 30 minutes (a minimum of eight overs) extra playing time at the end of any day (other than the last day) if:
  - 12.14.1.1 requested by either captain; and
  - 12.14.1.2 in the umpires' opinion, it would bring about an outright result on that day.

This is in addition to the Permitted Overtime provided for in 12.11.2.1.3.
- 12.14.2 If the umpires do not believe a result can be achieved no extra time shall be allowed. If it is decided to play such extra time on one or more of these days, the whole period shall be played out even though the possibility of an outright result may have disappeared before the full period has expired.
- 12.14.3 The actual amount of playing time up to the maximum 30 minutes extra time by which play is extended on any day will be deducted from the total number of hours of play remaining, and the match shall end earlier on the final day by the amount of time by which play was previously extended under this 12.14.1.
- 12.14.4 Lunch or Tea Interval — Outright Result

The umpires may also decide that the Lunch or Tea interval will not be taken until the end of the over in progress 15 minutes (a minimum of 4 overs) after the agreed time for that interval if:

12.14.4.1 requested by either captain; and

12.14.4.2 in the umpires' opinion, an outright result can be obtained in that time.

Such time will be played out unless the result is achieved. The following session of play shall be reduced by a maximum of 15 minutes.

|  |
|--|
| <b>NOTE:</b> 12.14.4 will still apply if the Lunch or Tea interval has already been delayed by operation of clause 11.7 above. |
|--|

## **12.15 Slow over rate breaches and penalties**

12.15.1 Penalties shall apply for not completing target overs by relevant times.

12.15.2 Subject to the provisions of this clause, over rates shall be assessed at the rate of 3.75 minutes per over, with a minimum of 96 overs to be bowled in a six hour day, subject to the following allowances:

12.15.2.1 **2 minutes** for every wicket taken which results in the subsequent batsman immediately commencing his innings. For the avoidance of doubt no allowance shall be given for the final wicket in an innings or for a wicket that falls prior to an interval.

12.15.2.2 **4 minutes** for each drinks break taken in any session.

12.15.2.3 **Actual time** where treatment by authorised medical personnel is required on the field of play and/or for a player leaving the field due to serious injury.

12.15.3 Over rates will be calculated at the end of the match.

12.15.4 After taking into account the provisions of 12.11 to 12.14 and the permitted allowances pursuant to 12.15.2, if a team has failed to bowl the required number of overs in the match after consultation with the match umpires and the scorers ("**over rate breach**"), the team will be penalised as follows (unless determined otherwise by the Match Referee):

- 12.15.4.1 1 match point per full over that was not completed in the scheduled time across the match will be deducted from the team's match points; and
- 12.15.4.2 the captain of the team will incur one strike for the over rate breach; and
- 12.15.4.3 for every two strikes imposed on a captain in respect of over rate breaches committed in a season within the same match format, the captain will be suspended for the next match for which he is available for selection in that format, regardless of whether that match is in the same or the next season. No strikes incurred by a captain in respect of an over rate breach will be carried over into the next season.

**NOTE:** A team must have **completed** bowling its required number of overs in the allocated time (after applicable allowances). For clarity, it is not sufficient to have commenced but not completed the final over to be bowled before expiry of the allocated time (after applicable allowances).

For clarity, a Team will be assessed as being a **full over** behind for every full 3.75 minute-block it is behind the allocated time (after applicable allowances).

For example, where a Team completes its necessary overs 10 minutes after the allocated time for completion, then it will be ruled as being 2 overs behind ( $10 / 3.75 = 2.67$  overs behind).

- 12.15.5 For the purposes of 12.15.4.2 to 12.5.4.3 above, if the player nominated as captain at the start of the season is in the starting 11 but not listed on the official team sheet as the captain:
- 12.15.5.1 any previous strike will carry over to the player nominated as captain for that match; and
- 12.15.5.2 should another over rate breach occur in this situation, both the originally nominated captain and the player nominated as captain for that match will incur an automatic 1 match suspension and that suspension shall be applied to the next match of the same format for which they are available for selection individually, regardless of whether that match is in the same or the next season.

- 12.15.6 In determining whether a team has fallen short of the target number of overs, umpires may take into account any factor they consider relevant, including whether inclement weather has adversely affected the ability of the team to comply with the required over rate.
- 12.15.7 A Commissioner appointed by Cricket Australia will hear and determine all appeals against penalties imposed.
- 12.15.8 Appeals must be lodged within 3 business days of the completion of the match or commencement of the team's next match in the same competition (whichever is sooner).
- 12.15.8.1 A \$5000 up front fee is to be paid by the appealing team with it being refunded either in part or full if appeal is successful or appeal is deemed as not frivolous by a Code of Conduct Commissioner
- 12.15.9 The onus is on the appellant to prove that the umpires have erred in their assessment of time allowances. Video evidence (where available) may be produced by the appellant in support of the appeal. Umpires will be required to record all delays and stoppages on the appropriate form.
- 12.15.10 For calculation of penalties:
- 12.15.10.1 the scheduled last hour of the match, as defined in 12.11.12. and 12.12 will be excluded.
- 12.15.10.2 a maximum allowance of 20 overs in any hour shall apply.
- 12.15.10.3 in the event of a match finishing within the first three scheduled playing days, penalties for not achieving the required over rates shall not apply, regardless of the hours played on those days.

## **13 INNINGS**

### **13.1 Number of innings**

- 13.1.1 A match shall be two innings per side.

### **13.2 Alternate innings**

Each side shall take their innings alternately except in the cases provided for in clause 14 (The follow-on) or in clause 15.2 (Forfeiture of an innings).

### **13.3 Completed innings**

A side's innings is to be considered as completed if any of the following applies:

- 13.3.1 the side is all out.
- 13.3.2 at the fall of a wicket or the retirement of a batsman, further balls remain to be bowled but no further batsman is available to come in.
- 13.3.3 the captain declares the innings closed.
- 13.3.4 the captain forfeits the innings.

### **13.4 The toss**

The captains shall toss a coin for the choice of innings, on the field of play and in the presence of the Match Referee, not earlier than 45 minutes, nor later than 15 minutes before the scheduled or any rescheduled time for the start of play. Note, however, the provisions of clause 1.3 (Captain).

### **13.5 Decision to be notified**

As soon as the toss is completed, the captain of the side winning the toss shall decide whether to bat or to field and shall notify the opposing captain and the Match Referee of this decision immediately. Once notified, the decision cannot be changed.

### **13.6 Match Duration**

A match will be scheduled for a duration of 4 days unless otherwise advised by Cricket Australia.

## **14 THE FOLLOW-ON**

### **14.1 Lead on first innings**

- 14.1.1 In the Sheffield Shield Final, the side which bats first and leads by at least 200 runs shall have the option of requiring the other side to follow their innings.
- 14.1.2 The same option shall be available in two-innings matches of shorter duration with the minimum leads as follows:
  - 14.1.2.1 150 runs in a match of 3 or 4 days;
  - 14.1.2.2 100 runs in a 2-day match;
  - 14.1.2.3 75 runs in a 1-day match.

## **14.2 Notification**

A captain shall notify the opposing captain and the umpires of his intention to take up this option. Once notified, the decision cannot be changed.

## **14.3 First day's play lost**

- 14.3.1 If the first day's play is lost, the match becomes a three day match (or a four day match for the Final), even though there are provisions to make up lost time. Refer to clauses 12.14 to 12.16. If no play takes place on the first day of a match of more than one day's duration, 14.1 shall apply in accordance with the number of days remaining from the start of play. The day on which play first commences shall count as a whole day for this purpose, irrespective of the time at which play starts.
- 14.3.2 Play will have taken place as soon as, after the call of Play, the first over has started. See clause 17.2 (Start of an over).

# **15 DECLARATION AND FORFEITURE**

## **15.1 Time of declaration**

The captain of the side batting may declare an innings closed, when the ball is dead, at any time during the innings. A declared innings shall be considered to be a completed innings.

## **15.2 Forfeiture of an innings**

A captain may forfeit either of his side's innings at any time before the commencement of that innings. A forfeited innings shall be considered to be a completed innings.

## **15.3 Notification**

A captain shall notify the opposing captain and the umpires of any decision to declare or to forfeit an innings. Once notified, the decision cannot be changed.

# **16 THE RESULT**

## **16.1 A Win – two-innings match**

The side which has scored a total of runs in excess of that scored in the two completed innings of the opposing side shall win the match. See clause 13.3 (Completed innings). Note also 16.6.

## **16.2 Umpires awarding a match**

- 16.2.1 A match shall be lost by a side which either concedes defeat or in the opinion of the umpires refuses to play. If so, the umpires shall award the match to the other side.
- 16.2.2 If an umpire considers that an action by any player or players might constitute a refusal by either side to play then the umpires together shall ascertain the cause of the action. If they then decide together that this action does constitute a refusal to play by one side, they shall so inform the captain of that side. If the captain persists in the action the umpires shall award the match in accordance with 16.3.1. See also clause 42.3 (Captain refusing to remove a player from the field).
- 16.2.3 If action as in 16.2.2 takes place after play has started and does not constitute a refusal to play:
- 16.2.3.1 playing time lost shall be counted as lost from the call of Time to the call of Play, excluding intervals (Law 11) and suspensions of play (Law 2.8).
  - 16.2.3.2 the time for close of play on that day shall be extended by this length of time, subject to clause 2.8 (Suspension of play in dangerous or unreasonable conditions).
  - 16.2.3.3 if applicable, no overs shall be deducted during the last hour of the match solely on account of this time.

## **16.3 All other matches – A Tie or Draw**

- 16.3.1 A Tie
- The result of a match shall be a Tie when all innings have been completed and the scores are equal.
- 16.3.2 A Draw
- The result of a match shall be a Draw when it is not determined in any of the ways stated in 16.1, 16.2 or 16.3.1.

## **16.4 Winning hit or extras**

- 16.4.1 As soon as a result is reached as defined in 16.1, 16.2 16.3.1, the match is at an end. Nothing that happens thereafter, except as in clause 41.18.2 (Penalty runs), shall be regarded as part of it. Note also 16.7.

- 16.4.2 The side batting last will have scored enough runs to win only if its total of runs is sufficient without including any runs completed by the batsmen before the completion of a catch, or the obstruction of a catch, from which the striker could be dismissed.
- 16.4.3 If a boundary is scored before the batsmen have completed sufficient runs to win the match, the whole of the boundary allowance shall be credited to the side's total and, in the case of a hit by the bat, to the striker's score.

## **16.5 Statement of result**

If the side batting last wins the match without losing all its wickets, the result shall be stated as a win by the number of wickets still then to fall.

If, without having scored a total of runs in excess of the total scored by the opposing side, the innings of the side batting last has been completed, but as the result of an award of 5 Penalty runs its total of runs is then sufficient to win, the result shall be stated as a win to that side by Penalty runs.

If the side fielding last wins the match, the result shall be stated as a win by runs.

If the match is decided by one side conceding defeat or refusing to play, the result shall be stated as Match Conceded or Match Awarded, as the case may be.

## **16.6 Correctness of result**

Any decision as to the correctness of the scores shall be the responsibility of the umpires. See clause 2.15 (Correctness of scores). Any query on the result of the match will be resolved as soon as possible and a final decision made by the umpires at close of play.

## **16.7 Mistakes in scoring**

If, after the players and umpires have left the field in the belief that the match has been concluded, the umpires discover that a mistake in scoring has occurred which affects the result then, subject to 16.10, they shall adopt the following procedure:



- 16.7.1 If, when the players leave the field, the side batting last has not completed its innings and either the number of overs to be bowled in the last hour, or in that innings, has not been completed or the agreed time for close of play, or for the end of the innings, has not been reached then, unless one side concedes defeat, the umpires shall order play to resume.

Unless a result is reached sooner, play will then continue, if conditions permit, until the prescribed number of overs has been completed and either time for close of play has been reached or the allotted time for the innings has expired, as appropriate. The number of overs and time remaining shall be taken as they were at the call of Time for the supposed conclusion of the match. No account shall be taken of the time between that moment and the resumption of play.

- 16.7.2 If, at this call of Time, the overs have been completed and no playing time remains, or if the side batting last has completed its innings, the umpires shall immediately inform both captains of the necessary corrections to the scores and to the result.

## **16.8 Result not to be changed**

Once the umpires have agreed with the scorers the correctness of the scores at the conclusion of the match – see clauses 2.15 (Correctness of scores) and 3.2 (Correctness of scores) – the result cannot thereafter be changed.

## **16.9 Match Points / Qualifying Provisions / Contrived Results**

- 16.9.1 Match Points earned by a team:

- 16.9.1.1 Outright win: **6 Points**  
16.9.1.2 Tie where both teams have completed two innings: **3 Points Each**

- 16.9.1.3 Loss: **0 Points**  
16.9.1.4 Abandoned (other than via 16.11.1.5 below) or drawn matches (irrespective of how many innings have been completed): **1 Point Each**

- 16.9.1.5** Abandoned or rescheduled/relocated matches due to inadequate pitch and/or ground preparation: **See clause 6.4**

- 16.9.1.6 Abandoned or rescheduled matches at the direction of the Cricket Australia Chief Medical Officer. Refer Clause 16.10.

## 16.9.2 Bonus Points

16.9.2.1 The following Bonus Points shall apply in addition to any Match Points.

16.9.2.2 Bonus Points will be calculated only using the statistics from the first 100 overs of each side's first innings in the match.

## 16.9.3 Batting Bonus Points:

A batting side shall receive 0.01 bonus points for every run they score over 200 runs in its innings.

## 16.9.4 Bowling Bonus Points:

A fielding side shall receive 0.1 points for each wicket taken in its bowling innings capped at a total of 1.0.

### **NOTE:**

- Bonus Points are received by a side irrespective of the match result.
- Bonus Batting Points are unlimited and apply to all runs scored in excess of 200 within the first 100 overs of the first innings. For example, if a team scores 201 they will receive 0.01 Batting Bonus Points.
- The maximum Bowling Bonus Points available is 1.0 within the first 100 overs of the first innings.

## 16.9.5 Qualifying for the Sheffield Shield Final

16.9.5.1 The two teams that have the highest aggregate of total points at the end of a season shall play off in a final for the Sheffield Shield for that season.

16.9.5.2 In the event of an equality of total points, the higher number of outright wins will determine the positions on the Sheffield Shield table.

16.9.5.3 Should there be equality in both total points and outright wins, the positions shall be determined by quotient calculated thus:

16.9.5.3.1 Divide the total number of runs scored by a team by the total number of wickets lost by it.

16.9.5.3.2 Divide the total number of runs scored against a team by the total number of wickets taken by it.

16.9.5.3.3 Divide the former (16.9.5.3.1) by the latter (16.9.5.3.2).

The team having the higher quotient shall be the higher placed team.

16.9.5.4 For the purpose of these calculations and for individual averages, a team forfeiting or declaring its innings closed shall be deemed to have lost only the number of wickets that have actually fallen.

16.9.5.5 For the purpose of these calculations and for individual averages a team forfeiting or declaring its innings closed shall be deemed to have lost only the number of wickets that have actually fallen.

#### 16.9.6 Contrived Result

16.9.6.1 Cricket Australia may investigate a match or the actions of the captains of the teams or any player involved in a match if it reasonably suspects that the competing States with or without the assistance of any other person or club have:

16.9.6.1.1 colluded to contrive the result of a match;  
or

16.9.6.1.2 unreasonably declared; or

16.9.6.1.3 forfeited an innings in the match.

16.9.6.2 Cricket Australia may conduct such investigations as it sees fit and invite submissions about the match or the conduct of either captain or any player, and will give interested parties, including representatives of both teams involved, the chance to be heard on the relevant matters.

16.9.6.3 If Cricket Australia finds that the team/s, official/s, captain/s or player/s have unfairly contrived the outcome of a match to the detriment of any other team in the competition, it may in its absolute discretion do one or more of the following:

16.9.6.3.1 fine a team, captain, official or player;

- 16.9.6.3.2 suspend a captain from playing in any match or matches;
  - 16.9.6.3.3 disallow any points earned by a team in respect of the match;
  - 16.9.6.3.4 amend any points earned by a team in the match; and/or
  - 16.9.6.3.5 take such other action as is deemed appropriate.
- 16.9.6.4 In this clause, “unfairly contrived the outcome of a match” means an agreement or action designed to contrive the outcome of a match in favour of a team or to achieve a result that is unfair to any of the other teams in the same competition. The operation of this clause is not intended to prevent captains from making aggressive declarations with a view to giving either side the chance of achieving an outright win.
- 16.9.6.5 Nothing in this 16.9.6 prevents Cricket Australia from taking any action/s under the Cricket Australia Code of Conduct or Anti-Corruption Code in relation to conduct captured by this clause.

## **16.10 COVID-19**

- 16.10.1 The Cricket Australia Chief Medical Officer has the power to make a direction to Cricket Australia that a match cannot proceed as scheduled or, if already underway, be suspended from being further played due to events including, but not limited to;
- 16.10.1.1 a direction of a State or Federal Government impacting the ability for a team to participate in the match due to COVID-19;
  - 16.10.1.2 a direction of the relevant Public Health Authority arising from or in relation to a case of COVID-19 impacting the ability for a team to participate in the match;
  - 16.10.1.3 a case (or suspected case) of COVID-19 impacting the ability for a team to participate in the match, as determined by the Cricket Australia Chief Medical Officer.
- 16.10.2 In the first instance and if possible, where a match is abandoned in accordance with section 16.10.1 above, that match will be rescheduled by Cricket Australia (in its absolute discretion).

Cricket Australia will determine the venue of the rescheduled match, taking into consideration the availability of venue and teams participating in the match.

- 16.10.3 Where a match is unable to be rescheduled in accordance with section 16.10.2 above, the Cricket Australia Head of Integrity & Security will determine whether a participating team (or player or support staff) is at fault. A team will be at fault where:

16.10.3.1 the team facilitates a breach of the Biosecurity Operations Plan by any player or support staff; or

16.10.3.2 the player or support staff breaches the COVID-19 Directive.

NOTE: If the Player or Player Support staff's alleged breach of the COVID Directive is reasonably likely to be dealt with as an alleged breach by the player or player support staff of the Code of Conduct, that process should first be completed under the Code of Conduct, and the CA Head of Integrity will abide by the outcome of that process in making their determination under this provision.

- 16.10.4 **NO FAULT:** If the scheduled match cannot be rescheduled, each team will be awarded:

16.10.4.1 3 points; plus

16.10.4.2 the average total bonus points that were accumulated per team across the other two matches played in the round of the abandoned match.

- 16.10.5 **TEAM AT FAULT:** Where a team (or player or support staff) is at fault as determined by section 16.10.3, the non-offending team will be awarded: 6 points plus the average bonus points of the other 2 matches within the same round of fixtures. Nothing in this section 16.10 prevents Cricket Australia from taking any action/s under the COVID-19 Directive for State Associations and W/BBL Teams and the relevant COVID-19 Directive for Players, Player Support Personnel and Match Officials in relation to such breaches.

- 16.10.6 A Commissioner appointed by Cricket Australia will hear and determine all appeals against penalties imposed under Clause 16.10

16.10.7 Appeals must be lodged within 3 business days of the determination that the match cannot be rescheduled

16.10.7.1 A \$5000 up-front fee is to be paid by the appealing team with it being refunded either in part or full if appeal is successful or appeal is deemed as not frivolous by a Code of Conduct Commissioner

16.10.8 The onus is on the appellant to prove that the CA Head of Integrity & Security erred in determining that the participating team (or player or player support staff) was at fault.

## **17 THE OVER**

### **17.1 Number of balls**

The ball shall be bowled from each end alternately in overs of 6 balls.

### **17.2 Start of an over**

An over has started when the bowler starts his run-up or, if there is no run-up, starts his action for the first delivery of that over.

### **17.3 Validity of balls**

17.3.1 A ball shall not count as one of the 6 balls of the over unless it is delivered, even though, as in clause 41.16 (Non-striker leaving his ground early) a batsman may be dismissed or some other incident occurs without the ball having been delivered.

17.3.2 A ball delivered by the bowler shall not count as one of the 6 balls of the over

17.3.2.1 if it is called dead, or is to be considered dead, before the striker has had an opportunity to play it. See clause 20.6 (Dead ball; ball counting as one of over).

17.3.2.2 if it is called dead in the circumstances of clause 20.4.2.6. Note also the special provisions of clause 20.4.2.5.

17.3.2.3 if it is a No ball. See clause 21 (No ball).

17.3.2.4 if it is a Wide. See clause 22 (Wide ball).

17.3.2.5 when any of clauses 24.4 (Player returning without permission), 28.2 (Fielding the ball), 41.4 (Deliberate attempt to distract striker), or 41.5 (Deliberate distraction, deception or obstruction of batsman) is applied.

- 17.3.3 Any deliveries other than those listed in 17.3.1 and 17.3.2 shall be known as valid balls. Only valid balls shall count towards the 6 balls of the over.

## **17.4 Call of Over**

When 6 valid balls have been bowled and when the ball becomes dead, the umpire shall call Over before leaving the wicket. See also clause 20.3 (Call of Over or Time).

## **17.5 Umpire miscounting**

- 17.5.1 If the umpire miscounts the number of valid balls, the over as counted by the umpire shall stand.
- 17.5.2 If, having miscounted, the umpire allows an over to continue after 6 valid balls have been bowled, they may subsequently call Over when the ball becomes dead after any delivery, even if that delivery is not a valid ball.
- 17.5.3 Whenever possible, the third umpire shall liaise with the scorers and, if possible, inform the on-field umpires if an over has been miscounted.

## **17.6 Bowler changing ends**

A bowler shall be allowed to change ends as often as desired, provided he does not bowl two overs consecutively, nor bowl parts of each of two consecutive overs, in the same innings.

## **17.7 Finishing an over**

- 17.7.1 Other than at the end of an innings, a bowler shall finish an over in progress unless incapacitated or suspended under any of the clauses.
- 17.7.2 If for any reason, other than the end of an innings, an over is left uncompleted at the start of an interval or interruption, it shall be completed on resumption of play.

## **17.8 Bowler incapacitated or suspended during an over**

If for any reason a bowler is incapacitated while running up to deliver the first ball of an over, or is incapacitated or suspended during an over, the umpire shall call and signal Dead ball. Another bowler shall complete the over from

the same end, provided that he does not bowl two overs consecutively, nor bowl parts of each of two consecutive overs, in that innings.

## **18 SCORING RUNS**

### **18.1 A run**

The score shall be reckoned by runs. A run is scored:

- 18.1.1 so often as the batsmen, at any time while the ball is in play, have crossed and made good their ground from end to end.
- 18.1.2 when a boundary is scored. See clause 19 (Boundaries).
- 18.1.3 when Penalty runs are awarded. See 18.6.

### **18.2 Runs disallowed**

- 18.2.1 Wherever in these clauses provision is made for the scoring of runs or awarding of penalties, such runs and penalties will be subject to any provisions that may be applicable for the disallowance of runs or for the non-award of penalties.
- 18.2.2 When runs are disallowed, the one run penalty for No ball or Wide shall stand and 5 run penalties shall be allowed, except for Penalty runs under clause 28.3 (Protective helmets belonging to the fielding side).

### **18.3 Short runs**

- 18.3.1 A run is short if a batsman fails to make good his ground in turning for a further run.
- 18.3.2 Although a short run shortens the succeeding one, the latter if completed shall not be regarded as short. A striker setting off for the first run from in front of the popping crease may do so also without penalty.

### **18.4 Unintentional short runs**

Except in the circumstances of 18.5:

- 18.4.1 if either batsman runs a short run, the umpire concerned shall, unless a boundary is scored, call and signal short run as soon as the ball becomes dead and that run shall not be scored.



- 18.4.2 if, after either or both batsmen run short, a boundary is scored the umpire concerned shall disregard the short running and shall not call or signal short run.
- 18.4.3 if both batsmen run short in one and the same run, this shall be regarded as only one short run.
- 18.4.4 if more than one run is short then, subject to 18.4.2 and 18.4.3, all runs called as short shall not be scored.
- 18.4.5 if there has been more than one short run, the umpire shall inform the scorers as to the number of runs to be recorded.

## **18.5 Deliberate short runs**

- 18.5.1 If either umpire considers that one or both batsmen deliberately ran short at that umpire's end, the umpire concerned shall, when the ball is dead, call and signal Short run and inform the other umpire of what has occurred and apply 18.5.2.
- 18.5.2 The bowler's end umpire shall:
- 18.5.2.1 disallow all runs to the batting side;
  - 18.5.2.2 return any not out batsman to his original end;
  - 18.5.2.3 signal No ball or Wide to the scorers, if applicable;
  - 18.5.2.4 award 5 Penalty runs to the fielding side;
  - 18.5.2.5 award any other 5-run Penalty that is applicable except for Penalty runs under clause 28.3 (Protective helmets belonging to the fielding side);
  - 18.5.2.6 inform the scorers as to the number of runs to be recorded; and
  - 18.5.2.7 inform the captain of the fielding side and, as soon as practicable, the captain of the batting side of the reason for this action.
- 18.5.3 The umpires together may report the occurrence under the Code of Conduct as soon as possible after the day's play to the Match Referee, who shall take such action as is considered appropriate against the captain, any other individuals concerned and, if appropriate, the team.

## **18.6 Runs awarded for penalties**

- 18.6.1 Runs awarded for penalties

Runs shall be awarded for penalties under 18.5, and Laws 21 (*No ball*), 22 (*Wide ball*), 24.4 (*Player returning without permission*), 26.4 (*Penalties for contravention*), 28.2 (*Fielding the ball*), 28.3 (*Protective helmets belonging to the fielding side*), 41 (*Unfair play*) and 42 (*Players' conduct*).

Note, however, the restrictions on the award of Penalty runs in Laws 18.5, (*Leg byes not to be awarded*), 25.6.5 (*Dismissal and conduct of a batsman and his runner*), 25.7 (*Restriction on the striker's runner*), 28.3 (*Protective helmets belonging to the fielding side*), 34 (*Hit the ball twice*), 41.14 (*Batsman damaging the pitch*) and 41.15 (*Striker in protected area*).

### **18.7 Runs scored for boundaries**

Runs shall be scored for boundary allowances under clause 19 (Boundaries).

### **18.8 Runs scored when a batsman is dismissed**

When a batsman is dismissed, any runs for penalties awarded to either side shall stand. No other runs shall be credited to the batting side, except as follows:

- 18.8.1 If a batsman is dismissed Obstructing the field, the batting side shall also score any runs completed before the offence.

If, however, the obstruction prevented a catch being made, no runs other than penalties shall be scored.

- 18.8.2 If a batsman is dismissed Run out, the batting side shall also score any runs completed before the wicket was put down.

### **18.9 Runs scored when the ball becomes dead other than at the fall of a wicket**

- 18.9.1 When the ball becomes dead for any reason other than the fall of a wicket, or is called dead by an umpire, unless there is specific provision otherwise in the clauses, any runs for penalties awarded to either side shall be scored. Note however the provisions of clauses 23.3 (*Leg byes not to be awarded*) and 28.3 (*Protective helmets belonging to the fielding side*).

- 18.9.2 Additionally the batting side shall be credited with, all runs completed by the batsmen before the incident or call of Dead ball and the run in progress if the batsmen had already crossed at the instant of the incident or call of Dead ball. Note specifically, however, the provisions of clause 41.5.8 (*Deliberate distraction, deception or obstruction of batsman*).

## **18.10 Crediting of runs scored**

Unless stated otherwise in any of the clauses:

- 18.10.1 if the ball is struck by the bat, all runs scored by the batting side shall be credited to the striker, except for the following:
  - 18.10.1.1 an award of 5 Penalty runs, which shall be scored as Penalty runs; and
  - 18.10.1.2 the 1 run penalty for a No ball, which shall be scored as a No balls extra.
- 18.10.2 if the ball is not struck by the bat, runs shall be scored as Penalty runs, Byes, Leg byes, No ball extras or Wides as the case may be. If Byes or Leg byes accrue from a No ball, only the one run penalty for No ball shall be scored as such, and the remainder as Byes or Leg byes as appropriate.
- 18.10.3 the bowler shall be debited with:
  - 18.10.3.1 all runs scored by the striker;
  - 18.10.3.2 all runs scored as No ball extras; and
  - 18.10.3.3 all runs scored as Wides.

## **18.11 Batsman returning to original end**

- 18.11.1 When the striker is dismissed in any of the circumstances in 18.11.1.1 to 18.11.1.6, the not out batsman shall return to his original end.
  - 18.11.1.1 A dismissal in the circumstances of clause 25.6.4 or 25.6.5.
  - 18.11.1.2 Bowled.
  - 18.11.1.3 Stumped.
  - 18.11.1.4 Hit the ball twice.
  - 18.11.1.5 LBW.
  - 18.11.1.6 Hit wicket.
- 18.11.2 The batsmen shall return to their original ends in any of the cases of 18.11.2.1 to 18.11.2.3.
  - 18.11.2.1 A boundary is scored.
  - 18.11.2.2 Runs are disallowed for any reason.

- 18.11.2.3 A decision by the batsmen at the wicket to do so, under clause 41.5 (Deliberate distraction, deception or obstruction of batsman).

## **18.12 Batsman returning to wicket he has left**

- 18.12.1 When a batsman is dismissed in any of the ways in 18.12.1.1 to 18.12.1.3, the not out batsman shall return to the wicket he has left but only if the batsmen had not already crossed at the instant of the incident causing the dismissal. If runs are to be disallowed, however, the not out batsman shall return to his original end.

18.12.1.1 Caught

18.12.1.2 Obstructing the field

18.12.1.3 Run out other than under clause 25.6.4 or 25.6.5.

- 18.12.2 If, while a run is in progress, the ball becomes dead for any reason other than the dismissal of a batsman, the batsmen shall return to the wickets they had left, but only if they had not already crossed in running when the ball became dead. If, however, any of the circumstances of 18.11.2.1 to 18.11.2.3 apply, the batsmen shall return to their original ends.

## **19 BOUNDARIES**

### **19.1 Determining the boundary of the field of play**

- 19.1.1 Before the toss, the umpires shall determine the boundary of the field of play, which shall be fixed for the duration of the match. See clause 2.3.1.4.
- 19.1.2 The boundary shall be determined such that no part of any sight-screen, will, at any stage of the match, be within the field of play.
- 19.1.3 The aim shall be to provide the largest playing area, subject to no boundary exceeding 82.29 metres (90 yards) from the centre of the pitch to be used.

### **19.2 Identifying and marking the boundary**

- 19.2.1 All boundaries must be designated by a rope or similar object of a minimum standard as authorised by Cricket Australia from time to time.

- 19.2.2 At all times, the rope or similar object must be placed a minimum distance of 4metres (4.37 yards) inside the perimeter fencing, advertising signs or any other hard or immovable object inside the perimeter fencing or advertising signs.

**NOTE:** Hard or immovable objects include (but are not limited to): broadcast cameras and tripods/stands, tables, dugout infrastructure, marquees, TVs, speakers, unpadded drinks eskies, non-plastic chairs, and all posts, poles and other hard infrastructure. As far as reasonably practicable, Match Managers must also eliminate all other hazards in the boundary area, such as kit bags, strength and conditioning gear, broadcast Segway and unnecessary people.

- 19.2.3 If the boundary is marked by means of:
- 19.2.3.1 a white line, the edge of the line nearest the pitch shall be the boundary.
  - 19.2.3.2 an object such as a flag, post or board, used merely to highlight the position of a line marked on the ground, must be placed beyond the boundary and is not itself to be regarded as being the boundary.
  - 19.2.3.3 an object that is in contact with the ground the boundary will be the edge of the grounded part of the object which is nearest the pitch.
- 19.2.4 A boundary that cannot be identified as in 19.2.2, 19.2.3 or 19.2.4 shall be determined by the umpires before the toss.
- 19.2.5 An obstacle within the field of play, other than as in 19.2.6, shall not be regarded as a boundary unless so determined by the umpires before the toss. See clause 2.3.1.4.
- 19.2.6 If an unauthorised person or animal enters the playing arena and comes into contact with the ball, the umpire at the bowler's end shall be the sole judge of whether the boundary allowance should be scored or the ball be treated as still in play or called dead ball if a batsman is liable to be out as a result.

### **19.3 Restoring the boundary**

If a solid object used to mark the boundary is disturbed for any reason, then:

- 19.3.1 the boundary shall be considered to be in its original position.

- 19.3.2 the object shall be returned to its original position as soon as is practicable. If play is taking place, this shall be as soon as the ball is dead.
- 19.3.3 if some part of a fence or other marker has come within the field of play, that part shall be removed from the field of play as soon as is practicable. If play is taking place, this shall be as soon as the ball is dead.

#### **19.4 Ball grounded beyond the boundary**

- 19.4.1 The ball in play is grounded beyond the boundary if it touches:
  - 19.4.1.1 the boundary or any part of an object used to mark the boundary;
  - 19.4.1.2 the ground beyond the boundary; or
  - 19.4.1.3 any object that is grounded beyond the boundary.
- 19.4.2 The ball in play is to be regarded as being grounded beyond the boundary if:
  - 19.4.2.1 a fielder, grounded beyond the boundary as in 19.5, touches the ball; or
  - 19.4.2.2 a fielder, after catching the ball within the boundary, becomes grounded beyond the boundary while in contact with the ball, before completing the catch.

#### **19.5 Fielder grounded beyond the boundary**

- 19.5.1 A fielder is grounded beyond the boundary if some part of his person is in contact with any of the following:
  - 19.5.1.1 the boundary or any part of an object used to mark the boundary;
  - 19.5.1.2 the ground beyond the boundary;
  - 19.5.1.3 any object that is in contact with the ground beyond the boundary; or
  - 19.5.1.4 another fielder who is grounded beyond the boundary
- 19.5.2 A fielder who is not in contact with the ground is considered to be grounded beyond the boundary if his final contact with the ground, before his first contact with the ball after it has been delivered by the bowler, was not entirely within the boundary.

#### **19.6 Boundary allowances**

- 19.6.1 Before the toss the umpires shall agree the runs to be allowed for boundaries with both captains. In deciding the allowances the umpires and captains shall be guided by the prevailing custom of the ground.
- 19.6.2 Unless agreed differently under 19.6.1, 6 runs shall be allowed for a boundary 6; and 4 runs for a boundary 4. See also 19.7.

## **19.7 Runs scored from boundaries**

- 19.7.1 A Boundary 6 will be scored if and only if the ball has been struck by the bat and is first grounded beyond the boundary without having been in contact with the ground within the field of play. This shall apply even if the ball has previously touched a fielder.
- 19.7.2 A Boundary 4 will be scored when a ball that is grounded beyond the boundary
- 19.7.2.1 whether struck by the bat or not, was first grounded within the boundary, or
  - 19.7.2.2 has not been struck by the bat.
- 19.7.3 When a boundary is scored, the batting side, except in the circumstances of 19.8, shall be awarded whichever is the greater of:
- 19.7.3.1 the allowance for the boundary; or
  - 19.7.3.2 the runs completed by the batsmen together with the run in progress if they had already crossed at the instant the boundary is scored.
- 19.7.4 When the runs in 19.7.3.2 exceed the boundary allowance they shall replace the boundary allowance for the purposes of clause 18.12.1.
- 19.7.5 The scoring of Penalty runs by either side is not affected by the scoring of a boundary.

## **19.8 Overthrow or wilful act of fielder**

If the boundary results from an overthrow or from the wilful act of a fielder, the runs scored shall be:

- 19.8.1 any runs for penalties awarded to either side; and
- 19.8.2 the allowance for the boundary; and

- 19.8.3 the runs completed by the batsmen, together with the run in progress if they had already crossed at the instant of the throw or act.

Clause 18.12.2 (Batsman returning to wicket they have left) shall apply as from the instant of the throw or act.

## **20 DEAD BALL**

### **20.1 Ball is dead**

- 20.1.1 The ball becomes dead when:

20.1.1.1 it is finally settled in the hands of the wicket-keeper or of the bowler.

20.1.1.2 a boundary is scored. See clause 19.7 (Runs scored from boundaries).

20.1.1.3 a batsman is dismissed. The ball will be deemed to be dead from the instant of the incident causing the dismissal.

20.1.1.4 whether played or not it becomes trapped between the bat and person of a batsman or between items of his clothing or equipment.

20.1.1.5 whether played or not it lodges in the clothing or equipment of a batsman or an umpire.

20.1.1.6 there is an award of Penalty runs under either of clauses 24.4 (Player returning without permission) or 28.2 (Fielding the ball). The ball shall not count as one of the over.

20.1.1.7 there is contravention of clause 28.3 (Protective helmets belonging to the fielding side).

20.1.1.8 the match is concluded in any of the ways stated in clause 12.9 (Conclusion of match).

- 20.1.2 The ball shall be considered to be dead when it is clear to the bowler's end umpire that the fielding side and both batsmen at the wicket have ceased to regard it as in play.

### **20.2 Ball finally settled**



Whether the ball is finally settled or not is a matter for the umpire alone to decide.

### **20.3 Call of Over or Time**

Neither the call of Over (see clause 17.4), nor the call of Time (see clause 12.2) is to be made until the ball is dead, either under 20.1 or under 20.4.

### **20.4 Umpire calling and signalling Dead ball**

20.4.1 When the ball has become dead under 20.1, the bowler's end umpire may call and signal Dead ball if it is necessary to inform the players.

20.4.2 Either umpire shall call and signal Dead ball when:

- 20.4.2.1 intervening in a case of unfair play.
- 20.4.2.2 a possibly serious injury to a player or umpire occurs.
- 20.4.2.3 leaving their normal position for consultation.
- 20.4.2.4 one or both bails fall from the striker's wicket before the striker has had the opportunity of playing the ball.
- 20.4.2.5 the striker is not ready for the delivery of the ball and, if the ball is delivered, makes no attempt to play it. Provided the umpire is satisfied that the striker had adequate reason for not being ready, the ball shall not count as one of the over.
- 20.4.2.6 the striker is distracted by any noise or movement or in any other way while preparing to receive, or receiving a delivery. This shall apply whether the source of the distraction is within the match or outside it. Note also 20.4.2.7. The ball shall not count as one of the over.
- 20.4.2.7 there is an instance of a deliberate attempt to distract under either of clauses 41.4 (Deliberate attempt to distract striker) or 41.5 (Deliberate distraction, deception or obstruction of batsman). The ball shall not count as one of the over.
- 20.4.2.8 the bowler drops the ball accidentally before delivery.
- 20.4.2.9 the ball does not leave the bowler's hand for any reason other than an attempt to run out the non-striker under clause 41.16 (Non-striker leaving his ground early).

- 20.4.2.10 satisfied that the ball in play cannot be recovered.
- 20.4.2.11 required to do so under any of the clauses not included above.
- 20.4.3 For matches where cameras are being used on or over the field of play, the following will also apply:
  - 20.4.3.1 Either umpire shall call and signal dead ball, should a ball that has been hit by the batsman make contact, while still in play, with the camera, its apparatus or its cable. The ball shall not count as one of the over and no runs shall be scored. If, however, the delivery had already been called a No ball, then the No ball shall count and the No ball penalty applied. No other runs (including penalty runs) apart from the No ball penalty shall be scored. For the sake of clarity, no warnings, penalties, or other actions by the players will be taken into account for the purpose of this clause other than the No ball infringement.
  - 20.4.3.2 Should a ball thrown by a fielder make contact with a camera on or over the field of play, its apparatus or its cable, either umpire shall call and signal dead ball. If, however, the delivery had already been called a No ball or Wide, the ball shall count as one of the over. All runs scored to that point shall count, plus the run in progress if the batsmen have already crossed.

## **20.5 Ball ceases to be dead**

The ball ceases to be dead – that is, it comes into play – when the bowler starts his run-up or, if there is no run-up, starts his bowling action.

## **20.6 Dead ball; ball counting as one of over**

- 20.6.1 When a ball which has been delivered is called dead or is to be considered dead then, other than as in 20.6.2,
  - 20.6.1.1 it will not count in the over if the striker has not had an opportunity to play it.

- 20.6.1.2 it will be a valid ball if the striker has had an opportunity to play it, unless No ball or Wide ball has been called, except in the circumstances of 20.4.2.6 and clauses 24.4 (Fielder returning without permission), 28.2 (Fielding the ball), 41.4 (Deliberate attempt to distract striker) and 41.5 (Deliberate distraction, deception or obstruction of batsman).
- 20.6.2 In 20.4.2.5, the ball will not count in the over only if both conditions of not attempting to play the ball and having an adequate reason for not being ready are met. Otherwise the delivery will be a valid ball.

## **21 NO BALL**

### **21.1 Mode of delivery**

- 21.1.1 The umpire shall ascertain whether the bowler intends to bowl right handed or left handed, over or round the wicket, and shall so inform the striker.
- 21.1.2 It is unfair if the bowler fails to notify the umpire of a change in his mode of delivery. In this case the umpire shall call and signal No ball.
- 21.1.3 Underarm bowling shall not be permitted.

### **21.2 Fair delivery – the arm**

- 21.2.1 For a delivery to be fair in respect of the arm the ball must not be thrown.
- 21.2.2 A ball is fairly delivered in respect of the arm if, once the bowler's arm has reached the level of the shoulder in the delivery swing, the elbow joint is not straightened partially or completely from that instant until the ball has left the hand. This definition shall not debar a bowler from flexing or rotating the wrist in the delivery swing.
- 21.2.3 Although it is the primary responsibility of the striker's end umpire to assess the fairness of a delivery in this respect, there is nothing in this clause to debar the bowler's end umpire from calling and signalling No ball if they considers that the ball has been thrown.

## **21.3 Ball thrown – action by umpires**

21.3.1 If, in the opinion of either umpire, the ball has been thrown, they shall call and signal No ball and, when the ball is dead, inform the other umpire of the reason for the call. The bowler's end umpire shall then:

21.3.1.1 warn the bowler, indicating that this is a first and final warning. This warning shall apply to that bowler throughout the innings;

21.3.1.2 inform the captain of the fielding side of the reason for this action; and

21.3.1.3 inform the batsmen at the wicket of what has occurred.

21.3.2 If either umpire considers that, in that innings, a further delivery by the same bowler is thrown, they shall call and signal No ball and when the ball is dead inform the other umpire of the reason for the call.

The bowler's end umpire shall then

- direct the captain of the fielding side to suspend the bowler immediately from bowling. The over shall, if applicable, be completed by another bowler, who shall neither have bowled the previous over or part thereof nor be allowed to bowl any part of the next over. The bowler thus suspended shall not bowl again in that innings.
- inform the batsmen at the wicket and, as soon as practicable, the captain of the batting side of the reason for this action.

21.3.3 The umpires together shall report the occurrence under the Code of Conduct and/or Suspect Bowling Action Policy (as appropriate) as soon as possible after the day's play to the Match Referee, who shall take such action as is considered appropriate against the captain, any other individuals concerned and, if appropriate, the team.

## **21.4 Bowler throwing towards striker's end before delivery**

If the bowler throws the ball towards the striker's end before entering the delivery stride, either umpire shall call and signal No ball. See clause 41.17 (Batsmen stealing a run). However, the procedure stated in 21.3 of caution,

informing, final warning, action against the bowler and reporting shall not apply.

## **21.5 Fair delivery – the feet**

For a delivery to be fair in respect of the feet, in the delivery stride

21.5.1 the bowler's back foot must land within and not touching the return crease appertaining to his stated mode of delivery.

21.5.2 the bowler's front foot must land with some part of the foot, whether grounded or raised

- on the same side of the imaginary line joining the two middle stumps as the return crease described in 21.5.1, and
- behind the popping crease.

If the bowler's end umpire is not satisfied that any of these three conditions have not been met, they shall call and signal No ball. See clause 41.8 (Bowling of deliberate front foot No ball).

## **21.6 Bowler breaking wicket in delivering ball**

If the ball is delivered and if the non-striker is not dismissed under Law 41.16 (Non-striker leaving his ground early), either umpire shall call and signal No ball if the bowler breaks the wicket at any time after the ball comes into play and before completion of the stride after the delivery stride. This shall include any clothing or other object that falls from his person and breaks the wicket. See Appendix A.12. Laws 20.4.2.8, 20.4.2.9 (Umpire calling and signalling Dead ball) and 21.12 will apply.

## **21.7 Ball bouncing more than once, rolling along the ground or pitching off the pitch**

The umpire shall call and signal No ball if a ball which they consider to have been delivered, without having previously touched bat or person of the striker,

- bounces more than once
- or rolls along the ground before it reaches the popping crease.
- or pitches wholly or partially off the pitch as defined in clause 6.1 before it reaches the line of the striker's wicket.

## **21.8 Ball coming to rest in front of striker's wicket**

If a ball delivered by the bowler comes to rest in front of the line of the striker's wicket, without having previously touched the bat or person of the striker, the

umpire shall call and signal No ball and immediately call and signal Dead ball.

### **21.9 Fielder intercepting a delivery**

If a ball, delivered by the bowler, makes contact with any part of a fielder's person before it either makes contact with the striker's bat or person, or it passes the striker's wicket, the umpire shall call and signal No ball and immediately call and signal Dead ball.

### **21.10 Ball bouncing over head height of striker**

See clause 22.1.1, 41.6.2.4 and 41.6.2.5.

### **21.11 Call of No ball for infringement of other clauses**

In addition to the instances above, No ball is to be called and signalled as required by the following clauses.

Clause 27.3 – Position of wicket-keeper clause 28.4 – Limitation of on side fielders

Clause 28.5 – Fielders not to encroach on pitch

Clause 41.6 – Bowling of dangerous and unfair short pitched deliveries

Clause 41.7 – Bowling of dangerous and unfair non-pitching deliveries

Clause 41.8 – Bowling of deliberate front foot No ball.

### **21.12 Revoking a call of No ball**

An umpire shall revoke the call of No ball if Dead ball is called under any of Laws 20.4.2.4, 20.4.2.5, 20.4.2.6, 20.4.2.8 or 20.4.2.9 (Umpire calling and signalling Dead ball).

### **21.13 No ball to over-ride Wide**

A call of No ball shall over-ride the call of Wide ball at any time. See clauses 22.1 (Judging a Wide) and 22.2 (Call and signal of Wide ball).

### **21.14 Ball not dead**

The ball does not become dead on the call of No ball.

### **21.15 Penalty for a No ball**

A penalty of one run shall be awarded instantly on the call of No ball. Unless the call is revoked, the penalty shall stand even if a batsman is dismissed. It shall be in addition to any other runs scored, any boundary allowance and any other runs awarded for penalties.

### **21.16 Runs resulting from a No ball – how scored**

The one run penalty shall be scored as a No ball extra and shall be debited against the bowler. If other Penalty runs have been awarded to either side these shall be scored as stated in clause 41.18 (Penalty runs). Any runs completed by the batsmen or any boundary allowance shall be credited to the striker if the ball has been struck by the bat; otherwise they shall also be scored as Byes or Leg byes as appropriate.

### **21.17 No ball not to count**

A No ball shall not count as one of the over. See clause 17.3 (Validity of balls).

### **21.18 Out from a No ball**

When No ball has been called, neither batsman shall be out under any of the clauses except 34 (Hit the ball twice), 37 (Obstructing the field) or 38 (Run out).

## **22 WIDE BALL**

### **22.1 Judging a Wide**

22.1.1 If the bowler bowls a ball, not being a No ball, the umpire shall adjudge it a Wide if, according to the definitions in 22.1.2:

22.1.1.1 the ball passes wide of where the striker is standing and which also would have passed wide of the striker standing in a normal guard position.

22.1.1.2 the ball passes above the head height of the striker standing upright at the popping crease.

22.1.2 The ball will be considered as passing wide of the striker unless it is sufficiently within reach for him to be able to hit it with the bat by means of a normal cricket stroke.

22.1.3 If in the umpire's opinion the bowler is attempting to utilise the rough outside a batsman's leg stump, or is bowling down the leg side as a negative tactic, the umpire will call and signal a Wide unless the ball passes sufficiently within the reach of the striker for him to be able to hit it with his bat by means of a normal cricket stroke.

### **22.2 Call and signal of Wide ball**

If the umpire adjudges a delivery to be a Wide they shall call and signal Wide ball as soon as the ball passes the striker's wicket. It shall, however, be

considered to have been a Wide from the instant that the bowler entered his delivery stride, even though it cannot be called Wide until it passes the striker's wicket.

### **22.3 Revoking a call of Wide ball**

22.3.1 The umpire shall revoke the call of Wide ball if there is then any contact between the ball and the striker's bat or person before the ball comes into contact with any fielder.

22.3.2 The umpire shall revoke the call of Wide ball if a delivery is called a No ball. See clause 21.13 (No ball to over-ride Wide).

### **22.4 Delivery not a Wide**

22.4.1 The umpire shall not adjudge a delivery as being a Wide, if the striker, by moving, either causes the ball to pass wide of him, as defined in 22.1.2 or brings the ball sufficiently within reach to be able to hit it by means of a normal cricket stroke.

22.4.2 The umpire shall not adjudge a delivery as being a Wide if the ball touches the striker's bat or person, but only as the ball passes the striker.

### **22.5 Ball not dead**

The ball does not become dead on the call of Wide ball.

### **22.6 Penalty for a Wide**

A penalty of one run shall be awarded instantly on the call of Wide ball. Unless the call is revoked, see 22.3, this penalty shall stand even if a batsman is dismissed, and shall be in addition to any other runs scored, any boundary allowance and any other runs awarded for penalties.

### **22.7 Runs resulting from a Wide – how scored**

All runs completed by the batsmen or a boundary allowance, together with the penalty for the Wide, shall be scored as Wide balls. Apart from any award of 5 Penalty runs, all runs resulting from a Wide shall be debited against the bowler.

### **22.8 Wide not to count**

A Wide shall not count as one of the over. See clause 17.3 (Validity of balls).

### **22.9 Out from a Wide**

When Wide ball has been called, neither batsman shall be out under any of the clauses except 35 (Hit wicket), 37 (Obstructing the field), 38 (Run out) or 39 (Stumped).



## **23 BYE AND LEG BYE**

### **23.1 Byes**

If the ball, delivered by the bowler, not being a Wide, passes the striker without touching his bat or person, any runs completed by the batsmen from that delivery, or a boundary allowance, shall be credited as Byes to the batting side. Additionally, if the delivery is a No ball, the one run penalty for such a delivery shall be incurred.

### **23.2 Leg byes**

23.2.1 If a ball delivered by the bowler first strikes the person of the striker, runs shall be scored only if the umpire is satisfied that the striker has either attempted to play the ball with the bat or tried to avoid being hit by the ball.

23.2.2 If the umpire is satisfied that either of these conditions has been met runs shall be scored as follows.

23.2.2.1 If there is either no subsequent contact with the striker's bat or person, or only inadvertent contact with the striker's bat or person any runs completed by the batsmen or a boundary allowance shall be credited to the striker in the case of subsequent contact with his bat but otherwise to the batting side as in 23.2.3.

23.2.2.2 If the striker wilfully makes a lawful second strike, clauses 34.3 (Ball lawfully struck more than once) and 34.4 (Runs scored from ball lawfully struck more than once) shall apply.

23.2.3 The runs in 23.2.2.1, unless credited to the striker, shall be scored as Leg byes. Additionally, if the delivery is a No ball, the one run penalty for the No ball shall be incurred.

### **23.3 Leg byes not to be awarded**

- 23.3.1 If in the circumstance of 23.2.1 the umpire considers that neither of the conditions therein has been met, then Leg byes shall not be awarded.
- 23.3.2 If the ball does not become dead for any other reason, the umpire shall call and signal Dead ball as soon as the ball reaches the boundary or at the completion of the first run. The umpire shall then:
- 23.3.2.1 disallow all runs to the batting side;
  - 23.3.2.2 return any not out batsman to his original end;
  - 23.3.2.3 signal No ball to the scorers if applicable;
  - 23.3.2.4 award any 5-run Penalty that is applicable except for Penalty runs under clause 28.3 (Protective helmets belonging to the fielding side).

## **24 FIELDER'S ABSENCE; SUBSTITUTES**

### **24.1 Substitute fielders**

- 24.1.1 The umpires shall allow a substitute fielder:
- 24.1.1.1 if they are satisfied that a fielder has been injured or become ill and that this occurred during the match;
  - 24.1.1.2 for any other wholly acceptable reason; or
  - 24.1.1.3 if a Concussion Substitute is activated in accordance with Appendix C.
- In all other circumstances, a substitute is not allowed.
- 24.1.2 Other than a player activated as a Concussion Substitute, a substitute shall not bowl or act as captain but may act as wicket-keeper only with the consent of the umpires. Note, however, clause 42.4.1.
- 24.1.3 A nominated player may bowl or field even though a substitute has previously acted for him, subject to 24.2 and 24.3.

## **24.2 Fielder absent or leaving the field of play**

- 24.2.1 A player going briefly outside the boundary while carrying out any duties as a fielder is not absent from the field of play nor, for the purposes of this clause, is he to be regarded as having left the field of play.
- 24.2.2 If a fielder fails to take the field at the start of the match or at any later time, or leaves the field during play,
- 24.2.2.1 an umpire shall be informed of the reason for this absence.
- 24.2.2.2 he shall not thereafter come on to the field of play during a session of play without the consent of the umpire. See 24.4. The umpire shall give such consent as soon as it is practicable.
- 24.2.3 If a player is absent from the field for longer than 8 minutes, the following restrictions shall apply to their future participation in the match:
- 24.2.3.1 The player shall not be permitted to bowl in the match until he has either been able to field, or his team has subsequently been batting, for the total length of playing time for which the player was absent (hereafter referred to as Penalty time). A player's unexpired Penalty time shall be limited to a maximum of 120 minutes. If any unexpired Penalty time remains at the end of an innings, it is carried forward to the next and subsequent innings of the match.
- 24.2.3.2 The player shall not be permitted to bat in the match until his team's batting innings has been in progress for the length of playing time that is equal to the unexpired Penalty time carried forward from the previous innings. However, once his side has lost five wickets in its batting innings, he may bat immediately. If any unexpired Penalty time remains at the end of that batting innings, it is carried forward to the next and subsequent innings of the match.
- 24.2.4 If the player leaves the field before having served all of his Penalty time, the balance is carried forward as unserved Penalty time.

- 24.2.5 On any occasion of absence, the amount of playing time for which the player is off the field shall be added to any Penalty time that remains unserved, subject to a maximum cumulative Penalty time of 120 minutes, and that player shall not bowl until all of his Penalty time has been served.
- 24.2.6 For the purposes of 24.2.3.1 and 24.2.3.2, playing time shall comprise the time play is in progress excluding lunch and tea intervals, intervals between innings and drinks intervals. For clarity, a player's Penalty time will continue to expire after he is dismissed, for the remainder of his team's batting innings.
- 24.2.7 If there is an unscheduled break in play, the stoppage time shall count as Penalty time served, provided that,
- 24.2.7.1 the fielder who was on the field of play at the start of the break either takes the field on the resumption of play, or his side is now batting.
- 24.2.7.2 the fielder who was already off the field at the start of the break notifies an umpire in person as soon as he is able to participate, and either takes the field on the resumption of play, or his side is now batting. Stoppage time before an umpire has been so notified shall not count towards unserved Penalty time.
- 24.2.8 Any unserved Penalty time shall be carried forward into the next and subsequent days and innings of the match, as applicable.

### **24.3 Penalty time not incurred**

A nominated player's absence will not incur Penalty time if,

- 24.3.1 he has suffered an external blow during the match and, as a result, has justifiably left the field or is unable to take the field.
- 24.3.2 in the opinion of the umpires, the player has been absent or has left the field for other wholly acceptable reasons, which shall not include illness or internal injury.
- 24.3.3 the player is absent from the field for a period of 8 minutes or less.

### **24.4 Player returning without permission**

If a player comes on to the field of play in contravention of 24.2.2.2 and comes into contact with the ball while it is in play, the ball shall immediately become dead and:

- 24.4.1 The umpire shall award 5 Penalty runs to the batting side.

- 24.4.2 Runs completed by the batsmen shall be scored together with the run in progress if they had already crossed at the instant of the offence.
- 24.4.3 The ball shall not count as one of the over.
- 24.4.4 The umpire shall inform the other umpire, the captain of the fielding side, the batsmen and, as soon as practicable, the captain of the batting side of the reason for this action.
- 24.4.5 Together with the other umpire, report the occurrence under the Code of Conduct as soon as possible after the day's play to the Match Referee, who shall take such action as is considered appropriate against the captain, any other individuals concerned and, if appropriate, the team.

## **25 BATSMAN'S INNINGS**

### **25.1 Eligibility to act as a batsman**

Only a nominated player or a Concussion Substitute (activated in accordance with Appendix C) may bat and, subject to 25.3, may do so even though a substitute fielder has previously acted for him.

### **25.2 Commencement of a batsman's innings**

- 25.2.1 The innings of the first two batsmen, and that of any new batsman on the resumption of play after a call of Time, shall commence at the call of Play. At any other time, a batsman's innings shall be considered to have commenced when that batsman first steps onto the field of play.
- 25.2.2 A batsman must wear a British Standard 7928:2013 compliant helmet at all times when batting against fast or medium-paced bowling.
- 25.2.3 The umpires are the sole judge of whether bowling is fast or medium-paced and will judge the pace of bowling against what is considered "fast", "medium-paced" or "slow" within the context of that particular match.
- 25.2.4 The umpires are responsible for ensuring that a helmet is worn when required by clause 25.2.3 but are not be responsible for ensuring that the helmet being worn by the batsman is compliant with British Standard 7928:2013.

- 25.2.5 The umpires must not allow the match to continue during any period in which a batsman fails to wear a helmet when required by this clause.

### **25.3 Restriction on batsman commencing an innings**

- 25.3.1 If a member of the batting side has unserved Penalty time, see clause 24.2.7, that player shall not be permitted to bat until that Penalty time has been served. However, even if the unserved Penalty time has not expired, that player may bat after his side has lost 5 wickets.
- 25.3.2 A batsman's Penalty time is served while waiting to bat, during his innings and for the remainder of the team's innings after he is dismissed, subject to the conditions in 25.3.2.1 to 25.3.2.2.
- 25.3.2.1 The period of time for a scheduled interval does not count as Penalty time served.
- 25.3.2.2 In the event of an unscheduled stoppage, the stoppage time after the batsman notifies an umpire in person that he is able to participate shall count as Penalty time served.
- 25.3.3 If any unserved Penalty time remains at the end of a team's innings, it shall be carried forward to the next and subsequent innings of the match if appropriate.

### **25.4 Batsman retiring**

- 25.4.1 A batsman may retire at any time during his innings when the ball is dead. The umpires, before allowing play to proceed, shall be informed of the reason for a batsman retiring.
- 25.4.2 If a batsman retires because of illness, injury or any other unavoidable cause, that batsman is entitled to resume his innings unless a Concussion Substitute has been activated to replace him. If for any reason this does not happen, that batsman is to be recorded as 'Retired - not out'.
- 25.4.3 If a batsman retires for any reason other than as in 25.4.2, the innings of that batsman may be resumed only with the consent of the opposing captain. If for any reason his innings is not resumed, that batsman is to be recorded as 'Retired - out'.
- 25.4.4 If after retiring a batsman resumes his innings, subject to the requirements of 25.4.2 and 25.4.3, it shall be only at the fall of a wicket or the retirement of another batsman.

- 25.4.5 Where an injury occurs to a batsman involved in a tenth wicket partnership, a maximum of five minutes will be allowed in order for the batsman to obtain treatment. If the injury occurs within 30 minutes of a scheduled interval, the interval shall be taken immediately if the batsman is unable to resume after the five minutes. If the batsman is unable to resume after the five minutes or after the early interval, he will be recorded as “Retired – not out”.

## **25.5 Runners**

- 25.5.1 The umpires shall allow a runner for a batsman if they are satisfied
- 25.5.1.1 that the batsman has sustained an injury that affects his ability to run and
  - 25.5.1.2 that this occurred during the match
  - 25.5.1.3 that the batting side has lost its 9<sup>th</sup> wicket
- 25.5.2 A runner shall
- 25.5.2.1 be a member of the batting side
  - 25.5.2.2 be changed only with the consent of the umpires
  - 25.5.2.3 wear external protective equipment equivalent to that worn by the batsman for whom he runs and shall carry a bat
  - 25.5.2.4 not have any unserved Penalty time as described in Law 24.2.7 (Fielder absent or leaving the field of play)
- 25.5.3 A batsman's runner is subject to the Laws and will be regarded as a batsman except where there are special provisions for his role as a runner. See Law 30.2 (Which is a batsman's ground)

## **25.6 Dismissal and conduct of a batsman and his runner**

- 25.6.1 A batsman who has a runner will suffer the penalty for any infringement of the Laws by the runner as if he, the batsman, had been responsible for the infringement. In particular he will be out if

the runner is out under either of Laws 37 (Obstructing the field) or 38 (Run Out)

- 25.6.2 When a batsman who has a runner is the striker he remains subject to the Laws and will be liable to the penalties that any infringement of them demands. In the case of Run out and Stumped, however, special provisions, set out in 25.6.3, 25.6.4, and 25.6.5, apply to him as a striker who has a runner.
- 25.6.3 When a batsman who has a runner is the striker, his ground is always at the wicket-keeper's end.
- 25.6.4 If the striker who has a runner is in his ground, and the runner is out of his ground at the wicket-keeper's end when the wicket is fairly put down at that end, the conditions of Law 38 (Run out) shall apply.
- 25.6.5 If the striker who has a runner is out of his ground and the wicket at the wicket-keeper's end is fairly put down, the striker is liable to be out under Laws 38 (Run out) or 39 (Stumped). If the runner is also out of his ground at the wicket-keeper's end, then only Law 38 (Run Out) can apply.
- 25.6.6 If a striker who has a runner is dismissed in 25.6.5 the umpire shall
- disallow all runs to the batting side
  - return any not out batsman to his original end
  - award any 5-run Penalty that is applicable
- 25.6.7 When a batsman who has a runner is not the striker, he
- 25.6.7.1 remains subject to Law 37 (Obstructing the field) but is otherwise out of the match
- 25.6.7.2 shall stand where directed by the striker's end umpire so as not to interfere with play
- 25.6.7.3 will be liable, even though out of the match as in 25.6.7.1 to any penalty demanded by the Laws should he commit any act of unfair play

## **25.7 Restriction on the striker's runner**

- 25.7.1 Once the ball comes into play, the runner for an injured batsman who is the striker shall have part of his person or bat grounded behind the popping crease until the ball reaches the striker or passes the popping crease, whichever is the sooner.



- 25.7.2 If the striker's end umpire considers the runner for an injured striker to be in breach of this restriction, then, if the ball does not become dead for any other reason, they shall call and signal Dead ball as soon as the ball reaches the boundary or at the completion of the first run. However, they shall delay the call of Dead ball to allow the opportunity for a catch to be completed.

The bowlers end umpire shall

- disallow all runs to the batting side
- return any not out batsman to his original end
- award any 5-run Penalty that is applicable except for Penalty runs under Law 28.3 (Protective helmets belonging to the fielding side)

## **25.8 Batsman's Equipment**

- 25.8.1 A batsman may call for a helmet to be brought out to him at any time.
- 25.8.2 He must then wear or carry it personally all the time while play is in progress, or can have it taken off the field at the fall of a wicket, at the end of an over, or at any drinks interval. In all cases, no actions involving helmets are to waste playing time.
- 25.8.3 Umpires are not to hold helmets.
- 25.8.4 A batsman may only change other items of protective equipment provided that there is no waste of playing time.

## **26 PRACTICE ON THE FIELD**

### **26.1 Practice on the pitch or the rest of the square**

- 26.1.1 There shall not be any practice on the pitch at any time on any day of the match.
- 26.1.2 There shall not be any practice on the rest of the square at any time on any day of the match, except with the approval of the umpires and, if approved, such practice must be restricted to any netted practice area on the square set aside for that purpose.

## **26.2 Practice on the outfield**

- 26.2.1 On any day of the match, all forms of practice are permitted on the outfield:
- 26.2.1.1 before the start of play;
  - 26.2.1.2 after the close of play; and
  - 26.2.1.3 during the lunch and tea intervals or between innings providing the umpires are satisfied that such practice will not cause significant deterioration in the condition of the outfield.
- 26.2.2 Between the call of Play and the call of Time, practice shall be permitted on the outfield, providing that all of the following conditions are met:
- 26.2.2.1 only the fielders as defined in Appendix A.7 participate in such practice;
  - 26.2.2.2 no ball other than the match ball is used for this practice;
  - 26.2.2.3 no bowling practice takes place in the area between the square and the boundary in a direction parallel to the match pitch; and
  - 26.2.2.4 the umpires are satisfied that it will not contravene either of clauses 41.3 (The match ball changing its condition) or 41.9 (Time wasting by the fielding side).

## **26.3 Trial run-up**

A bowler is permitted to have a trial run-up provided the umpire is satisfied that it will not contravene either of clauses 41.9 (Time wasting by the fielding side) or 41.12 (Fielder damaging the pitch).

## **26.4 Penalties for contravention**

All forms of practice are subject to the provisions of clauses 41.3 (The match ball – changing its condition), 41.9 (Time wasting by the fielding side) and 41.12 (Fielder damaging the pitch).

- 26.4.1 If there is a contravention of any of the provisions of 26.1 or 26.2, the umpire shall:
- warn the player that the practice is not permitted;
  - inform the other umpire and, as soon as practicable, both captains of the reason for this action; or

- 26.4.1.1 if the contravention is by a batsman at the wicket, the umpire shall inform the other batsman and each incoming batsman that the warning has been issued. The warning shall apply to the team of that player throughout the match.
- 26.4.2 If during the match there is any further contravention by any player of that team, the umpire shall:
- award 5 Penalty runs to the opposing side;
  - inform the other umpire, the scorers and, as soon as practicable, both captains, and, if the contravention is during play, the batsmen at the wicket; and
- 26.4.2.1 together with the other umpire, report the occurrence under the Code of Conduct as soon as possible after the day's play to the Match Referee, who shall take such action as is considered appropriate against the captain, any other individuals concerned and, if appropriate, the team.

## **27 THE WICKET-KEEPER**

### **27.1 Protective equipment**

- 27.1.1 The wicket-keeper is the only fielder permitted to wear gloves and external leg guards. If these are worn, they are to be regarded as part of his person for the purposes of clause 28.2 (Fielding the ball). If by the wicket-keeper's actions and positioning when the ball comes into play it is apparent to the umpires that he will not be able to carry out the normal duties of a wicket-keeper, he shall forfeit this right and also the right to be recognised as a wicket-keeper for the purposes of clauses 33.2 (A fair catch), 39 (Stumped), 28.1 (Protective equipment), 28.4 (Limitation of on-side fielders) and 28.5 (Fielders not to encroach on pitch).
- 27.1.2 At all times when wicket-keeping up to the stumps, the wicket-keeper must wear a British Standard 7928:2013 compliant helmet, unless otherwise approved in writing by Cricket Australia.
- 27.1.3 The umpires are responsible for ensuring that a helmet is worn when required by this playing condition but are not be responsible for ensuring that the helmet being worn by the wicket-keeper is compliant with British Standard 7928:2013.

- 27.1.4 The umpires must not allow the match to continue during any period in which a wicket-keeper fails to wear a helmet when required by this clause 27.

## **27.2 Gloves**

- 27.2.1 If, as permitted under 27.1, the wicket-keeper wears gloves, they shall have no webbing between the fingers except joining index finger and thumb, where webbing may be inserted as a means of support.
- 27.2.2 If used, the webbing shall be a single piece of non-stretch material which, although it may have facing material attached, shall have no reinforcements or tucks.
- 27.2.3 The top edge of the webbing shall not protrude beyond the straight line joining the top of the index finger to the top of the thumb and shall be taut when a hand wearing the glove has the thumb fully extended. See the Clothing and Equipment Regulations.

## **27.3 Position of wicket-keeper**

- 27.3.1 The wicket-keeper shall remain wholly behind the wicket at the striker's end from the moment the ball comes into play until a ball delivered by the bowler touches the bat or person of the striker or passes the wicket at the striker's end or the striker attempts a run.
- 27.3.2 In the event of the wicket-keeper contravening this clause, the striker's end umpire shall call and signal No ball as soon as applicable after the delivery of the ball.

## **27.4 Movement by wicket-keeper**

- 27.4.1 After the ball comes into play and before it reaches the striker, it is unfair if the wicket-keeper significantly alters his position in relation to the striker's wicket, except for the following:
- 27.4.1.1 movement of a few paces forward for a slower delivery, unless in so doing it brings him within reach of the wicket.
  - 27.4.1.2 lateral movement in response to the direction in which the ball has been delivered.
  - 27.4.1.3 movement in response to the stroke that the striker is playing or that his actions suggest he intends to play. However the provisions of 27.3 shall apply.
- 27.4.2 In the event of unfair movement by the wicket-keeper, either umpire shall call and signal Dead ball.

## **27.5      Restriction on actions of wicket-keeper**

- 27.5.1      If, in the opinion of either umpire, the wicket-keeper interferes with the striker's right to play the ball and to guard his wicket, clause 20.4.2.6 shall apply.
- 27.5.2      If, however, either umpire considers that the interference by the wicket-keeper was wilful, then clause 41.4 (Deliberate attempt to distract striker) shall also apply.

## **27.6      Interference with wicket-keeper by striker**

If, in playing at the ball or in the legitimate defence of his wicket, the striker interferes with the wicket-keeper, he shall not be out except as provided for in clause 37.3 (Obstructing a ball from being caught).

# **28      THE FIELDER**

## **28.1      Protective equipment**

- 28.1.1      No fielder other than the wicket-keeper shall be permitted to wear gloves or external leg guards. In addition, protection for the hand or fingers may be worn only with the consent of the umpires.
- 28.1.2      The exchange of protective equipment between members of the fielding side on the field of play is permitted provided that the umpires do not consider that it constitutes a waste of playing time.
- 28.1.3      At all times when fielding in a position closer than 7 metres (7.66 yards) from the batsman's position on the popping crease on a middle stump line (for example, short leg or silly point), with the exception of any fielding position behind the popping crease (on both the off and on sides), a fielder must wear a British Standard 7928:2013 compliant helmet.

|   |
|---|
| <p><b>NOTE:</b> While it is not mandatory to wear a helmet when fielding in a position closer than 7 metres (7.66 yards) behind the popping crease, it is still strongly recommended for the fielder to wear a British Standard 7928:2013 compliant helmet.</p> |
|---|

- 28.1.4      The umpires are responsible for ensuring that a helmet is worn when required by 28.1 but are not responsible for ensuring that the helmet being worn by the fielder is compliant with British Standard 7928:2013.

- 28.1.5 The umpires must not allow the match to continue during any period in which a fielder fails to wear a helmet when required by this clause 28.

## **28.2 Fielding the ball**

- 28.2.1 A fielder may field the ball with any part of his person (see Appendix A.12), except as in 28.2.1.2. However, he will be deemed to have fielded the ball illegally if, while the ball is in play he wilfully:

- 28.2.1.1 uses anything other than part of his person to field the ball;
- 28.2.1.2 extends his clothing with his hands and uses this to field the ball; or
- 28.2.1.3 discards a piece of clothing, equipment or any other object which subsequently makes contact with the ball.

- 28.2.2 It is not illegal fielding if the ball in play makes contact with a piece of clothing, equipment or any other object which has accidentally fallen from the fielder's person.

- 28.2.3 If a fielder illegally fields the ball, the ball shall immediately become dead and:

- 28.2.3.1 the penalty for a No ball or a Wide shall stand;
- 28.2.3.2 any runs completed by the batsmen shall be credited to the batting side, together with the run in progress if the batsmen had already crossed at the instant of the offence; and
- 28.2.3.3 the ball shall not count as one of the over.

In addition, the umpire shall:

- 28.2.3.4 award 5 Penalty runs to the batting side;
- 28.2.3.5 inform the other umpire and the captain of the fielding side of the reason for this action;
- 28.2.3.6 inform the batsmen and, as soon as practicable, the captain of the batting side of what has occurred; and

28.2.3.7 together with the other umpire, may report the occurrence under the Code of Conduct as soon as possible after the match to the Match Referee, who shall take such action as is considered appropriate against the captain, any other individuals concerned and, if appropriate, the team.

### **28.3 Protective helmets belonging to the fielding side**

28.3.1 Protective helmets, when not in use by fielders, may not be placed on the ground, above the surface except behind the wicket-keeper and in line with both sets of stumps.

28.3.2 If a protective helmet belonging to the fielding side is on the ground within the field of play, and the ball while in play strikes it the ball shall become dead and, subject to 28.3.3:

28.3.2.1 an award of 5 Penalty runs shall be made to the batting side;

28.3.2.2 any runs completed by the batsmen before the ball strikes the protective helmet shall be scored, together with the run in progress if the batsmen had already crossed at the instant of the ball striking the protective helmet.

28.3.3 Unless the circumstances of clause 23.3 (Leg byes not to be awarded) or clause 34 (Hit the ball twice), apply, the umpire shall:

28.3.3.1 permit the batsman's runs as in 28.3.2.2 to be scored;

28.3.3.2 signal No ball or Wide ball to the scorers if applicable;

28.3.3.3 award 5 Penalty runs as in 28.3.2.1; and

28.3.3.4 award any other Penalty runs due to the batting side.

28.3.4 If the circumstances of clause 23.3 (Leg byes not to be awarded) or clause 34 (Hit the ball twice) apply, the umpire shall:

28.3.4.1 disallow all runs to the batting side;

28.3.4.2 return any not out batsman to his original end;

28.3.4.3 signal No ball or Wide ball to the scorers if applicable; and

28.3.4.4 award any 5-run Penalty that is applicable except for Penalty runs under 28.3.1.

## **28.4 Limitation of on side fielders**

- 28.4.1 At the instant of the bowler's delivery there shall not be more than 2 fielders, other than the wicket-keeper, behind the popping crease on the on side. A fielder will be considered to be behind the popping crease unless the whole of his person whether grounded or in the air is in front of this line.
- 28.4.2 In the event of infringement of this clause by any fielder, the striker's end umpire shall call and signal No ball.

## **28.5 Fielders not to encroach on pitch**

- 28.5.1 While the ball is in play and until the ball has made contact with the striker's bat or person, or has passed the striker's bat, no fielder, other than the bowler, may have any part of his person grounded on or extended over the pitch.
- 28.5.2 In the event of infringement of this clause by any fielder other than the wicket-keeper, the bowler's end umpire shall call and signal No ball as soon as possible after delivery of the ball. Note, however, clause 27.3 (Position of wicket-keeper).

## **28.6 Movement by any fielder other than the wicket-keeper**

- 28.6.1 Any movement by any fielder, excluding the wicket-keeper, after the ball comes into play and before the ball reaches the striker, is unfair except for the following:
- 28.6.1.1 minor adjustments to stance or position in relation to the striker's wicket.
  - 28.6.1.2 movement by any fielder, other than a close fielder, towards the striker or the striker's wicket that does not significantly alter the position of the fielder.
  - 28.6.1.3 movement by any fielder in response to the stroke that the striker is playing or that his actions suggest he intends to play.
- 28.6.2 In all circumstances clause 28.4 (Limitation of on side fielders) shall apply.
- 28.6.3 In the event of such unfair movement, either umpire shall call and signal Dead ball.
- 28.6.4 Note also the provisions of clause 41.4 (Deliberate attempt to distract striker). See also clause 27.4 (Movement by wicket-keeper).



## **29 THE WICKET IS DOWN**

### **29.1 Wicket put down**

- 29.1.1 The wicket is put down if a bail is completely removed from the top of the stumps, or a stump is struck out of the ground:
- 29.1.1.1 by the ball;
  - 29.1.1.2 by the striker's bat if held or by any part of the bat that he is holding;
  - 29.1.1.3 for the purpose of this clause only, by the striker's bat not in hand, or by any part of the bat which has become detached;
  - 29.1.1.4 by the striker's person or by any part of his clothing or equipment becoming detached from his person; or
  - 29.1.1.5 by a fielder with his hand or arm, providing that the ball is held in the hand or hands so used, or in the hand of the arm so used.
  - 29.1.1.6 The wicket is also put down if a fielder strikes or pulls a stump out of the ground as in 29.1.1.5.
- 29.1.2 The disturbance of a bail, whether temporary or not, shall not constitute its complete removal from the top of the stumps, but if a bail in falling lodges between two of the stumps this shall be regarded as complete removal.
- 29.1.3 For the purposes of 29.1, when "LED" stumps and bails are in use, the bails will be deemed to have been completely removed from the top of the stumps when the lights on the stumps and/or bails illuminate provided that one or both of the bails remains dislodged from the top of the stumps.

### **29.2 One bail off**

If one bail is off, it shall be sufficient for the purpose of putting the wicket down to remove the remaining bail or to strike or pull any of the three stumps out of the ground, in any of the ways stated in 29.1.

### **29.3 Remaking wicket**

If a wicket is broken or put down while the ball is in play, it shall not be remade by an umpire until the ball is dead. See clause 20 (Dead ball). Any fielder may, however, while the ball is in play:

- 29.3.1 replace a bail or bails on top of the stumps.
- 29.3.2 put back one or more stumps into the ground where the wicket originally stood.

#### **29.4 Dispensing with bails**

If the umpires have agreed to dispense with bails in accordance with clause 8.5 (Dispensing with bails), it is for the umpire concerned to decide whether or not the wicket has been put down.

- 29.4.1 After a decision to play without bails, the wicket has been put down if the umpire concerned is satisfied that the wicket has been struck by the ball, by the striker's bat, person or items of his clothing or equipment as described in 29.1.1.2, 29.1.1.3 or 29.1.1.4, or by a fielder in the manner described in 29.1.1.5.
- 29.4.2 If the wicket has already been broken or put down, 29.4.1 shall apply to any stump or stumps still in the ground. Any fielder may replace a stump or stumps, in accordance with 29.3, in order to have an opportunity of putting the wicket down.

### **30 BATSMAN OUT OF HIS GROUND**

#### **30.1 When out of his ground**

- 30.1.1 A batsman shall be considered to be out of his ground unless some part of his person or bat is grounded behind the popping crease at that end.
- 30.1.2 However, a batsman shall not be considered to be out of his ground if, in running or diving towards his ground and beyond, and having grounded some part of his person or bat beyond the popping crease, there is subsequent loss of contact between:
  - 30.1.2.1 the ground and any part of his person or bat; or
  - 30.1.2.2 between the bat and person,

#### **30.2 Which is a batsman's ground**

- 30.2.1 If only one batsman is within a ground, it is his ground and will remain so even if he is later joined there by the other batsman.
- 30.2.2 If both batsmen are in the same ground and one of them subsequently leaves it, the ground belongs to the batsman who remains in it.

- 30.2.3 If there is no batsman in either ground, then each ground belongs to whichever batsman is nearer to it, or, if the batsmen are level, to whichever batsman was nearer to it immediately prior to their drawing level.
- 30.2.4 If a ground belongs to one batsman then the other ground belongs to the other batsman, irrespective of his position.
- 30.2.5 When a batsman who has a runner is striker, his ground is always at the wicket-keepers end, However, 30.2.1, 30.2.2, 30.2.3 and 30.2.4 will still apply, but only to the runner and the non-striker, so that that ground will also belong to either the non-striker or the runner, as the case may be.

### **30.3 Position of non-striker**

The non-striker, when standing at the bowler's end, should be positioned on the opposite side of the wicket to that from which the ball is being delivered, unless a request to do otherwise is granted by the umpire.

## **31 APPEALS**

### **31.1 Umpire not to give batsman out without an appeal**

Neither umpire shall give a batsman out, even though he may be out under the clauses, unless appealed to by a fielder. This shall not debar a batsman who is out under any of the clauses from leaving the wicket without an appeal having been made. Note, however, the provisions of 31.7.

### **31.2 Batsman dismissed**

A batsman is dismissed if he is:

- 31.2.1 either given out by an umpire, on appeal; or
- 31.2.2 out under any of the clauses and leaves the wicket as in 31.1.

### **31.3 Timing of appeals**

For an appeal to be valid, it must be made before the bowler begins his run-up or, if there is no run-up, his bowling action to deliver the next ball, and before Time has been called.

The call of Over does not invalidate an appeal made prior to the start of the following over, provided Time has not been called. See clauses 12.2 (Call of Time) and 17.2 (Start of an over).

### **31.4 Appeal “How’s That?”**

An appeal “How’s That?” covers all ways of being out.

### **31.5 Answering appeals**

The striker’s end umpire shall answer all appeals arising out of any of clauses 35 (Hit wicket), 39 (Stumped) or 38 (Run out) when this occurs at the wicket-keeper’s end. The bowler’s end umpire shall answer all other appeals.

When an appeal is made, each umpire shall answer on any matter that falls within their jurisdiction.

When a batsman has been given Not out, either umpire may answer an appeal, made in accordance with 31.3, if it is on a further matter and is within their jurisdiction.

### **31.6 Consultation by umpires**

Each umpire shall answer appeals on matters within their own jurisdiction. If an umpire is doubtful about any point that the other umpire may have been in a better position to see, they shall consult the latter on this point of fact and shall then give the decision. If, after consultation, there is still doubt remaining, the decision shall be Not out.

### **31.7 Batsman leaving the wicket under a misapprehension**

An umpire shall intervene if satisfied that a batsman, not having been given out, has left the wicket under a misapprehension of being out. The umpire intervening shall call and signal Dead ball to prevent any further action by the fielding side and shall recall the batsman.

A batsman may be recalled at any time up to the instant when the ball comes into play for the next delivery, unless it is the final wicket of the innings, in which case it should be up to the instant when the umpires leave the field.

### **31.8 Withdrawal of an appeal**

The captain of the fielding side may withdraw an appeal only after obtaining the consent of the umpire within whose jurisdiction the appeal falls. If such consent is given, the umpire concerned shall, if applicable, revoke the decision and recall the batsman.

The withdrawal of an appeal must be before the instant when the ball comes into play for the next delivery or, if the innings has been completed, the instant when the umpires leave the field.

## **32 BOWLED**

### **32.1 Out Bowled**

- 32.1.1 The striker is out Bowled if his wicket is put down by a ball delivered by the bowler, not being a No ball, even if it first touches the striker's bat or person.
- 32.1.2 However, the striker shall not be out Bowled if before striking the wicket the ball has been in contact with any other player or an umpire. The striker will, however, be subject to clauses 37 (Obstructing the field), 38 (Run out) and 39 (Stumped).

### **32.2 Bowled to take precedence**

The striker is out Bowled if his wicket is put down as in 32.1, even though a decision against him for any other method of dismissal would be justified.

## **33 CAUGHT**

### **33.1 Out Caught**

The striker is out Caught if a ball delivered by the bowler, not being a No ball, touches his bat without having previously been in contact with any fielder, and is subsequently held by a fielder as a fair catch, as described in 33.2, before it touches the ground.

### **33.2 A fair catch**

- 33.2.1 A catch will be fair only if, in every case:
- 33.2.1.1 either the ball, at any time; or
  - 33.2.1.2 any fielder in contact with the ball,  
is not grounded beyond the boundary before the catch is completed. Note clauses 19.4 (Ball grounded beyond the boundary) and 19.5 (Fielder grounded beyond the boundary).
- 33.2.2 Furthermore, a catch will be fair if any of the following conditions applies:

- 33.2.2.1 the ball is held in the hand or hands of a fielder, or is hugged to the body, or lodges in the external protective equipment worn by a fielder, or lodges accidentally in a fielder's clothing.
- 33.2.2.2 fielder catches the ball after it has been lawfully struck more than once by the striker, but only if it has not been grounded since it was first struck. See clause 34 (Hit the ball twice).
- 33.2.2.3 a fielder catches the ball after it has touched or ricocheted off:
  - 33.2.2.3.1 the wicket;
  - 33.2.2.3.2 an umpire;
  - 33.2.2.3.3 any member of the fielding side; or
  - 33.2.2.3.4 either batsman, or any protective equipment worn by any of those persons.
- 33.2.2.4 a fielder catches the ball after it has crossed the boundary in the air, provided that the conditions in 33.2.1 are met.
- 33.2.2.5 the ball is caught off an obstruction within the boundary that is not designated a boundary by the umpires.

### **33.3 Making a catch**

The act of making a catch shall start from the time when the ball first comes into contact with a fielder's person and shall end when a fielder obtains complete control over both the ball and his own movement.

### **33.4 No runs to be scored**

If the striker is dismissed Caught, runs from that delivery completed by the batsmen before the completion of the catch shall not be scored but any runs for penalties awarded to either side shall stand. Clause 18.12 (Batsman returning to wicket he has left shall apply from the instant of the completion of the catch.

### **33.5 Caught to take precedence**

If the criteria of 33.1 are met and the striker is not out Bowled, then he is out Caught, even though a decision against either batsman for another method of dismissal would be justified.

## **34 HIT THE BALL TWICE**

### **34.1 Out Hit the ball twice**

- 34.1.1 The striker is out Hit the ball twice if, while the ball is in play, it strikes any part of his person or is struck by his bat and, before the ball has been touched by a fielder, the striker wilfully strikes it again with his bat or person, other than a hand not holding the bat, except for the sole purpose of guarding his wicket. See 34.3 and clause 37 (Obstructing the field).
- 34.1.2 For the purpose of this clause 'struck' or 'strike' shall include contact with the person of the striker.

### **34.2 Not out Hit the ball twice**

The striker will not be out under this clause if he:

- 34.2.1 strikes the ball a second or subsequent time in order to return the ball to any fielder. Note, however, the provisions of clause 37.4 (Returning the ball to a fielder).
- 34.2.2 wilfully strikes the ball after it has touched a fielder. Note, however the provisions of clause 37.1 (Out Obstructing the field).

### **34.3 Ball lawfully struck more than once**

The striker may, solely in order to guard his wicket and before the ball has been touched by a fielder, lawfully strike the ball a second or subsequent time with the bat, or with any part of his person other than a hand not holding the bat.

The striker may guard his wicket even if the delivery is a No Ball.

However, the striker may not prevent the ball from being caught by striking the ball more than once in defence of his wicket. See clause 37.3 (Obstructing a ball from being caught).

### **34.4 Runs permitted from ball lawfully struck more than once**

When the ball is lawfully struck more than once, as permitted in 34.3, if the ball does not become dead for any reason, the umpire shall call and signal Dead ball as soon as the ball reaches the boundary or at the completion of the first run. However, they shall delay the call of Dead ball to allow the opportunity for a catch to be completed. The umpire shall:

- 34.4.1 disallow all runs to the batting side
- 34.4.2 return any not out batsman to his original end

- 34.4.3 signal No ball to the scorers if applicable.
- 34.4.4 award any 5-run Penalty that is applicable except for Penalty runs under clause 28.3 (Protective helmets belonging to the fielding side).

### **34.5 Bowler does not get credit**

The bowler does not get credit for the wicket.

## **35 HIT WICKET**

### **35.1 Out Hit wicket**

- 35.1.1 The striker is out Hit wicket if, after the bowler has entered the delivery stride and while the ball is in play, his wicket is put down by either the striker's bat or person as described in clauses 35.1.1.2 to 35.1.1.4 in any of the following circumstances:
- 35.1.1.1 in the course of any action taken by him in preparing to receive or in receiving a delivery;
  - 35.1.1.2 in setting off for the first run immediately after playing or playing at the ball;
  - 35.1.1.3 if no attempt is made to play the ball, in setting off for the first run, providing that in the opinion of the umpire this is immediately after the striker has had the opportunity of playing the ball; or
  - 35.1.1.4 in lawfully making a second or further stroke for the purpose of guarding his wicket within the provisions of clause 34.3 (Ball lawfully struck more than once).
- 35.1.2 If the striker puts his wicket down in any of the ways described in clauses 35.1.1.2 to 35.1.1.4 before the bowler has entered the delivery stride, either umpire shall call and signal Dead ball.

### **35.2 Not out Hit wicket**

The striker is not out under this clause should his wicket be put down in any of the ways referred to in 35.1, if any of the following applies:

- 35.2.1 it occurs after the striker has completed any action in receiving the delivery, other than in 35.1.1.2 to 35.1.1.4;



- 35.2.2 it occurs when the striker is in the act of running, other than setting off immediately for the first run;
- 35.2.3 it occurs when the striker is trying to avoid being run out or stumped;
- 35.2.4 it occurs when the striker is trying to avoid a throw in at any time;
- 35.2.5 the bowler after entering the delivery stride does not deliver the ball. In this case either umpire shall immediately call and signal Dead ball. See clause 20.4 (Umpire calling and signalling Dead ball); or
- 35.2.6 the delivery is a No ball.

## **36 LEG BEFORE WICKET**

### **36.1 Out LBW**

The striker is out LBW if all the circumstances set out in 36.1.1 to 36.1.5 apply.

- 36.1.1 The bowler delivers a ball, not being a No ball.
- 36.1.2 The ball, if it is not intercepted full-pitch, pitches:
  - 36.1.2.1 in line between wicket and wicket; or
  - 36.1.2.2 on the off side of the striker's wicket.
- 36.1.3 The ball not having previously touched his bat, the striker intercepts the ball, either full-pitch or after pitching, with any part of his person.
- 36.1.4 The point of impact, even if above the level of the bails:
  - 36.1.4.1 either is between wicket and wicket; or
  - 36.1.4.2 if the striker has made no genuine attempt to play the ball with the bat, is between wicket and wicket or outside the line of the off stump.
- 36.1.5 But for the interception, the ball would have hit the wicket.

### **36.2 Interception of the ball**

- 36.2.1 In assessing 36.1.3, 36.1.4 and 36.1.5, only the first interception is to be considered.

- 36.2.2 In assessing 36.1.3, if the ball makes contact with the striker's person and bat simultaneously, this shall be considered as the ball having first touched the bat.
- 36.2.3 In assessing 36.1.5, it is to be assumed that the path of the ball before interception would have continued after interception, irrespective of whether the ball might have pitched subsequently or not.

### **36.3 Off side of wicket**

The off side of the striker's wicket shall be determined by the striker's stance at the moment the ball comes into play for that delivery. See Appendix A.13.

## **37 OBSTRUCTING THE FIELD**

### **37.1 Out Obstructing the field**

- 37.1.1 Either batsman is out Obstructing the field if, except in the circumstances of 37.2, and while the ball is in play, he wilfully attempts to obstruct or distract the fielding side by word or action. See also clause 34 (Hit the ball twice).
- 37.1.2 The striker is out Obstructing the field if, except in the circumstances of 37.2, in the act of receiving a ball delivered by the bowler, he wilfully strikes the ball with a hand not holding the bat. This will apply whether it is the first strike or a second or subsequent strike. The act of receiving the ball shall extend both to playing at the ball and to striking the ball more than once in defence of his wicket.
- 37.1.3 This clause will apply whether or not No ball is called.

**NOTE:** For the avoidance of doubt if a batsman, in running between the wickets, has significantly changed his direction without probable cause and thereby obstructed a fielder's attempt to effect a run out, the batsman should, on appeal, be given out Obstructing the field.

It shall not be relevant whether a run out would have occurred or not.

If the change of direction involves the batsman crossing the pitch, clause 41.14 shall also apply.

### **37.2 Not out Obstructing the field**

A batsman shall not be out Obstructing the field if:

- 37.2.1 obstruction or distraction is accidental, or
- 37.2.2 obstruction is in order to avoid injury; or
- 37.2.3 in the case of the striker, he makes a second or subsequent strike to guard his wicket lawfully as in clause 34.3 (Ball lawfully struck more than once). However, see 37.3.

### **37.3 Obstructing a ball from being caught**

- 37.3.1 If the delivery is not a no ball, the striker is out Obstructing the field if wilful obstruction or distraction by either batsman prevents the striker being out caught
- 37.3.2 37.3.1 shall apply even if the obstruction is caused by the striker in lawfully guarding his wicket under the provisions of Law 34.3 (Ball lawfully struck more than once)
- 37.3.3 If an obstruction or distraction takes place from a No Ball then the batsman who caused the obstruction or distraction will be out Obstructing the field
- 37.3.4 37.3.3 shall not apply if the striker obstructs while instinctively defending his wicket with a lawful second strike.

### **37.4 Returning the ball to a fielder**

Either batsman is out Obstructing the field if, at any time while the ball is in play and, without the consent of a fielder, he uses the bat or any part of his person to return the ball to any fielder.

### **37.5 Runs scored**

When either batsman is dismissed Obstructing the field:

- 37.5.1 unless the obstruction prevents a catch from being made, any runs completed by the batsmen before the offence shall be scored, together with any runs awarded for penalties to either side. See clauses 18.6 (Runs awarded for penalties) and 18.8 (Runs scored when a batsman is dismissed).
- 37.5.2 if the obstruction prevents a catch from being made, any runs completed by the batsmen shall not be scored but any penalties awarded to either side shall stand.

### **37.6 Bowler does not get credit**

The bowler does not get credit for the wicket.

## **38 RUN OUT**

### **38.1 Out Run out**

Either batsman is out Run out, except as in 38.2, if, at any time while the ball is in play:

38.1.1 he is out of his ground; and

38.1.2 his wicket is fairly put down by the action of a fielder,

even though No ball has been called, except in the circumstances of 38.2.2.2, and whether or not a run is being attempted.

**NOTE:** For the avoidance of doubt, a batsman can be out Run out where the ball rebounds or ricochets directly onto the stumps off the helmet being worn by a fielder.

### **38.2 Batsman not out Run out**

38.2.1 A batsman is not out Run out in the circumstances of 38.2.1.1 or 38.2.1.2.

38.2.1.1 He has been within his ground and has subsequently left it to avoid injury, when the wicket is put down.

Note also the provisions of clause 30.1.2 (When out of his ground).

38.2.1.2 The ball, delivered by the bowler, has not made contact with a fielder before the wicket is put down.

38.2.2 The striker is not out Run out in any of the circumstances in 38.2.2.1 and 38.2.2.2.

38.2.2.1 He is out Stumped. See clauses 25.6.5 and 39.1.2 (Out Stumped).

38.2.2.2 No ball has been called and:

38.2.2.2.1 he is out of his ground not attempting a run; and

38.2.2.2.2 the wicket is fairly put down by the wicket-keeper without the intervention of another fielder.

### **38.3 Which batsman is out**

The batsman out in the circumstances of 38.1 is the one whose ground is at the end where the wicket is put down. See clause 30.2 (Which is a batsman's ground).

### **38.4 Runs scored**

If either batsman is dismissed Run out, the run in progress when the wicket is put down shall not be scored, but any runs completed by the batsmen shall stand, together with any runs for penalties awarded to either side. See clauses 18.6 (Runs awarded for penalties) and 18.8 (Runs scored when a batsman is dismissed) and 18.8 (Runs scored when a batsman is dismissed).

If however, a striker who has a runner is himself dismissed Run out and runs are completed by the runner and the other batsman before the wicket is put down

- all runs to the batting side from that delivery shall be disallowed
- the one run penalty for No ball shall stand and 5 run penalties shall be allowed
- the umpire shall return the non-striker to his original end.

See Law 25.6 (Dismissal and conduct of a batsman and his runner).

### **38.5 Bowler does not get credit**

The bowler does not get credit for the wicket.

## **39 STUMPED**

### **39.1 Out Stumped**

39.1.1 The striker is out Stumped, except as in 39.3, if:

39.1.1.1 a ball which is delivered is not called No ball; and

39.1.1.2 he is out of his ground, other than as in 39.3.1; and

39.1.1.3 he has not attempted a run,

when his wicket is fairly put down by the wicket-keeper without the intervention of another fielder. Note, however, clauses 25.6.2 and 25.6.5 (Dismissal and conduct of a batsman and his runner) and 27.3 (Position of wicket-keeper).

39.1.2 The striker is out Stumped if all the conditions of 39.1.1 are satisfied, even though a decision of Run out would be justified.

### **39.2 Ball rebounding from wicket-keeper's person**

If the wicket is put down by the ball, it shall be regarded as having been put down by the wicket-keeper if the ball rebounds on to the stumps from any part of the wicket-keeper's person or equipment or has been kicked or thrown on to the stumps by the wicket-keeper.

**NOTE:** For the avoidance of doubt, a batsman can be out Stumped where the ball rebounds or ricochets directly onto the stumps off the helmet being worn by a wicket-keeper.

### **39.3 Not out Stumped**

- 39.3.1 The striker will not be out Stumped if, after having received the delivery, he has left his ground in order to avoid injury.
- 39.3.2 If the striker is not out Stumped he may, except in the circumstances of Law 38.2.2.2, be out Run out if the conditions of clause 38.1 (Out Run out) apply.

## **40 TIMED OUT**

### **40.1 Out Timed out**

- 40.1.1 After the fall of a wicket or the retirement of a batsman, the incoming batsman must, unless Time has been called, be in position to take guard or for the other batsman to be ready to receive the next ball within 3 minutes of the dismissal or retirement. If this requirement is not met, the incoming batsman will be out, Timed out.
- 40.1.2 In the event of an extended delay in which no batsman comes to the wicket, the umpires shall adopt the procedure of clause 16.3 (Umpires awarding a match). For the purposes of that clause the start of the action shall be taken as the expiry of the 3 minutes referred to above.

### **40.2 Bowler does not get credit**

The bowler does not get credit for the wicket.

## **41 UNFAIR PLAY**

### **41.1 Fair and unfair play – responsibility of captains**

The captains are responsible for ensuring that play is conducted within The Spirit of Cricket, as described in The Preamble – The Spirit of Cricket, as well as within the clauses.

## **41.2 Fair and unfair play – responsibility of umpires**

41.2.1 The umpires shall be the sole judges of fair and unfair play. If an umpire considers that any action by a player, not covered in the Laws, is unfair, they shall call and signal Dead ball, if appropriate, as soon as it becomes clear that the call will not disadvantage the non-offending side, and report the matter to the other umpire

41.2.1.1 If this is a first offence by that side, the bowler's end umpire shall then

- summon the offending player's captain and issue a first and final warning which shall apply to all members of the team for the remainder of the match
- warn the offending player's captain that any further such offence by any member of his team shall result in the award of 5 Penalty runs to the opposing team

41.2.1.2 If this is a second or subsequent offence by that side, the bowler's end umpire shall then

- summon the offending player's captain and inform him that there has been a further such offence
- award 5 penalty runs to the opposing side

41.2.1.3 The umpires together shall report the incident as soon as possible after the match to the Executive of the offending side and to any Governing Body responsible for the match, who shall take such action as is considered appropriate against the captain, any other individuals concerned and, if appropriate the team.

### **41.3 The match ball – changing its condition**

41.3.1 The umpires shall make frequent and irregular inspections of the ball. In addition, they shall immediately inspect the ball if they suspect anyone of attempting to change the condition of the ball, except as permitted in 41.3.2.

41.3.2 It is an offence for any player to take any action which changes the condition of the ball.

A batsman may not wilfully change the condition of the ball other than, when the ball is in play, in striking it with the bat. See also clause 5.5 (Damage to the ball).

A fielder may, however:

41.3.2.1 polish the ball on his clothing provided that no artificial substance, saliva or sweat from the face or from the front of the neck is used and that such polishing wastes no time.

41.3.2.2 remove mud from the ball under the supervision of an umpire.

41.3.2.3 dry a wet ball on a piece of cloth that has been approved by the umpires.

41.3.3 The umpires shall consider the condition of the ball to have been unfairly changed if any action by any person does not comply with the conditions in 41.3.2.

41.3.4 If the umpires together suspect, but are not certain, that the condition of the ball has been unfairly changed, or that its condition is inconsistent with the use it has received, the umpires may:

41.3.4.1 Change the ball forthwith. The umpires shall choose a replacement ball for one of similar wear and of the same brand as the ball in use prior to the contravention

41.3.4.2 Bowler's end umpire shall issue the captain with a first and final warning.

41.3.5 If the umpires together agree that the condition of the ball has been unfairly changed by person or either side, they shall consider that there has been a contravention of this clause. They shall then:

41.3.5.1 Ask the captain of the opposing side if he would like the ball to be replace. If necessary, in the case of the batting side, the batters at the wicket may deputise for their captain.



#### 41.3.5.2 If a replacement ball is requested

- By the batting side, the batters shall choose the replacement ball from a selection of six other balls of various degrees of usage (including a new ball) and of the same brand as the ball in use prior to the contravention.
- By the fielding side, the umpires shall select and bring into use immediately, a ball which shall have wear comparable to that of the previous ball immediately prior to the contravention.

#### 41.3.5.3 Regardless of whether a replacement ball has been chosen to be used, the bowler's end umpire shall:

- award 5 Penalty runs to the opposing side.
- if appropriate, inform the batsmen at the wicket and the captain of the fielding side that the ball has been changed and the reason for their action.
- inform the captain of the batting side as soon as practicable of what has occurred.

The umpires together shall report the matter under the Code of Conduct as soon as possible after the day's play to the Match Referee,

- The person or persons responsible for the contravention and/or
- The captain of the offending side in the event that the person or persons are not able to be identified, or where the umpires believe the contravention was planned or systematic to the extent that the captain either knew, or ought to have known that the contravention was occurring.

The Match Referee shall then take such action as is considered appropriate against the person/s concerned.

If person/s responsible for changing the condition of the ball are later identified then any CoC report brought against the captain of the offending side is to be withdrawn..

- 41.3.6 If the umpires agree that in the match there has been any further instance by that team of unfairly changing the condition of the ball they shall repeat the procedures in 41.3.5
- 41.3.7 If the umpire believes that saliva or sweat from the face or from the front of the neck has been applied to the ball the umpires shall:
- 41.3.7.1 If it is the first instance during an innings, summon the captain of the fielding side and issue a first warning
  - 41.3.7.2 If it is a second instance during an innings, summon the captain of the fielding side and issue a second and final warning and warn the captain of the fielding side that any further such offence by any member of the team during the innings shall result in the award of 5 Penalty runs to the batting side
  - 41.3.7.3 If it is a third or subsequent instance award 5 Penalty runs to the batting side
  - 41.3.7.4 The ball shall not be changed but the umpires shall wipe the ball with an appropriate cloth
- 41.3.8 Use of saliva in breach of 41.3.2.1 above shall not in and of itself be considered an offence under Article 2.16 of the CA Code of Conduct (Changing the condition of the ball in breach of clause 41.3 of the CA Sheffield Shield, One Day Cup/WNCL and W/BBL Playing Conditions)

#### **41.4 Deliberate attempt to distract striker**

- 41.4.1 It is unfair for any fielder deliberately to attempt to distract the striker while he is preparing to receive or receiving a delivery.
- 41.4.2 If either umpire considers that any action by a fielder is such an attempt, they shall immediately call and signal Dead ball and inform the other umpire of the reason for the call. The bowler's end umpire shall:
- award 5 Penalty runs to the batting side;
  - inform the captain of the fielding side, the batsmen and, as soon as practicable, the captain of the batting side of the reason for the action; and

Neither batsman shall be dismissed from that delivery and the ball shall not count as one of the over.

The umpires together may report the matter under the Code of Conduct as soon as possible after the day's play to the Match Referee, who shall take such action as is considered appropriate against the fielder/s concerned.

#### **41.5 Deliberate distraction, deception or obstruction of batsman**

- 41.5.1 In addition to 41.4, it is unfair for any fielder wilfully to attempt, by word or action, to distract, deceive or obstruct either batsman after the striker has received the ball.
- 41.5.2 It is for either one of the umpires to decide whether any distraction, deception or obstruction is wilful or not.
- 41.5.3 If either umpire considers that a fielder has caused or attempted to cause such a distraction, deception or obstruction, they shall immediately call and signal Dead ball and inform the other umpire of the reason for the call.
- 41.5.4 Neither batsman shall be dismissed from that delivery.
- 41.5.5 If an obstruction involves physical contact, the umpires together shall decide whether or not an offence under clause 42 has been committed and:
- 41.5.5.1 if an offence under clause 42 has been committed, they shall apply the relevant procedures in clause 42 and shall also apply each of 41.5.7 to 41.5.9.
  - 41.5.5.2 If they consider that there has been no offence under clause 42, they shall apply each of 41.5.6 to 41.5.10.

- 41.5.6 The bowler's end umpire shall:
- 41.5.6.1 award 5 Penalty runs to the batting side; and
  - 41.5.6.2 inform the captain of the fielding side of the reason for this action and as soon as practicable inform the captain of the batting side.
- 41.5.7 The ball shall not count as one of the over.
- 41.5.8 Any runs completed by the batsmen before the offence shall be scored, together with any runs for penalties awarded to either side. Additionally, the run in progress shall be scored whether or not the batsmen had already crossed at the instant of the offence.
- 41.5.9 The batsmen at the wicket shall decide which of them is to face the next delivery.
- 41.5.10 The umpires together, if they consider it appropriate, may report the occurrence under the Code of Conduct to the Match Referee, who shall take such action as is considered appropriate against the person/s concerned.

## **41.6 Bowling of dangerous and unfair short pitched deliveries**

**NOTE:** 41.6.1 to 41.6.11 below regulate the bowling of "fast short pitched deliveries" that pass or would pass above the shoulder height of the striker standing upright at the crease to no more than two per over.

- 41.6.1 A bowler shall be limited to two fast short pitched deliveries per over.
- 41.6.2 A "fast short pitched delivery" is defined as a ball, which after pitching, passes or would have passed above the shoulder height of the striker standing upright at the crease.

**NOTE:** Fast short pitched deliveries described in 41.6.2 are distinct from the fast short pitched balls described in 41.6.12 to 41.6.13, although fast short pitched deliveries can be considered fast short pitched balls for the purpose of determining whether the bowling is dangerous and unfair under 41.6.12.

- 41.6.3 The umpire at the bowler's end shall advise the bowler and the batsman on strike when each fast short pitched delivery has been bowled.

- 41.6.4 For the avoidance of doubt any fast short pitched delivery that is called a Wide under clause 22.1 above shall also count as one of the fast short pitched deliveries in that over.
- 41.6.5 In the event of a bowler bowling more than two fast short pitched deliveries in an over as defined in 41.6.2, the umpire at the bowler's end shall call and signal No ball on each occasion. A differential signal shall be used to signify a fast short pitched delivery. The umpire shall call and signal No ball and then tap the head with the other hand.
- 41.6.6 If a bowler delivers a third fast short pitched delivery in an over, the umpire, after the call of No ball and when the ball is dead, shall caution the bowler, inform the other umpire, the captain of the fielding side and the batsmen at the wicket of what has occurred. This caution shall apply throughout the innings.
- 41.6.7 If there is a second instance of the bowler being no balled in the same innings for bowling more than two fast short pitched deliveries in an over, the umpire shall advise the bowler that this is his final warning for the innings. The umpire will also inform the other umpire, the captain of the fielding side and the batsmen at the wicket of what has occurred.
- 41.6.8 Should there be any further instance by the same bowler in that same innings, the umpire shall call and signal No ball and when the ball is dead direct the captain to take the bowler off forthwith. If necessary, the over shall be completed by another bowler, who shall neither have bowled the previous over, or part thereof nor be allowed to bowl the next over, or part thereof.
- 41.6.9 The bowler thus taken off shall not be allowed to bowl again in that innings.
- 41.6.10 The umpire will report the occurrence to the other umpire, the batsmen at the wicket and as soon as possible to the captain of the batting side.
- 41.6.11 The umpires may then report the matter under the Code of Conduct to the Match Referee who shall take such action as is considered appropriate against the captain and the bowler concerned. Refer also to 41.1 (Fair and Unfair Play - Responsibility of Captains).

**NOTE:** 41.6.12 to 41.6.13 regulate short pitched bowling, including both fast short pitched deliveries (as defined in 41.6.2) and fast short pitched balls bouncing below shoulder height, that pose a danger to the batsman.

These provisions apply regardless of any action taken by the umpire as a result of a breach of 41.6.1 to 41.6.11 at any time during the match:

- 41.6.12 The bowling of short pitched deliveries is dangerous if the bowler's end umpire considers that, taking into consideration the skill of the striker, by their speed, length, height and direction they are likely to inflict physical injury on him. The fact that the striker is wearing protective equipment shall be disregarded.
- 41.6.13 The bowler's end umpire may still consider that the bowling of short pitched deliveries, although not dangerous under 41.6.12, is unfair if they pass above head height of the striker standing upright at the crease. See also clause 22.1.

**NOTE:** The fast short pitched balls referred to in 41.6.12 and 41.6.13 include fast short pitched bowling that is not above shoulder height and fast short pitched deliveries (as defined in 41.6.2).

- 41.6.14 As soon as the umpire decides that the bowling of short pitched deliveries has become dangerous under 41.6.12, or unfair under 41.6.13, they shall adopt the following procedure:
- 41.6.14.1 in the first instance, call and signal No ball, and when the ball is dead, caution the bowler and inform the other umpire, the captain of the fielding side and the batsmen of what has occurred.
- 41.6.14.2 if there is a second instance by the same bowler in that innings, the umpire shall repeat the above procedure and indicate to the bowler that this is a final warning.
- 41.6.15 Both the above caution and final warning shall continue to apply even though the bowler may later change ends.
- 41.6.16 Should there be any further instance by the same bowler in that innings, the umpire shall:
- 41.6.16.1 call and signal No ball; and
- 41.6.16.2 when the ball is dead direct the captain to take the bowler off forthwith.
- 41.6.17 If necessary, the over shall be completed by another bowler, who shall neither have bowled the previous over, or part thereof, nor be allowed to bowl the next over, or part thereof.

- 41.6.18 The bowler thus taken off shall not be able to bowl again in that innings.
- 41.6.19 The umpire will report the occurrence to the other umpire, the batsmen at the wicket and as soon as possible to the captain of the batting side.
- 41.6.20 The umpires will then report the matter under the Code of Conduct to the Match Referee who shall take such action as is considered appropriate against the captain and the bowler concerned. Refer also to 41.1 (Fair and Unfair Play - Responsibility of Captains).
- 41.6.21 The warning sequences in 41.6 are independent of the warning and action sequence in 41.7.

#### **41.7 Bowling of dangerous and unfair non-pitching deliveries**

- 41.7.1 Any delivery, which passes or would have passed, without pitching, above waist height of the striker standing upright at the popping crease, is unfair. Whenever such a delivery is bowled, the umpire shall call and signal No ball..
- 41.7.2 The bowling of a delivery as defined in 41.7.1 is also dangerous if the bowler's end umpire considers that there is a risk of injury to the striker. In making that judgement the umpire shall:
- disregard any protective equipment worn by the striker
  - be mindful of:
    - the speed, height and direction of the delivery
    - the skill of the striker
    - the repeated nature of such deliveries
- 41.7.3 If the umpire considers a non-pitching delivery, or a series of non-pitching deliveries, to be dangerous under 41.7.2 when the ball is dead, the umpire shall repeat the No ball signal to the scorers and then caution the bowler, indicating that this is a first and final warning. The umpire shall also inform the other umpire, the captain of the fielding side and the batsmen of what has occurred. This caution shall apply to that bowler throughout the innings.
- 41.7.4 Should there be any further dangerous such delivery by the same bowler in that innings the umpire shall:
- call and signal No ball

- when the ball is dead, direct the captain of the fielding side to suspend the bowler immediately from bowling
- inform the other umpire of the reason for this action:

The bowler thus suspended shall not be allowed to bowl again in that innings.

If applicable, the over shall be completed by another bowler, who shall neither have bowled any part of the previous over, nor be allowed to bowl any part of the next over.

Additionally, the umpire shall

Report the occurrence to the batsmen and, as soon as practicable, to the captain of the batting side.

The umpires together shall report the occurrence as soon as possible after the match to the Executive of the offending side and to any Governing Body responsible for the match, who shall take such action as is considered appropriate against the

- 41.7.5 The warning and action sequences in 41.7.3 and 41.7.4 are independent of those in 41.6.
- 41.7.6 If the umpire considers that a bowler deliberately bowled a non-pitching delivery, deemed to be unfair as defined in 41.7.1, then the caution and warning in 41.7.3 shall be dispensed with.

The umpire shall

- immediately call and signal No ball
- when the ball is dead, direct the captain of the fielding side to suspend the bowler immediately from bowling and inform the other umpire for the reason for this action.

The bowler thus suspended shall not be allowed to bowl again in that innings.

If applicable, the over shall be completed by another bowler, who shall neither have bowled any part of the previous over, nor allowed to bowl any part of the next over

- report the occurrence to the batsmen and, as soon as practicable, to the captain of the batting side

The umpires together shall report the occurrence as soon as possible after the match to the Executive of the offending side and



to any Governing Body responsible for the match, who shall such action as is considered appropriate against the captain, any other individuals concerned and, if appropriate, the team.

#### **41.8 Bowling of deliberate front-foot No ball**

- 41.8.1 If the umpire considers that the bowler has delivered a deliberate front-foot No ball, they shall:
  - 41.8.1.1 call and signal No ball; and
  - 41.8.1.2 when the ball is dead, direct the captain to take the bowler off forthwith.
- 41.8.2 If necessary, the over shall be completed by another bowler, who shall neither have bowled the previous over, or part thereof, nor be allowed to bowl the next over, or part thereof.
- 41.8.3 The bowler thus taken off shall not be able to bowl again in that innings.
- 41.8.4 The umpire will report the occurrence to the other umpire, the batsmen at the wicket and as soon as possible to the captain of the batting side.
- 41.8.5 The umpires will then report the matter under the Conduct of Conduct to the Match Referee who shall take such action as is considered appropriate against the captain and the bowler concerned. Refer also to 41.1 (Fair and Unfair Play - Responsibility of Captains).

#### **41.9 Time wasting by the fielding side**

- 41.9.1 It is unfair for any fielder to waste time.
- 41.9.2 If either umpire considers that the progress of an over is unnecessarily slow, or time is being wasted in any other way, by the captain of the fielding side or by any other fielder, at the first instance the umpire concerned shall:
  - 41.9.2.1 if the ball is in play, call and signal Dead ball.
  - 41.9.2.2 inform the other umpire of what has occurred.The bowler's end umpire shall then:
  - 41.9.2.3 warn the captain of the fielding side, indicating that this is a first and final warning.
  - 41.9.2.4 inform the batsmen of what has occurred.

- 41.9.3 If either umpire considers that there is any further waste of time in that innings by any fielder, the umpire concerned shall:
- 41.9.3.1 if the ball is in play, call and signal Dead ball.
  - 41.9.3.2 inform the other umpire of what has occurred.
  - 41.9.3.3 award 5 penalty runs to the batting side.
- 41.9.4 Additionally, the umpire shall inform the batsmen and, as soon as is practicable, the captain of the batting side of what has occurred.
- 41.9.5 The umpires may then report the matter under the Conduct of Conduct to the Match Referee who shall take such action as is considered appropriate against the captain and the fielder concerned. Refer also to 41.1 (Fair and Unfair Play - Responsibility of Captains).

#### **41.10 Batsman wasting time**

- 41.10.1 It is unfair for a batsman to waste time. In normal circumstances, the striker should always be ready to take strike when the bowler is ready to start his run-up.
- 41.10.2 Should either batsman waste time by failing to meet this requirement, or in any other way, the following procedure shall be adopted. At the first instance, either before the bowler starts his run-up or when the ball becomes dead, as appropriate, the umpire shall:
- 41.10.2.1 warn both batsmen and indicate that this is a first and final warning. This warning shall apply throughout the innings. The umpire shall so inform each incoming batsman.
  - 41.10.2.2 inform the other umpire of what has occurred.
  - 41.10.2.3 inform the captain of the fielding side and, as soon as practicable, the captain of the batting side of what has occurred.
- 41.10.3 If there is any further time wasting by any batsman in that innings, the umpire shall, at the appropriate time while the ball is dead:
- 41.10.3.1 award 5 Penalty runs to the fielding side.
  - 41.10.3.2 inform the other umpire of the reason for this action.
  - 41.10.3.3 inform the other batsman, the captain of the fielding side and, as soon as practicable, the captain of the batting side of what has occurred.

- 41.10.4 The umpires may then report the matter under the Conduct of Conduct to the Match Referee who shall take such action as is considered appropriate against the captain and the batsman concerned. Refer also to clause 41.1 (Fair and Unfair Play - Responsibility of Captains).

#### **41.11 The protected area**

The protected area is defined as that area of the pitch contained within a rectangle bounded at each end by imaginary lines parallel to the popping creases and 5 ft/1.52 m in front of each, and on the sides by imaginary lines, one each side of the imaginary line joining the centres of the two middle stumps, each parallel to it and 1 ft/30.48 cm from it. Guidance markings will be made as per Appendix E.

#### **41.12 Fielder damaging the pitch**

- 41.12.1 It is unfair to cause deliberate or avoidable damage to the pitch. A fielder will be deemed to be causing avoidable damage if either umpire considers that his presence on the pitch is without reasonable cause.
- 41.12.2 If a fielder causes avoidable damage to the pitch, other than as in 41.13.1, at the first instance the umpire seeing the contravention shall, when the ball is dead, inform the other umpire. The bowler's end umpire shall then:
- 41.12.2.1 caution the captain of the fielding side and indicate that this is a first and final warning. This warning shall apply throughout the innings.
  - 41.12.2.2 inform the batsmen of what has occurred.
- 41.12.3 If, in that innings, there is any further instance of avoidable damage to the pitch, by any fielder, the umpire seeing the contravention shall, when the ball is dead, inform the other umpire. The bowler's end umpire shall then:
- 41.12.3.1 award 5 Penalty runs to the batting side.
  - 41.12.3.2 inform the fielding captain of the reason for this action.
  - 41.12.3.3 inform the batsmen and, as soon as practicable, the captain of the batting side of what has occurred.

- 41.12.4 The umpires will then report the matter under the Conduct of Conduct to the Match Referee who shall take such action as is considered appropriate against the captain and the fielder concerned. Refer also to clause 41.1 (Fair and Unfair Play - Responsibility of Captains).

#### **41.13 Bowler running on protected area**

- 41.13.1 It is unfair for a bowler to enter the protected area in his follow-through without reasonable cause, whether or not the ball is delivered.
- 41.13.2 If a bowler contravenes this clause, at the first instance and when the ball is dead, the umpire shall:
- 41.13.2.1 caution the bowler and inform the other umpire of what has occurred. This caution shall apply to that bowler throughout the innings.
  - 41.13.2.2 inform the captain of the fielding side and the batsmen of what has occurred.
- 41.13.3 If, in that innings, the same bowler again contravenes this clause, the umpire shall repeat the above procedure indicating that this is a final warning. This warning shall also apply throughout the innings.
- 41.13.4 If, in that innings, the same bowler contravenes this clause a third time, when the ball is dead, the umpire shall:
- 41.13.4.1 direct the captain of the fielding side to suspend the bowler immediately from bowling. If applicable, the over shall be completed by another bowler, who shall neither have bowled any part of the previous over, nor be allowed to bowl any part of the next over.
  - 41.13.4.2 inform the other umpire of the reason for this action.
  - 41.13.4.3 inform the batsmen and, as soon as practicable, the captain of the batting side of what has occurred.
- 41.13.5 The umpires may then report the matter under the Conduct of Conduct to the Match Referee who shall take such action as is considered appropriate against the captain and the bowler concerned. Refer also to clause 41.1 (Fair and Unfair Play - Responsibility of Captains).

#### **41.14 Batsman damaging the pitch**

- 41.14.1 It is unfair to cause deliberate or avoidable damage to the pitch. If the striker enters the protected area in playing or playing at the ball, he must move from it immediately thereafter. A batsman will be deemed to be causing avoidable damage if either umpire considers that his presence on the pitch is without reasonable cause.
- 41.14.2 If either batsman causes deliberate or avoidable damage to the pitch, other than as in 41.15, at the first instance the umpire seeing the contravention shall, when the ball is dead, inform the other umpire of the occurrence. The bowler's end umpire shall then:
- 41.14.2.1 warn both batsmen that the practice is unfair and indicate that this is a first and final warning. This warning shall apply throughout the innings. The umpire shall so inform each incoming batsman.
  - 41.14.2.2 inform the captain of the fielding side and, as soon as practicable, the captain of the batting side of what has occurred.
- 41.14.3 If there is any further instance of avoidable damage to the pitch by any batsman in that innings, the umpire seeing the contravention shall, when the ball is dead, inform the other umpire of the occurrence. The bowler's end umpire shall:
- 41.14.3.1 disallow all runs to the batting side
  - 41.14.3.2 return any not out batsman to his original end
  - 41.14.3.3 signal No ball or Wide to the scorers if applicable.
  - 41.14.3.4 award 5 Penalty runs to the fielding side.
  - 41.14.3.5 award any other 5-run Penalty that is applicable except for Penalty runs under clause 28.3 (Protective helmets belonging to the fielding side).
  - 41.14.3.6 inform the captain of the fielding side and, as soon as practicable, the captain of the batting side of the reason for this action.
- 41.14.4 The umpires will then report the matter under the Conduct of Conduct to the Match Referee who shall take such action as is considered appropriate against the captain and the batsman concerned. Refer also to clause 41.1 (Fair and Unfair Play - Responsibility of Captains).

## **41.15 Striker in protected area**

- 41.15.1 The striker shall not adopt a stance in the protected area or so close to it that frequent encroachment is inevitable. The striker may mark a guard on the pitch provided that no mark is unreasonably close to the protected area.
- 41.15.2 If either umpire considers that the striker is in breach of any of the conditions in 41.15.1, if the bowler has not entered the delivery stride, they shall immediately call Dead ball, otherwise, wait until the ball is dead and they shall then inform the other umpire of the occurrence. The bowler's end umpire shall then:
- 41.15.2.1 warn the striker that the practice is unfair and indicate that this is a first and final warning. This warning shall apply throughout the innings. The umpire shall so inform the non-striker and each incoming batsman.
- 41.15.2.2 inform the captain of the fielding side and, as soon as practicable, the captain of the batting side of what has occurred.
- 41.15.3 If there is any further breach of any of the conditions in 41.15.1 by any batsman in that innings, the umpire seeing the contravention shall, if the bowler has not entered his delivery stride, immediately call and signal Dead ball, otherwise, they shall wait until the ball is dead and then inform the other umpire of the occurrence. The bowler's end umpire shall:
- 41.15.3.1 disallow all runs to the batting side;
- 41.15.3.2 return any not out batsman to his original end;
- 41.15.3.3 signal No ball or Wide to the scorers if applicable;
- 41.15.3.4 award 5 Penalty runs to the fielding side; and
- 41.15.3.5 award any other 5-run Penalty that is applicable except for Penalty runs under clause 28.3 (Protective helmets belonging to the fielding side); and
- 41.15.3.6 inform the captain of the fielding side and, as soon as practicable, the captain of the batting side of the reason for this action.
- 41.15.4 The umpires will then report the matter under the Conduct of Conduct to the Match Referee who shall take such action as is considered appropriate against the captain and the batsman concerned. Refer also to 41.1 (Fair and Unfair Play - Responsibility of Captains).

#### **41.16 Non-striker leaving his ground early**

- 41.16.1 If the non-striker is out of his ground at any time from the moment the ball comes into play until the instant when the bowler would normally have been expected to release the ball, the non-striker is liable to be Run out. In these circumstances, the non-striker will be out Run out if he is out of his ground when his wicket is put down by the bowler throwing the ball at the stumps or by the bowler's hand holding the ball, whether or not the ball is subsequently delivered.
- 41.16.2 If the ball is not delivered and there is an appeal
- the umpire shall make their decision on the Run out  
If it is not out, they shall call and signal Dead ball as soon as possible
  - the ball shall not count as one in the over
- 41.16.3 If the ball is delivered and there is an appeal
- the umpire shall make their decision on the Run out
  - if the non-striker is not dismissed, the ball remains in play and Law 21.6 (Bowler breaking the wicket in delivering the ball) shall apply
  - if the non-striker is dismissed, the ball shall not count as one in the over.

#### **41.17 Batsmen stealing a run**

- 41.17.1 It is unfair for the batsmen to attempt to steal a run during the bowler's run-up. Unless the bowler attempts to run out either batsman – see 41.16 and clause 21.4 (Bowler throwing towards striker's end before delivery) – the umpire shall:
- 41.17.1.1 call and signal Dead ball as soon as the batsmen cross in such an attempt.
- 41.17.1.2 inform the other umpire of the reason for this action.
- The bowler's end umpire shall then:
- 41.17.1.3 return the batsmen to their original ends.
- 41.17.1.4 award 5 Penalty runs to the fielding side.
- 41.17.1.5 inform the batsmen, the captain of the fielding side and, as soon as practicable, the captain of the batting side, of the reason for this action.

- 41.17.2 The umpires may then report the matter under the Conduct of Conduct to the Match Referee who shall take such action as is considered appropriate against the captain and the batsman concerned. Refer also to 41.1 (Fair and Unfair Play - Responsibility of Captains).

#### **41.18 Penalty runs**

- 41.18.1 When Penalty runs are awarded to either side, when the ball is dead the umpire shall signal the Penalty runs to the scorers. See clause 2.13 (Signals).

- 41.18.2 Penalty runs shall be awarded in each case where the clauses require the award, even if a result has already been achieved. See clause 16.6 (Winning hit or extras).

Note, however, that the restrictions on awarding Penalty runs, in clauses 23.3 (Leg byes not to be awarded), 34.4 (Runs scored from ball lawfully struck more than once) and 28.3 (Protective helmets belonging to the fielding side), will apply.

- 41.18.3 When 5 Penalty runs are awarded to the batting side under any of clauses 24.4 (Player returning without permission), 28.2 (Fielding the ball), or 28.3 (Protective helmets belonging to the fielding side) or under 41.3, 41.4, 41.5, 41.9 or 41.12, then:

41.18.3.1 they shall be scored as Penalty extras and shall be in addition to any other penalties.

41.18.3.2 they are awarded when the ball is dead and shall not be regarded as runs scored from either the immediately preceding delivery or the immediately following delivery, and shall be in addition to any runs from those deliveries.

41.18.3.3 the batsmen shall not change ends solely by reason of the 5 run penalty.

- 41.18.4 When 5 Penalty runs are awarded to the fielding side, under clause 18.5.2 (Deliberate short runs), or under 41.10, 41.14, 41.15 or 41.17, they shall be added as Penalty extras to that side's total of runs in its most recently completed innings. If the fielding side has not completed an innings, the 5 Penalty runs shall be added to the score in its next innings.

#### **41.19 Use of Electronic Communications Equipment**



Other than the approved 'miking-up' of players by the host broadcaster, the use of electronic communication devices and equipment of any kind to communicate with players on the field of play shall not be permitted.

## **42 PLAYERS' CONDUCT**

### **42.1 Serious misconduct**

- 42.1.1 The umpires shall act upon any serious misconduct. The relevant offences and the corresponding actions by the umpires are identified in 42.2.1. These offences correspond with Level 4 offences in the CA Code of Conduct.
- 42.1.2 If either umpire considers that a player has committed one of these offences at any time during the match, the umpire concerned shall call and signal Dead ball. This call may be delayed until the umpire is satisfied that it will not disadvantage the non-offending side.
- 42.1.3 The umpire concerned shall report the matter to the other umpire and together they shall decide whether an offence has been committed. The umpires may also consult with the third umpire (where available) and the Match Referee, who may review any audio or video evidence to confirm whether an offence has been committed. If so, the umpires shall then apply the related sanctions.
- 42.1.4 If the offence is committed by a batsman, the umpires shall summon the offending player's captain to the field. Solely for the purpose of this clause, the batsmen at the wicket may not deputise for their captain.
- 42.1.5 Playing time shall be counted as lost from the call of Time to the call of Play, excluding intervals (Law 11) and suspensions of play (Law 2.8).

The time for close of play on that day shall be extended by this length of time

If applicable, no overs shall be deducted during the last hour of the match solely on account of this time.

### **42.2 Level 4 offences and action by umpires**

- 42.2.1 Any of the following actions by a player shall constitute a Level 4 offence:
- threatening to assault an umpire

- making inappropriate and deliberate physical contact with an umpire
- physically assaulting a player or any other person
- committing any other act of violence.

42.2.2 If such an offence is committed, 42.2.2.1 to 42.2.2.5 shall be implemented.

42.2.2.1 The umpire shall call Time if necessary.

42.2.2.2 Together the umpires shall summon and inform the offending player's captain that an offence at this Level has occurred.

42.2.2.3 The umpires shall instruct the captain to remove the offending player immediately from the field of play for the remainder of the match and shall apply the following:

42.2.2.3.1 If the offending player is a fielder, no substitute shall be allowed for him. He is to be recorded as Retired – out at the commencement of any subsequent innings in which his team is the batting side.

42.2.2.3.2 If a bowler is suspended mid-over, then that over must be completed by a different bowler, who shall not have bowled the previous over nor shall be permitted to bowl the next over.

42.2.2.3.3 If the offending player is a batsman he is to be recorded as Retired – out in the current innings, unless he has been dismissed under any of clauses 32 to 39, and at the commencement of any subsequent innings in which his team is the batting side. If no further member of the batting side is available to bat, the innings is completed.

42.2.2.4 As soon as practicable, the umpire shall:

- award 5 Penalty runs to the opposing team
- signal the Level 4 penalty to the scorers
- call Play.

42.2.2.5 The umpires must then report the matter under the Code of Conduct.

### **42.3 Captain refusing to remove a player from the field**

- 42.3.1 If a captain refuses to carry out an instruction under 42.2.2.3, the umpires shall invoke clause 16.3 (Umpires awarding a match).
- 42.3.2 If both captains refuse to carry out instructions under 42.2.2.3 in respect of the same incident, the umpires shall instruct the players to leave the field. The match is not concluded as in clause 12.9 and there shall be no result under clause 16.

### **42.4 Additional points relating to Level 4 offences**

- 42.4.1 If a player, while acting as wicket-keeper, commits a Level 4 offence, clause 24.1.2 shall not apply, meaning that only a nominated player may keep wicket, even if another fielder becomes injured or ill and is replaced by a substitute.
- 42.4.2 A nominated player who has a substitute or has a runner will also suffer the penalty for any Level 4 offence committed by the substitute or by that runner. However, only the substitute or runner will be reported under 42.2.2.5.

## **43 SHEFFIELD SHIELD FINAL**

### **43.1 Sheffield Shield Final**

Except as varied hereunder, the Sheffield Shield clauses above will apply.

### **43.2 Duration of Match and Hours of Play**

- 43.2.1 The Final shall be of five days scheduled duration with scheduled hours of play to be advised on announcement of the venue.
- 43.2.2 If the match has not commenced by the end of the third scheduled day, it will revert to a first innings match with no compulsory declaration. At this point, with make-up time of one hour per day, the total time remaining is 14 hours.

### **43.3 Over Rates**

- 43.3.1 As per clause 12 except that the initial minimum of overs shall be 90 per day calculated at one over for each full four minutes (minimum of 15 overs per hour).

- 43.3.2 On the last day there shall be a minimum of 75 overs (or a minimum of 15 overs per hour) for playing time other than the last hour of the match where a minimum of 15 overs must be bowled.

#### **43.4 Penalties For Not Achieving Over Rates**

Clause 12.15 is replaced with the following:

- 43.4.1 Penalties shall apply for not achieving target overs.
- 43.4.2 Subject to the provisions of this clause, over rates shall be assessed at the rate of 4 minutes per over, with a minimum of 90 overs in a six hour day, subject to the following allowances:
- 43.4.2.1 **2 minutes** for every wicket taken which results in the subsequent batsman immediately commencing his innings. For the avoidance of doubt no allowance shall be given for the final wicket in an innings or for a wicket that falls prior to an interval.
- 43.4.2.2 **4 minutes** for each drinks break taken in any session.
- 43.4.2.3 **Actual time** where treatment by authorised medical personnel is required on the field of play and/or for a player leaving the field due to serious injury.
- 43.4.3 Over rates will be calculated at the end of the match.
- 43.4.4 After taking into account the provisions of 43.4.2 and the permitted allowances pursuant to clause 43.4.2, if a team has failed to bowl the required number of overs in the match after consultation with the match umpires and the scorers ("**over rate breach**"), the team will be penalised as follows (unless determined otherwise by the Match Referee):
- 43.4.4.1 each of the 11 players in that team will be fined 5% of his match fee for the first 5 full overs that were not completed in the scheduled time across the match;
- 43.4.4.2 each of the 11 players in that team will be fined an additional 10% of his match fee per full over after the initial 5 that were not completed in the scheduled time across the match;
- 43.4.4.3 the captain of the team will incur one strike for the over rate breach; and

- 43.4.4.4 for every two strikes imposed on a captain in respect of over rate breaches committed in a season within the same match format, the captain will be suspended for the next match for which he is available for selection in that format, regardless of whether that match is in the same or the next season. No strikes incurred by a captain in respect of an over rate breach will be carried over into the next season.
- 43.4.5 For the purposes of clause 43.4.4.3 to 43.4.4.4 above, if the player nominated as captain at the start of the season is in the starting 11 but not listed on the official team sheet as the captain:
- 43.4.5.1 any previous strike will carry over to the player nominated as captain for that match; and
- 43.4.5.2 should another over rate breach occur in this situation, both the originally nominated captain and the player nominated as captain for that match will incur an automatic 1 match suspension and that suspension shall be applied to the next match of the same format for which they are available for selection individually, regardless of whether that match is in the same or the next season.
- 43.4.6 In determining whether a team has fallen short of the target number of overs, umpires may take into account any factor they consider relevant, including whether inclement weather has adversely affected the ability of the team to comply with the required over rate.
- 43.4.7 A Commissioner appointed by Cricket Australia will hear and determine all appeals against penalties imposed.
- 43.4.8 Appeals must be lodged within 3 business days of the completion of the match.
- 43.4.8.1 A \$5000 up front fee is to be paid by the appealing team with it being refunded either in part or full if appeal is successful or appeal is deemed as not frivolous by a Code of Conduct Commissioner
- 43.4.9 The onus is on the appellant to prove that the umpires have erred in their assessment of time allowances. Video evidence (where available) may be produced by the appellant in support of the appeal. Umpires will be required to record all delays and stoppages on the appropriate form.
- 43.4.10 For calculation of penalties:

- 43.4.10.1 the scheduled last hour of the match, as defined in clauses 12.11.12. and 12.12 will be excluded.
- 43.4.10.2 A maximum allowance of 20 overs in any hour shall apply.
- 43.4.10.3 In the event of a match finishing within three scheduled playing days, penalties for not achieving the required over rates shall not apply, regardless of the hours played on those days.

## **43.5 Venue**

- 43.5.1 The team that finished first on the points table at the conclusion of the preliminary matches shall earn the right to host the Final at a venue:

- 43.5.1.1 within its state; or

- 43.5.1.2 outside of its state,

provided that the venue nominated by that team is a suitable first class venue and acceptable to Cricket Australia. Should the team expressly waive this right in writing, or if Cricket Australia notifies the team in writing that the nominated venue is not acceptable to Cricket Australia and no alternative venue can be put forward that is acceptable to Cricket Australia within 24 hours of the initial notification by Cricket Australia, the Final's venue shall be selected by Cricket Australia.

- 43.5.2 In addition, Cricket Australia reserves the right to oversee and direct the preparation of the pitch for the Final at any venue.

## **43.6 Result**

- 43.6.1 The Sheffield Shield final shall be played under ordinary conditions in where the side which has scored a total of runs in excess of that scored in the two innings of the opposing side shall win the match. See Clause 13.3 (Completed Innings). Note also 16.6 (Correctness of results).
- 43.6.2 In the event of a draw the result shall be decided by using bonus points.
- 43.6.2.1 Bonus points shall be calculated as per clauses 16.9.2, 16.9.3 and 16.9.4
- 43.6.3 If the match is drawn and the bonus points, as calculated per clauses 16.9.2, 16.9.3 and 16.9.4, are tied then the team which finished higher on the Sheffield Shield ladder shall be declared the winner
- 43.6.4 In a reduced overs match, a result from bonus points will only be applicable if a minimum of 270 completed overs are bowled in the match
- 43.6.4.1 If there is no result at the end of a reduced overs match the team which finished higher on the Sheffield Shield ladder shall be declared the winner
- 43.6.5 If there has been no play on the first three day (Refer Clause 43.2.2) the match will become one in which the first innings result shall determine the winner
- 43.6.5.1 If there is no result at the end of a match where there was no play on the first three days then the team which finished higher on the Sheffield Shield ladder shall be declared the winner.

## **APPENDIX A**

### **Definitions and explanations of words or phrases not defined in the text.**

- A1 The match**
- A1.1 The game** is used in these Playing Conditions as a general term meaning the Game of Cricket.
- A1.2 A match** is a single encounter (or contest) between two sides (or teams), played under the Playing Conditions.
- A1.3 The toss** is the toss for choice of innings.

- A1.4** **Before the toss** is at any time before the toss on the day the match is expected to start or, in the case of a one-day match, on the day the match is due to take place.
- A1.5** **Before the match** is at any time before the toss, not restricted to the day on which the toss is to take place.
- A1.6** **During the match** is at any time after the toss until the conclusion of the match, whether play is in progress or not.
- A1.7** **Playing time** is any time between the call of Play and the call of Time.
- A1.8** **Conduct of the match** includes any action relevant to the match at any time on any day of the match.
- A2** **Implements and equipment**
- A2.1** **Implements used in the match** are the bat, the ball, the stumps and bails.
- A2.2** **External protective equipment** is any visible item of apparel worn for protection against external blows.
- For a batter, items permitted are a protective helmet, external leg guards (batting pads), batting gloves and, if visible, forearm guards.
- For a fielder, only a protective helmet is permitted, except in the case of a wicket-keeper, for whom wicket-keeping pads and gloves are also permitted.
- A2.3** **A protective helmet** is headwear made of hard material and designed to protect the head or the face or both. For the purposes of interpreting these Playing Conditions, such a description will include faceguards.
- A2.4** **Equipment** – a batter's equipment is his bat as defined above, together with any external protective equipment he is wearing.
- A fielder's equipment is any external protective equipment that he is wearing.
- A2.5** **The bat** – the following are to be considered as part of the bat:
- the whole of the bat itself.
  - the whole of a glove (or gloves) worn on the hand (or hands) holding the bat.
  - the hand (or hands) holding the bat, if the batter is not wearing a glove on that hand or on those hands.



- A2.6 Held in batter's hand.** Contact between a batter's hand, or glove worn on his hand, and any part of the bat shall constitute the bat being held in that hand.
- A3 The playing area**
- A3.1 The field of play** is the area contained within the boundary.
- A3.2 The square** is a specially prepared area of the field of play within which the match pitch is situated.
- A3.3 The outfield** is that part of the field of play between the square and the boundary.
- A4 Positioning**
- A4.1 Behind the popping crease** at one end of the pitch is that area of the field of play, including any other marking, objects and persons therein, that is on that side of the popping crease that does not include the creases at the opposite end of the pitch. **Behind**, in relation to any other marking, object or person, follows the same principle. See the diagram in A 13.
- A4.2 In front of the popping crease** at one end of the pitch is that area of the field of play, including any other marking, objects and persons therein, that is on that side of the popping crease that includes the creases at the opposite end of the pitch. **In front of**, in relation to any other marking, object or person, follows the same principle. See the diagram in A 13.
- A4.3 The striker's end** is the place where the striker stands to receive a delivery from the bowler only insofar as it identifies, independently of where the striker may subsequently move, one end of the pitch.
- A4.4 The bowler's end** is the end from which the bowler delivers the ball. It is the other end of the pitch from the striker's end and identifies that end of the pitch that is not the striker's end as described in A4.3.
- A4.5 The wicket-keeper's end** is the same as the striker's end as described in A4.3.
- A4.6 In front of the line of the striker's wicket** is in the area of the field of play in front of the imaginary line joining the fronts of the stumps at the striker's end; this line to be considered extended in both directions to the boundary. See A4.2.
- A4.7 Behind the wicket** is in the area of the field of play behind the imaginary line joining the backs of the stumps at the appropriate

end; this line to be considered extended in both directions to the boundary. See A4.1.

- A4.8 Behind the wicket-keeper** is behind the wicket at the striker's end, as defined above, but in line with both sets of stumps and further from the stumps than the wicket-keeper.
- A4.9 Off side/on side** – see diagram in A13
- A4.10 Inside edge** is the edge on the same side as the nearer wicket.
- A5 Umpires**
- A5.1 Umpire** – where the description **the umpire** is used on its own, it always means 'the bowler's end umpire' though this full description is sometimes used for emphasis or clarity. Similarly, **the umpires** always means both umpires. **An umpire** and **umpires** are generalised terms. Otherwise, a fuller description indicates which one of the umpires is specifically intended. Each umpire will be bowler's end umpire and striker's end umpire in alternate overs.
- A5.2 Bowler's end umpire** is the umpire who is standing at the bowler's end (see A4.4) for the current delivery.
- A5.3 Striker's end umpire** is the umpire who is standing at the striker's end (see A4.3), to one side of the pitch or the other, depending on their choice, for the current delivery.
- A5.4 Umpires together agree** applies to decisions which the umpires are to make jointly, independently of the players.
- A6 Batters (including references to batsman/batsmen)**
- A6.1 Batting side** is the side currently batting, whether or not play is in progress.
- A6.2 Member of the batting side** is one of the players nominated by the captain of the batting side, or any authorised replacement for such nominated player.
- A6.3 A batter's ground** – at each end of the pitch, the whole area of the field of play behind the popping crease is the ground at that end for a batter.
- A6.4 Original end** is the end where a batter was when the ball came into play for that delivery.
- A6.5 Wicket he has left** is the wicket at the end where a batter was at the start of the run in progress.

- A6.6** **Guard position** is the position and posture adopted by the striker to receive a ball delivered by the bowler
- A6.7** For the purposes of these Laws, waist height is defined as the point at which the top of the batsman's trousers would conventionally be when he is standing upright at the popping crease.
- A7** **Fielders**
- A7.1** **Fielding side** is the side currently fielding, whether or not play is in progress.
- A7.2** **Member of the fielding side** is one of the players nominated by the captain of the fielding side, or any authorised replacement or substitute for such nominated player.
- A7.3** **Fielder** is one of the 11 or fewer players who together represent the fielding side on the field of play. This definition includes not only both the bowler and the wicket-keeper but also nominated players who are legitimately on the field of play, together with players legitimately acting as substitutes for absent nominated players. It excludes any nominated player who is absent from the field of play, or who has been absent from the field of play and who has not yet obtained the umpire's permission to return.
- A player going briefly outside the boundary in the course of discharging his duties as a fielder is not absent from the field of play nor, for the purposes of clause 24.2 (Fielder absent or leaving the field of play), is he to be regarded as having left the field of play.
- A8** **Substitutes, Replacements**
- A8.1** **A Substitute** is a player who takes the place of a fielder on the field of play, but does not replace the player for whom he substitutes on that side's list of nominated players. A substitute's activities are limited to fielding (other than a Concussion Substitute, which is managed in accordance with Appendix C).
- A8.2** **A Replacement** is a player who takes the place of a nominated player and who, thereby, becomes a nominated player. A replacement's activities on the field of play are no more limited than those of any other nominated player.
- A8.3** **A Runner** is a nominated player who runs for another nominated player of his own side who is batting and is unable to run
- A9** **Bowlers**
- A9.1** **Over the wicket / round the wicket** – If, as the bowler runs up between the wicket and the return crease, the wicket is on the

same side as his bowling arm, he is bowling over the wicket. If the return crease is on the same side as his bowling arm, he is bowling round the wicket.

**A9.2 Delivery swing** is the motion of the bowler's arm during which he normally releases the ball for a delivery.

**A9.3 Delivery stride** is the stride during which the delivery swing is made, whether the ball is released or not. It starts when the bowler's back foot lands for that stride and ends when the front foot lands in the same stride. The stride after the delivery stride is completed when the next foot lands, i.e. when the back foot of the delivery stride lands again.

## **A10 The ball**

**A10.1 The ball is struck/strikes the ball** unless specifically defined otherwise, mean 'the ball is struck by the bat'/'strikes the ball with the bat'.

**A10.2 Rebounds directly/strikes directly** and similar phrases mean 'without contact with any fielder' but do not exclude contact with the ground.

**A10.3 Full-pitch** describes a ball delivered by the bowler that reaches or passes the striker without having touched the ground. Sometimes described as non-pitching.

## **A11 Runs**

**A11.1 A run to be disallowed** is one that in the Playing Conditions should not have been taken. It is not only to be cancelled but the batters are to be returned to their original ends.

**A11.2 A run not to be scored** is one that is not illegal, but is not recognised as a properly executed run. It is not a run that has been made, so the question of cancellation does not arise. The loss of the run so attempted is not a disallowance and the batters will not be returned to their original ends on that account.

## **A12 The person**

**A12.1 Person;** A player's person is his physical person (flesh and blood) together with any clothing or legitimate external protective equipment that he is wearing except, in the case of a batter, his bat.


A hand, whether gloved or not, that is not holding the bat is part of the batter's person.

No item of clothing or equipment is part of the player's person unless it is attached to him.

For a batter, a glove being held but not worn is part of his person.

For a fielder, an item of clothing or equipment he is holding in his hand or hands is not part of his person.

- A12.2 Clothing** – anything that a player is wearing, including such items as spectacles or jewellery, that is not classed as external protective equipment is classed as clothing, even though he may be wearing some items of apparel, which are not visible, for protection. A bat being carried by a batter does not come within this definition of clothing.
- A12.3 Hand** for batter or wicket-keeper shall include both the hand itself and the whole of a glove worn on the hand.
- A13 Off side/on side; in front of / behind the popping crease.**



## **APPENDIX B**

### **The bat (Clause 5)**

#### **B.1. General guidance**

**B.1.1. Measurements** - All provisions in sections B.2 to B.6 below are subject to the measurements and restrictions stated in the Playing Conditions and this Appendix.

**B.1.2. Adhesives** – Throughout, adhesives are permitted only where essential and only in minimal quantity and in accordance with any Clothing and Equipment Regulations.

**B.1.3. Categories of bat** – The specifications given below relate to Type A bats unless specified otherwise.

#### **B.2. Specifications for the Handle**

**B.2.1** One end of the handle is inserted into a recess in the blade as a means of joining the handle and the blade.

This lower portion is used purely for joining the blade and the handle together. It is not part of the blade but, solely in interpreting B.3 and B.4 below, references to the blade shall be considered to extend also to this lower portion of the handle where relevant.

**B.2.2.** The handle may be glued where necessary and bound with twine along the upper portion.

Providing clause 5.5 is not contravened, the upper portion may be covered with materials solely to provide a surface suitable for gripping. Such covering is an addition and is not part of the bat, except in relation to clause 5.6. The bottom of this grip should not extend below the point defined in B.2.4 below.

Twine binding and the covering grip may extend beyond the junction of the upper and lower portions of the handle, to cover part of the shoulders of the bat as defined in B.3.1.

No material may be placed on or inserted into the lower portion of the handle other than as permitted above together with the minimal adhesives or adhesive tape used solely for fixing these items, or for fixing the handle to the blade.

**B.2.3. Materials in handle** – As a proportion of the total volume of the handle, materials other than cane, wood or twine are restricted to one-tenth for Type A. Such materials must not project more than 3.25 in/8.26 cm into the lower portion of the handle

**B.2.4 Binding and covering of handle** – The permitted continuation beyond the junction of the upper and lower portions of the handle is restricted to a maximum, measured along the length of the handle, of

- 2.5 in/6.35 cm in for the twine binding
- 2.75 in/6.99 cm for the covering grip.

### **B.3 Specifications for the Blade**

**B.3.1.** The blade has a face, a back, a toe, sides and shoulders

B.3.1.1 The face of the blade is its main striking surface and shall be flat or have a slight convex curve resulting from traditional pressing techniques. The back is the opposite surface.

B.3.1.2 The shoulders, sides and toe are the remaining surfaces, separating the face and the back.

B.3.1.3. The shoulders, one on each side of the handle, are along that portion of the blade between the first entry point of the handle and the point at which the blade first reaches its full width.

B.3.1.4. The toe is the surface opposite to the shoulders taken as a pair.

B.3.1.5. The sides, one each side of the blade, are along the rest of the blade, between the toe and the shoulders.

**B.3.2.** No material may be placed on or inserted into the blade other than as permitted in B.2.4, B.3.3. and clause 5.4 together with the minimal adhesives or adhesive tape used solely for fixing these items, or for fixing the handle to the blade.

**B.3.3 Covering the blade.** Type A bats shall have no covering on the blade except as permitted in clause 5.4. This may be treated as specified in B.4 below.

Any materials referred to in clause 5.4 and B.4 below, are to be considered as part of the bat, which must still pass through the gauge as defined in B.7.

### **B.4 Protection and repair**

**B.4.1.** The surface of the blade may be treated with non-solid materials to improve resistance to moisture penetration and/or mask natural blemishes in the appearance of the wood. Save for the purpose of giving a homogeneous appearance by masking natural blemishes,



such treatment shall not materially alter the colour of the blade unless otherwise approved by Cricket Australia (in its absolute discretion).

- B.4.2.** Materials can be used for protection and repair as stated in clause 5.4 and are additional to the blade. Note however clause 5.6.

Any such material shall not extend over any part of the back of the blade except in the case of clause 5.4.1 and then only when it is applied as a continuous wrapping covering the damaged area.

The repair material shall not extend along the length of the blade more than 0.79 in/2.0 cm in each direction beyond the limits of the damaged area. Where used as a continuous binding, any overlapping shall not breach the maximum of 0.04 in/0.1 cm in total thickness.

The use of non-solid material which when dry forms a hard layer more than 0.004 in/0.01 cm in thickness is not permitted.

- B.4.3.** Permitted coverings, repair material and toe guards, not exceeding their specified thicknesses, may be additional to the dimensions above, but the bat must still pass through the gauge as described in B.7.

- B.5. Toe and side inserts** – The wood used must not be more than 0.35 in/0.89 cm in thickness.

The toe insert shall not extend from the toe more than 2.5 in/6.35 cm up the blade at any point.

Neither side insert may extend from the edge more than 1 in/2.54 cm across the blade at any point.

- B.6 Commercial identifications** These identifications may not exceed 0.008 in/0.02 cm in thickness. On the back of the blade they must occupy no more than 50% of the surface. On the face of the blade, they must be confined within the top 9 in/22.86 cm, measured from where the bottom of the grip as defined in B.2.2 and B.2.4, would finish.


- B.7 Bat Gauge**

All bats that conform to the Laws of Cricket must meet the specifications defined in clause 5.7. They must also, with or without protective coverings permitted in clause 5.4, be able to pass through a bat gauge, the dimensions and shape of which are shown in the diagram below.

Dimensions of aperture

|              |                 |
|--------------|-----------------|
| Total depth: | 2.68 in/6.8 cm  |
| Width:       | 4.33 in/11.0 cm |
| Edge:        | 1.61 in/4.1 cm  |
| Curve:       | 0.20 in/0.5 cm  |

Note: The curve of the lower edge of the aperture is an arc of a circle of radius 12.0 in/30.5 cm, whose centre is on the vertical centre line of the aperture.



## **APPENDIX C**

### **Concussion Substitute**

#### **C.1. Concussion or Head Trauma Assessment**

- C.1.1. If a head trauma occurs or the concussion of a player or umpire is suspected by an umpire, team-mate, team support staff or qualified medical personnel (either immediately after a head/neck trauma or at any later time during play), play shall cease immediately and the highest qualified medical personnel available can enter the field of play (in their absolute discretion) to conduct an initial assessment for the presence of concussion symptoms and signs.
- C.1.2. If the medical personnel determine that concussion is established or that further assessment is required:
  - C.1.2.1. the medical personnel (in their absolute discretion) may direct the player or umpire to leave the field of play; and
  - C.1.2.2. play must not resume until that player or umpire has completely left the field of play.
- C.1.3. A maximum of 5 minutes will be allowed for the initial assessment on the field of play.
- C.1.4. For clarity:
  - C.1.4.1. A batter instructed to leave the field of play following an assessment is deemed to have retired pursuant to clause 25.4 and can, if no concussion has been diagnosed after a full assessment, return to play pursuant to clause 25.
  - C.1.4.2. A player on the fielding team instructed to leave the field of play following an assessment can, if no concussion has been diagnosed after further assessment, return to play pursuant to clause 24.
  - C.1.4.3. Where an umpire is instructed to leave the field of play following an assessment, clause 2.2 applies.
  - C.1.4.4. If a player or umpire has been diagnosed with a concussion following any assessment, then their return to play will be strictly in accordance with the provisions of the Australian Cricket Concussion and Head Trauma Policy and will be managed by the relevant medical personnel.

- C.1.4.5. The outcome of any assessment by the relevant medical personnel is final and should not be subject to any influence or interference from any players, umpires, coaches or team support staff.

## **C.2. Activation of a Concussion Substitute**

- C.2.1. If the relevant medical personnel formally notify the Match Referee of the diagnosis of a player with concussion (**Concussed Player**), then a Concussion Substitute may be activated to take the place of the Concussed Player for the remainder of the match.
- C.2.2. Formal notification in accordance with C.2.1:
- C.2.2.1. must be made orally by the relevant medical personnel to the Match Referee or the umpire/s to be relayed to the Match Referee (if made on the field of play);
  - C.2.2.2. must be followed up in writing from the relevant medical personnel to the Match Referee as soon as practicable after making the oral notification; and
  - C.2.2.3. requires the relevant medical personnel to provide the Match Referee with a copy of the completed Head Trauma Report Form (as contained in the Concussion and Head Trauma Policy and uploaded on the AMS by that medical personnel) for that incident as soon as practicable.
- C.2.3. A Concussion Substitute:
- C.2.3.1. cannot be activated without the formal notification of the diagnosis of the concussion of the Concussed Player to the Match Referee; and
  - C.2.3.2. can be activated in accordance with and at any time during the remainder of the match following the formal notification.
- C.2.4. There is no obligation for a team to immediately or subsequently activate a Concussion Substitute following any formal notification/s made in accordance with C.2.1.
- C.2.5. Following the notification at C.2.1, if the Concussed Player's team wishes to activate the Concussion Substitute, it must have its captain (or coach where the captain cannot practically do so):
- C.2.5.1. formally notify the Match Referee of its election to activate a Concussion Substitute for that Concussed Player; and

- C.2.5.2. nominate a like-player to the opposing team captain (or coach if the opposing team captain is on the field of play) for approval (which must not be unreasonably withheld) as the Concussion Substitute for that Concussed Player for the remainder of the match concerned.
- C.2.6. Where approval is not provided by the opposing team captain as contemplated by C.2.5 above, the Match Referee will make the final determination (in consultation with Cricket Australia) on whether to approve the nominated player as a Concussion Substitute for that Concussed Player.
- C.2.7. Once approved, the Concussion Substitute may immediately participate in the match as a complete replacement player for the Concussed Player. To be clear, the Concussion Substitute is able to **Captain**, bat, bowl, keep wicket or field as though he was a member of the starting 11.
- C.2.8. If, at the time of activation, the Concussion Substitute is replacing a:
- C.2.8.1. Concussed Player that has “retired not out” during his team’s current batting innings, the Concussion Substitute may only bat in that innings (where possible) pursuant to clause 25 as though he was a batter returning to his innings; or
- NOTE:** For the purposes of scoring, the Concussion Substitute will be entered as an additional batter and his innings will be considered separate to the innings of the Concussed Player (who will remain “Retired – Not out”). However, the fielding side still only needs to take 10 wickets to complete the batting innings.
- C.2.8.2. Concussed Player that has “retired not out” during his team’s previous batting innings and that batting innings has since concluded, the Concussion Substitute may bat at any position in the batting order in that team’s subsequent batting innings (if any); or
- C.2.8.3. Concussed Player from the fielding team, the Concussion Substitute may enter play pursuant to clause 24 as though he was a member of the fielding side returning to play and without needing to serve any Penalty Time when entering the match.

- C.2.9. Once replaced by a Concussion Substitute, a Concussed Player may take no further part in the match concerned.
- C.2.10. There is no maximum number of Concussion Substitutes available in a particular match.

## **APPENDIX D**

### **Third Umpire and TV/Stream Replays**

In relation to clause 2.16 (Third Umpire/TV/Stream Replays), the following specifically explains the role of the Third Umpire for televised/streamed matches.

#### **D.1. General**

Cricket Australia will appoint a third umpire from its panel of umpires who shall act as the emergency umpire and officiate on TV/stream replays in all televised/streamed matches where the third umpire specific technology is available.

In the circumstances detailed in paragraphs D.2, D.3, D.4 and D.5 below, the on-field umpire shall have the discretion to refer the decision to the third umpire or, in the case of paragraphs D.3 and D.4, to consult with the third umpire before making a decision.

Players may not appeal to the on-field umpires to use the Umpire Review. Breach of this provision may constitute dissent.

#### **D.2. Run Out, Stumped, Bowled and Hit Wicket Decisions**

- D.2.1. The relevant on-field umpire shall be entitled to refer an appeal for run-out, stumped, bowled or hit wicket to the third umpire.
- D.2.2. An on-field umpire wishing to refer a decision to the third umpire shall signal to the third umpire by making the shape of a TV screen with their hands.
- D.2.3. In the case of a referral of a bowled, hit wicket or stumped decision, the third umpire shall first check the fairness of the delivery (all modes of No ball except for the bowler using an Illegal Bowling Action). If the delivery was not a fair delivery the third umpire shall indicate that the batsman is Not out and advise the on-field umpire to signal No ball. See also paragraph D.6 below.
- D.2.4. Additionally, if the third umpire finds the batsman is Out by another mode of dismissal (excluding LBW), or Not out by any mode of dismissal (excluding LBW), they shall notify the on-field umpire so that the correct decision is made.

- D.2.5. If the third umpire decides the batter is out a red light is displayed; a green light means Not-out. Should the third umpire be temporarily unable to respond, a white light (where available) will remain illuminated throughout the period of interruption to signify to the on-field umpires that Umpire Reviews are temporarily unavailable, in which case the decision will be made by the on-field umpire. As an alternative to the red/green light system and where available, the big replay screen may be used for the purpose of conveying the third umpire's decision.

### **D.3. Caught Decisions, Obstructing the Field**

- D.3.1. Where the bowler's end umpire is unable to decide upon a Fair Catch or a Bump Ball, or if, on appeal from the fielding side, the batsman obstructed the field, they shall first consult with the striker's end umpire.
- D.3.2. Should both on-field umpires require assistance from the third umpire to make a decision, the bowler's end umpire shall firstly take a decision on-field after consulting with the striker's end umpire, before consulting by two-way radio with the third umpire. Such consultation shall be initiated by the bowler's end umpire to the third umpire by making the shape of a TV screen with their hands, followed by a Soft Signal of Out or Not out made with the hands close to the chest at chest height. If the third umpire advises that the replay evidence is inconclusive, the on-field decision communicated at the start of the consultation process shall stand.
- D.3.3. The third umpire shall determine whether the batsman has been caught, whether the delivery was a Bump Ball, or if the batsman obstructed the field. However, in reviewing the television replay(s), the third umpire shall first check the fairness of the delivery for all decisions involving a catch (all modes of No ball except for the bowler using an Illegal Bowling Action) and whether the batsman has hit the ball. If the delivery was not a fair delivery or if it is clear to the third umpire that the batsman did not hit the ball they shall indicate to the bowler's end umpire that the batsman is Not out caught, and in the case of an unfair delivery, advise the bowler's end umpire to signal No ball. See also paragraph D.6.below. Additionally, if it is clear to the third umpire that the batsman is Out by another mode of dismissal (excluding LBW), or Not out by any mode of dismissal (excluding LBW), they shall notify the bowler's end umpire so that the correct decision can be made.



D.3.4. The third umpire shall communicate their decision as set out in paragraph D.2.5.

#### **D.4. Boundary Decisions**

D.4.1. The bowler's end umpire shall be entitled to refer to the third umpire for a decision on:

D.4.1.1. whether a four or six has been scored;

D.4.1.2. whether a fielder had any part of his person in contact with the ball when he touched the boundary; or

D.4.1.3. whether the fielder had any part of his person in contact with the ball when he had any part of his person grounded beyond the boundary.

D.4.2. A decision shall be made immediately and cannot be changed thereafter.

D.4.3. If the television evidence is inconclusive as to whether or not a boundary has been scored, the default presumption shall be in favour of no boundary being awarded.

D.4.4. Where the bowler's end umpire wishes to use the assistance of the third umpire in this circumstance, they shall communicate with the third umpire by use of a two-way radio and the third umpire shall convey his decision to the bowler's end umpire by the same method.

D.4.5. The third umpire may initiate contact with the on-field umpire by two-way radio if TV coverage shows a boundary line infringement or incident that appears not to have been acted upon by the on-field umpires.

#### **D.5. Batters running to the Same End**

D.5.1. In the event of both batters running to the same end and the umpires are uncertain over which batter made their ground first, the on-field umpire may consult with the third umpire.


D.5.2. An on-field umpire requiring the assistance of the third umpire in this circumstance shall communicate with the third umpire by two-way radio and they will convey the decision to the on-field umpire by this method.

## **D.6. No balls**


- D.6.1 If the umpires are uncertain as to the fairness of the delivery following a dismissal, either affecting the validity of the dismissal or which batsman is dismissed, they shall be entitled to request the batsman to delay leaving the field and to check the fairness of the delivery with the third umpire. Communication with the third umpire shall be by two-way radio.
- D.6.2 The third umpire shall check all modes of No ball except for the bowler using an Illegal Bowling Action. The third umpire shall apply clause 21.5 when deciding whether a No ball should have been called (and must therefore be satisfied that none of the three conditions in clause 21.5 have been met before calling a No ball).
- D.6.3 If the delivery was not a fair delivery, the bowler's end umpire shall indicate that the batsman is Not out and signal No ball (except in the case of a dismissal for obstructing the field, which may still be effected despite a No ball being called, in which case the bowler's end umpire shall indicate that the relevant batsman is Out and additionally call a No ball).
- D.6.4 If a No ball is called following the check by the third umpire, the batting side shall benefit from the reversal of the dismissal and the one run for the No ball, but shall not benefit from any runs that may subsequently have accrued from the delivery had the on-field umpire originally called a No ball. Where the batsmen crossed while the ball was in the air before being caught, the batsmen shall remain at the same ends as if the striker had been dismissed, but no runs shall be credited to the striker even if one (or more) runs were completed prior to the catch being taken.

## APPENDIX E

### The creases (Clause 7.1)




## The protected area markings (Clause 41.11)



## APPENDIX F

### The wickets (Clause 8)



## **APPENDIX G**

### **Over calculation guidance and tables (Clauses 12.11 to 12.14)**

- G.1.1. The scheduled hours in clause 12.10.1 assumes no adjustment or extension to the originally scheduled hours of play.
- G.1.2. On the final day always set aside the last hour of play (16 overs) and exclude from any calculations.
- G.1.3. The times used in these examples assumes a match where play was scheduled to start at 10:30am, and subsequently the last hour was to begin at 4:30pm.
- G.1.4. If the last hour of play commences after 4.30pm, the cessation time will be re-scheduled accordingly and remains the re-scheduled cessation time even if the minimum overs are completed before the rescheduled cessation time is reached.

#### **Example 1:**

80 overs completed at 4:32pm. Drinks are to be taken and play resumes at, say, 4:36pm. The re-scheduled cessation time is 5:36pm with a minimum of 16 overs to be bowled.

#### **Example 2:**

80 overs completed at 4:22pm, so play must continue until after 4:30pm. Drinks will then be taken at the completion of the over in progress at 4.30pm and play resumes at, say, 4:35pm. The re-scheduled cessation time is 5:35pm with a minimum of 16 overs to be bowled.

#### **Example 3:**

77 overs completed and an innings ends at 4:25pm. Deduct 2 overs for change of innings, therefore minimum 17 overs remaining for the day. Next innings commences at 4:35pm, with 1 further over to be completed before the last hour commences. At the start of the next over at, say, 4.39pm, last hour to commence and the re-scheduled cessation time is 5:39pm with a minimum of 16 overs to be bowled.

- G.1.5. In circumstances where there is a change of innings within 10 minutes of the scheduled last hour, where the innings ends in the:
  - G.1.5.1. 78th over, deduct 2 overs for the change of innings, commence the next innings after the 10 minute interval and the last hour will commence at the commencement of the next innings;

- G.1.5.2. 79th over at or prior to 4.26pm, the last hour is deemed to commence at 4.30pm and the scheduled cessation time will remain at 5.30pm;
- G.1.5.3. 79th over at or after 4.27pm, the last hour is deemed to commence 4 minutes after the end of the innings and the next innings is to commence after the 10 minute interval. The rescheduled cessation time will be 56 minutes after the commencement of the next innings;
- G.1.5.4. 80th over at or prior to 4.30pm, the last hour will commence at 4.30pm and the scheduled cessation time will remain at 5.30pm;
- G.1.5.5. 80th over at or after 4.31pm, the last hour will commence at the time that the innings ended.
- G.1.6. Note the numbers in the table are in the following order:

**Play Resuming / Last Hour Commencing / Scheduled Cessation Time / Minimum Overs Remaining**

| Time End of Innings | Innings Ends 78th Over | Innings Ends 79th Over | Innings Ends 80th Over | Innings Ends 81st Over |
|---------------------|------------------------|------------------------|------------------------|------------------------|
| 4.20pm              | 4.30/4.30/5.30/16      | 4.30/4.30/5.30/16      | 4.30/4.30/5.30/16      | 4.30/4.30/5.30/16      |
| 4.21pm              | 4.31/4.31/5.31/16      | 4.31/4.31/5.31/16      | 4.31/4.31/5.31/16      | 4.31/4.31/5.31/16      |
| 4.22pm              | 4.32/4.32/5.32/16      | 4.32/4.30/5.30/16      | 4.32/4.30/5.30/16      | 4.32/4.30/5.30/16      |
| 4.23pm              | 4.33/4.33/5.33/16      | 4.33/4.30/5.30/16      | 4.33/4.30/5.30/16      | 4.33/4.30/5.30/16      |
| 4.24pm              | 4.34/4.34/5.34/16      | 4.34/4.30/5.30/15      | 4.34/4.30/5.30/15      | 4.34/4.30/5.30/15      |
| 4.25pm              | 4.35/4.35/5.35/16      | 4.35/4.30/5.30/15      | 4.35/4.30/5.30/15      | 4.35/4.30/5.30/15      |
| 4.26pm              | 4.36/4.36/5.36/16      | 4.36/4.30/5.30/15      | 4.36/4.30/5.30/15      | 4.36/4.30/5.30/15      |
| 4.27pm              | 4.37/4.37/5.37/16      | 4.37/4.31/5.31/15      | 4.37/4.30/5.30/15      | 4.37/4.30/5.30/15      |
| 4.28pm              | 4.38/4.38/5.38/16      | 4.38/4.32/5.32/15      | 4.38/4.30/5.30/14      | 4.38/4.30/5.30/14      |
| 4.29pm              | 4.39/4.39/5.39/16      | 4.39/4.33/5.33/15      | 4.39/4.30/5.30/14      | 4.39/4.30/5.30/14      |
| 4.30pm              | 4.40/4.40/5.40/16      | 4.40/4.34/5.34/15      | 4.40/4.30/5.30/14      | 4.40/4.30/5.30/14      |
| 4.31pm              | 4.41/4.41/5.41/16      | 4.41/4.35/5.35/15      | 4.31/4.31/5.31/14      |                        |
| 4.32pm              | 4.42/4.42/5.42/16      | 4.42/4.36/5.36/15      | 4.42/4.32/5.32/14      |                        |
| 4.33pm              | 4.43/4.43/5.43/16      | 4.43/4.37/5.37/15      | 4.43/4.33/5.33/14      |                        |
| 4.34pm              | 4.44/4.44/5.44/16      | 4.44/4.38/5.38/15      | 4.44/4.34/5.34/14      |                        |
| 4.35pm              | 4.45/4.45/5.45/16      | 4.45/4.39/5.39/15      | 4.45/4.35/5.35/14      |                        |
| 4.36pm              | 4.46/4.46/5.46/16      | 4.46/4.40/5.40/15      | 4.46/4.36/5.36/14      |                        |
| 4.37pm              | 4.47/4.47/5.47/16      | 4.47/4.41/5.41/15      | 4.47/4.37/5.37/14      |                        |
| 4.38pm              | 4.48/4.48/5.48/16      | 4.48/4.42/5.42/15      | 4.48/4.38/5.38/14      |                        |
| 4.39pm              | 4.49/4.49/5.49/16      | 4.49/4.43/5.43/15      | 4.49/4.39/5.39/14      |                        |
| 4.40pm              | 4.50/4.50/5.50/16      | 4.50/4.44/5.44/15      | 4.50/4.40/5.40/14      |                        |

## APPENDIX H

### Australian Cricket Heat Policy

- H.1** The Australian Cricket Heat Policy (the Policy) applies to all Players, Player Support Personnel and Match Officials (collectively known as **Participants**) involved in any CA sanctioned competitions, including matches or training for such competitions (collectively known as **Elite Cricket**).

The aims of the AC Heat Policy are to:

- a. Ensure that there is a protocol that can be implemented when extreme (heat related) weather conditions are expected
- b. Introduce and implement an evidence-based Heat Stress Risk Index (HSRI) that provides an objective measure to indicate when heat stress management strategies and interventions should be implemented during CA sanctioned matches; and
- c. Outline and reinforce guidelines for heat management strategies to reduce the risk of heat illness incidents to participants

**For the sake of applicability to this set of Playing Conditions, the application sections have been reproduced below.**

**H.2 Match days**

- a) Pre-Match Medical Meeting
  - i. A real-time HSRI measure should be taken just prior to the Pre-Match Medical Meeting to determine the baseline measure for the match day; and



- II. Forecasted HSRI measures for each hour of the match day should also be taken.

The Match Event Manager or the **Medical Officials** (match day Medical Officer or physiotherapist) present at the match should communicate the real-time and forecasted HSRI measures at the Pre-Match Medical Meeting. If either, forecasted or real-time, HSRI for the match day is greater than 3 (see appendix H.4) then weather conditions must be monitored regularly throughout the match day (hourly) to determine if the Heat Stress Management Interventions outlined in appendix H.4 should apply.

- b) If at any time during the day the real-time HSRI is greater than 3 refer to appendix H.4.1. for the relevant Heat Stress Management Interventions
- c) If the forecasted and the real-time HSRI is 3 or less, no further Heat Stress Management Interventions are required for the remainder of the match; unless there is a change in weather conditions or concern is raised by the **Match Officials** (umpires or match referees) or Medical Officials at the match or by Cricket Australia. In this instance, further measures of the HSRI must be observed and the Heat Stress Management Interventions implemented if the HSRI is greater than 3.

### **H.3 Responsibility for Measuring and Implementing the HSRI**

- a) Matches
- i. The highest qualified Medical Official in attendance at match and the Match Event

Manager is responsible for calculating the HSRI.

- ii. The highest qualified Medical Official in attendance at Match and the Match Event Manager is responsible for collating and entering the data into the HSRI and making recommendations to the Match Referee and Match Officials (at Pre-Match Medical Meeting or in real-time during the match) based on the Heat Stress Management Interventions in section H.4.

#### **H.4 Heat Stress Risk Index Management Interventions**

**H.4.1** The HSRI rating outlines the Heat Stress Management Interventions to be considered for different heat-related weather conditions. In the instance that:

- a) **HSRI rating is between 0 to 3** (inclusive): no change to usual heat management strategies.
- b) **HSRI rating is between 4 to 7** (inclusive): heat management strategies and consider extra drinks breaks, in accordance with appendix H.4.2 (e.g. every 40 mins in First Class instead of every hour). Medical Officials should be extra vigilant in monitoring Participants that exhibit signs of heat stress illness such as excessive muscle cramping, dizziness, excessive fatigue etc.);
- c) **HSRI rating is between 8 to 10** (inclusive): extra drinks break's in accordance with item H.4.1 a) and b) above should be considered; and with potential that each drink's break should be extended in accordance with appendix H.4.2 (e.g. 15 mins instead of 5 mins) to allow

Players and Match Officials to leave the field of play if required;

- d) **HSRI rating is above 10:** all Heat Stress Management Interventions in accordance with items H.4.1 a) to c) applied and / or consideration to suspend the match in accordance with appendix H.4.3 until the HSRI is 10 or below. A meeting between Medical Officer (or highest qualified Medical Official), the Match Event Manager (if present) and Match Referee (or highest-ranking Match Official) to consider how Participants and Match Officials are responding to the Heat Stress Management Interventions and if the match should be suspended until conditions improve. The Match Referee and the Medical Officials are responsible for making any decision to suspend the match. If no agreement can be made the opinion of the CA SSSM Manager and/or the CA Head of Cricket Operations should be sought.
- e) If suspension has been agreed on, the Match Referee (or highest-ranking match official) responsible for the match confirms with the umpires that the match is at the suspension stage. The Match Referee is to contact CA (CA SSSM Manager, CA Head of Operations, or in their absence the CA Match Officials Manager) to inform them that the match has been suspended. Should all parties still agree, the umpires call a suspension.

**H.4.2** If any additional and/or extended drinks break/s impact on the time allocated to the fielding team to complete their overs, the Match Referee (or highest-ranking Match Official) will determine if time lost can be added later in the day / match in accordance with the relevant Cricket Australia Playing Conditions.

**H.4.3** If a determination is made to suspend a match, the Medical Officials and Match Event Manager are

responsible for monitoring the HSRI at regular intervals in real-time (such as when a match is suspended due to rain). Play should only resume when the Medical Officials, Match Event Manager and Match Referee (or highest-ranking Match Official) have unanimously determined that the HSRI indicates it is safe to resume the game (HSRI 10 or below) and the risk to Participants has been mitigated. The Match Referee (or highest-ranking Match Official) will determine when the match can resume or if time lost can be added later in the day or match in accordance with the relevant Cricket Australia Playing Conditions.

Note: Implementation of the Heat Stress Management Interventions must take a common-sense approach. In situations when Medical Officials, at Elite Cricket become concerned for Participants welfare due to heat they should consider implementing the strategies outlined in appendix H.4.1, regardless of the HSRI. Conversely, in circumstances where Participants are responding to the Heat Stress Management Interventions, Medical Officials and Match Officials may decide to adjust the Heat Stress Management Interventions (e.g. not suspend play if Players and Match Officials are responding well to additional and/or extended drinks breaks).

- H.4.4** If no data is available to calculate the HSRI, the Medical Official at the match must decide if players are likely to be at risk of heat stress illness and if the Heat Stress Management Interventions (outlined in H.4.1 b, c and d) apply. The Medical Official should then communicate with the Match Referee (or highest-ranking Match Official) the recommendations. The Match Referee (or highest- Match Official) and the Medical Officials are responsible for making any decision to suspend the match.

## **APPENDIX I**

### **COVID Illness Replacement**

#### **I.1 COVID-19**

I1.1 If during the course of the relevant match a player tests positive for COVID-19, displays COVID-19 symptoms, or is prevented from participating as a result of applicable COVID-19 public health guidance, a COVID-19 Replacement may be permitted in the following circumstances

I1.1.1 The positive test for COVID-19, symptoms of COVID-19 or public health guidance preventing participation is be formally confirmed by the Team Medical Representative and endorsed by an independent medical practitioner

#### **I.2 Activation of COVID-19 Replacement**

I2.1 The Team Medical Representative or Team Manager shall submit a COVID-19 Replacement Request to the Match Referee on a standard form which shall:

I2.1.1 Identify the relevant player

I2.1.2 Specify whether the player has tested positive for COVID-19, is displaying COVID-19 symptoms, or is prevented from participating as a result of applicable COVID-19 public health guidance; and

I2.1.3 Nominate a like-player to the opposing team captain (or coach if the opposing team captain is on the field of play) for approval (which must not be unreasonably withheld) as the COVID-19 Replacement for

that player for the remainder of the match concerned

- I2.2 Where approval is not provided by the opposing team captain as contemplated in I2.1.3 above, the Match Referee will make the final determination (in consultation with Cricket Australia) on whether to approve the nominated player as a Covid-19 replacement player
- I2.3 Once approved, the COVID-19 replacement may immediately participate in the match as a complete replacement player. To be clear, the COVID-19 replacement player is able to bat, bowl, keep wicket or field as though he was a member of the starting 11.
- I2.4 If at the time of activation the COVID-19 replacement is replacing a:
  - I2.4.1 player that has “retired not out” during his team’s current batting innings, the COVID-19 replacement may only bat in that innings (where possible) pursuant to clause 25 as though he was a batter returning to his innings; or

NOTE: For purposes of scoring the COVID-19 replacement will be entered as an additional batter and his innings will be considered separate to the innings of the replaced player (who will remain “Retired – Not Out”). However, the fielding side still only needs to take 10 wickets to complete the batting innings.

- I2.4.2 player that has “retired -not out” during his team’s previous batting innings and that batting innings has since concluded, the COVID-19

replacement may bat at any position in the batting order in that team's subsequent batting innings (if any); or

12.4.3 player from the fielding team, the COVID-19 replacement may enter play pursuant to clause 24 as though he was a member of the fielding side returning to play and without needing to serve any Penalty Time when entering the match.

**12.5** Once replaced by a COVID-19 replacement, a replaced player may take no further part in the match concerned.

**12.6** There is no maximum number of COVID-19 replacement players available in a particular match